



LORNAY
ENVIRONMENTAL CONSULTING

FINAL BASIC ASSESSMENT REPORT

**PROPOSED RESIDENTIAL DEVELOPMENT
ERF 1486 VERMONT, HERMANUS**

11 September 2026

Consultant:

Michelle Naylor | Env. Consultant | M.Sc., Pr. Sci. Nat., EAPASA
cell: 083 245 6556 | michelle@lornay.co.za | www.lornay.co.za
Unit 5/1F Hemel en Aarde Wine Village, Hermanus, 7200
Lornay Environmental Consulting Pty Ltd | Reg 2015/445417/07

DETAILS OF THE AUTHOR(S)

EAP ORGANISATION: Lornay Environmental Consulting (Pty) Ltd

AUTHOR (S): Michelle Naylor
Pr.Sci.Nat. 400327/13
EAPASA. 2019/698

Njabulo Magoswana
Cand. EAP. 2021/3178



BASIC ASSESSMENT REPORT

**THE NATIONAL ENVIRONMENTAL MANAGEMENT ACT, 1998 (ACT NO. 107 OF 1998) AND
THE ENVIRONMENTAL IMPACT ASSESSMENT REGULATIONS.**

NOVEMBER 2019

(For official use only)	
Pre-application Reference Number (if applicable):	
EIA Application Reference Number:	
NEAS Reference Number:	
Exemption Reference Number (if applicable):	
Date BAR received by Department:	
Date BAR received by Directorate:	
Date BAR received by Case Officer:	

GENERAL PROJECT DESCRIPTION

(This must Include an overview of the project including the Farm name/Portion/Erf number)

BASIC ASSESSMENT REPORT

PROPOSED RESIDENTIAL DEVELOPMENT — ERF 1486, VERMONT, HERMANUS

EXECUTIVE SUMMARY | May 2026

Applicant	Elephant Ventures Africa CC (Craig Saunders)
EAP	Michelle Naylor, Lornay Environmental Consulting (Pty) Ltd — EAPASA 2019/698
Property	Erf 1486, Vermont, Hermanus
Site area	15 079 m ² (1.507 ha)
Municipality	Overstrand Municipality
Region	DEA&DP Region 2 (Cape Winelands & Overberg District)
Application type	Basic Assessment — new submission (previous application withdrawn)
Preferred alternative	Alternative 4 (6 single residential erven, 1 private road, 1 open space erf)
Report date	11 September 2026 (Version 4)

1. Project Description and Context

Erf 1486 is located at the corner of the R43 and Lynx Avenue in the built-up residential suburb of Vermont, approximately 9 km west of Hermanus. The property is zoned Residential Zone I and is one of the last remaining large erven available for development within Vermont's established urban edge. The site is characterised by a mixture of partially transformed and ecologically sensitive areas, including a delineated Unchanneled Valley-Bottom (UVB) wetland covering approximately 0.90 ha (60%) of the 1,507-ha property.

The proposed development comprises the subdivision of Erf 1486 to create six single residential erven, one private internal access road, and one large open space erf (Erf 8) incorporating the entire delineated wetland. The total development footprint under the preferred Alternative 4 is approximately 5 709 m², with 9 361 m² (approximately 58% of the site) designated as protected private open space in perpetuity.

The site forms part of an Ecological Support Area (ESA2) as identified in the Western Cape Biodiversity Spatial Plan (WCBSP, 2017), linking the Hoek van der Berg Private Nature Reserve to the west with the Vermont Salt Pan to the east. The 2023 WCBSP further maps portions of the site as Critical Biodiversity Area 1 (CBA1: Terrestrial). The site falls within the Urban Conservation Environmental Management Overlay Zone (EMOZ Category D) as per the Overstrand Municipality's draft EMOZ.

2. Assessment Process and Public Participation

The assessment has been conducted under the NEMA EIA Regulations (2014, as amended) in terms of Chapter 5 of the National Environmental Management Act, 1998 (Act No. 107 of 1998). The previous application was formally withdrawn prior to final submission to allow for layout refinement, additional specialist input, and the resubmission of a new application incorporating the final preferred layout. This report constitutes the Final BAR submitted for the new application.

Five rounds of public participation have been conducted to date, spanning March 2023 to July 2026. The first three rounds were conducted on a pre-application, out-of-process basis, while the fourth and fifth rounds were conducted in-process, in terms of the current application, culminating in the finalisation of the preferred layout. A sixth round of public participation (PPP 6) has since been initiated, following a 50-day extension notice submitted to DEA&DP after the applicant was unable to meet the Final BAR submission due date of 7 September 2026, owing to additional information required for inclusion in the report.

Public Participation:

PPP Round 1 (Pre-application)	22 March 2023 – 24 April 2023
PPP Round 2 (Pre-application)	17 May 2024 – 17 June 2024
PPP Round 3 (In-process)	20 June 2025 – 23 July 2025
PPP Round 4 (In-process)	29 September 2025 – 29 October 2025
PPP Round 5 (In-process)	20 May 2026 – 20 July 2026
PPP Round 6 (In Process)	11 September 2026 – 11 October 2026

Organs of State consulted include DEA&DP, CapeNature, Overstrand Municipality, Overberg District Municipality, and BOCMA. All five organs of state responded. Cape Nature's formal support for the final preferred layout (Alternative 4, Revision 24, dated 25 September 2025) was confirmed by letter on 6 November 2025, subject to all conditions raised across the four rounds of participation remaining in effect.

3. Listed Activities

The following listed activities are triggered by the proposed development:

Listing Notice 1 (GN No. R983, 2014)

- Activity 12: Construction of infrastructure or structures with a physical footprint of 100 m² or more within or within 32 m of a watercourse — access road encroachment on seasonal wetland (approximately 240 m²) and gabion outlet structures positioned on the wetland edge.
- Activity 19: Infilling or depositing of material exceeding 10 m³ into a watercourse — access road construction involves infilling of approximately 240 m² of seasonal wetland. Rehabilitation of the wetland will also require removal of existing infill material.

Listing Notice 3 (GN No. R985, 2014)

- Activity 12: Clearance of 300 m² or more of indigenous vegetation within a critically endangered ecosystem — more than 300 m² of Hangklip Sand Fynbos will be cleared within a Critically Endangered vegetation type.
- Activity 14: Development of infrastructure with a footprint of 10 m² or more within a watercourse in a Critical Biodiversity Area or Ecological Support Area — access road encroachment on seasonal wetland within an ESA2 and CBA1 area.

The sewer pipeline upgrade (110 mm to 160 mm) in Kolgans and Malmok Roads does not trigger any additional listed activities, as the works are confined to existing transformed road reserves.

4. Site Characteristics and Environmental Sensitivities

Wetland

A natural UVB wetland occupying approximately 0.90 ha of the site was confirmed and delineated independently on three separate occasions (EnviroSwift 2018; Delta Ecology 2023; EnviroSwift/Steytler 2025). All three delineations are consistent with no material differences, endorsing the accuracy of the wetland boundary for planning purposes. The wetland is in a largely modified condition (Present Ecological State Category D, WET-Health v2.0), primarily as a result of historical infilling, excavation, alien vegetation infestation, and urban runoff. Despite this, it retains moderate Ecological Importance and Sensitivity (EIS) and forms an important hydrological link in a 1.4 km system connecting to the Vermont Salt Pan.

Terrestrial Vegetation

Approximately 70% of the site supports Hangklip Sand Fynbos, a Critically Endangered vegetation type (gazetted under NEM:BA). The vegetation is senescent, having not been subjected to fire for over 20 years. No plant Species of Conservation Concern (SoCC) were recorded during site surveys, although the presence of *Disa hallackii* (Endangered) cannot be excluded in low numbers.

Fauna

The Cape Dwarf Chameleon (*Bradypodion pumilum*, Near Threatened) has been recorded directly adjacent to the site and is considered likely to be present. Two Endangered bird species the African Marsh Harrier (*Circus ranivorus*) and Black Harrier (*Circus maurus*) may use the site for occasional foraging. Small mammals including Cape Grey Mongoose, Water Mongoose, and Cape Porcupine have been recorded. The site functions as part of the ESA2 ecological corridor facilitating ground-dwelling species movement between the nature reserve and the Vermont Salt Pan.

Biodiversity Planning Context

The site is mapped within ESA2 (WCBSP 2017) and partially within CBA1 Terrestrial (WCBSP 2023). The WCBSP 2023 guidelines indicate that CBA1 areas should be maintained in a natural or near-natural state. The EAP notes that the project was initiated and much of the specialist assessment was undertaken under the 2017 WCBSP (ESA2 designation) prior to the promulgation of the 2023 WCBSP update in December 2024.

5. Alternatives Assessed

Four layout alternatives and the No-Go option were assessed over the course of the impact assessment process. The evolution of the layout from Alternative 1 to Alternative 4 was directly driven by specialist input, organ of state comment, and public participation feedback particularly from Cape Nature, BOCMA, Overstrand Municipality, and Overberg District Municipality.

Alternative 1	12 residential erven, no open space. Complete loss of the wetland area. Ecological impact unacceptable. Not preferred.
Alternative 2	13 residential erven and road. Reduced wetland impact but still unacceptable encroachment into permanent and seasonal wetland. Not preferred.
Alternative 3 (previously preferred)	9 erven, two road erven, one open space erf. Significant reduction in wetland impact. Not supported by CapeNature due to residual encroachment of erven into seasonal wetland and enforceability concerns.
Alternative 4 (final preferred)	6 residential erven, 1 road erf, 1 open space erf. All residential erven positioned outside delineated wetland. Only unavoidable encroachment is access road (0.024 ha, 3% of wetland). Supported by CapeNature (6 November 2025).
No-Go	No development. Status quo maintained. Continued unmanaged disturbance, alien vegetation, and no formal wetland protection. Not preferred.

6. Preferred Alternative — Alternative 4

Alternative 4 provides for the following development components on a total site area of 15 070 m²:

Residential erven (Erven 1–6)	6 x single residential erven — total footprint approximately 4 253 m ²
Private access road (Erf 7)	One internal access road connecting to Lynx Avenue — approximately 1 456 m ²
Private open space (Erf 8)	Protected open space incorporating the entire wetland — approximately 9 361 m ² (58% of site)
Total development footprint	Approximately 5 709 m ²
Wetland encroachment	Approximately 0.024 ha (3%) — access road only; offset required

All residential erven are positioned outside the delineated permanent and seasonal wetland. The only remaining wetland encroachment is confined to the internal access road, which is unavoidable given site constraints and line-of-sight requirements at the R43/Lynx Avenue intersection. This encroachment is explicitly quantified and addressed through the Wetland Offset, Rehabilitation, and Management Plan.

The sewer line and stormwater swale have been repositioned to fall entirely outside the delineated wetland boundary, directly addressing concerns raised by CapeNature during the fourth round of public participation. The preferred stormwater option is the installation of 2 x 900 mm diameter culvert pipes to control runoff from the R43, connecting to an enhanced vegetated swale system north of the wetland.

7. Specialist Assessments and Impact Ratings

The following specialist studies were commissioned and informed the evolution of the layout:

- Wetland Screening and Delineation — EnviroSwift (2018)
- Aquatic Biodiversity Impact Assessment and Risk Matrix — Delta Ecology, Van Zyl et al. (2023, updated 2025)
- Independent Wetland Delineation Review — EnviroSwift/Steytler (August 2025)
- Terrestrial Botanical Impact Assessment and Addendum — Nick Helme Botanical Surveys (2023, addendum 2025)
- Terrestrial Animal Site Sensitivity Verification Report and Species Specialist Assessment — Jan Venter (2024)
- Stormwater Management Plan — DECA Consulting Engineers

- Wetland Offset, Rehabilitation and Management Plan — Delta Ecology, Van Zyl and Morton (2026, Version 2)
- Water and Sewer Line Alignment Report — Appendix F6a/b
- Services Capacity Report — GLS Consulting (Appendix K)
- Heritage Western Cape NID response — HWC confirmed no further heritage assessment required (Appendix F5)
- Phase 1 WULA Maintenance Management Plan — Appendix I

Residual Impact Ratings — Alternative 4 (Preferred)

Impact Theme	Pre-mitigation	Post-mitigation
Terrestrial vegetation loss (Hangklip Sand Fynbos)	High Negative	Low–Medium Negative
Wetland loss (access road only, 3% of wetland area)	Medium Negative	Low–Medium Negative (offset)
Faunal connectivity — Cape Dwarf Chameleon corridor	Medium	Low–Medium
Altered wetland flow regime	Low–Medium	Very Low (with SMP)
Water quality impairment	Low–Medium	Very Low (with SMP)
Dust and noise (construction)	High Negative	Very Low–Low Negative
Socio-economic: job creation and housing provision	—	High Positive

8. Wetland Offset, Rehabilitation, and Management Plan

The unavoidable loss of approximately 0.024–0.027 ha of seasonal wetland (3% of the 0.90 ha UVB wetland) due to access road construction has been assessed and quantified using the Macfarlane et al. (2016) Wetland Offset Calculator. The calculation applies the upper precautionary figure of 0.027 ha.

Wetland area lost	0.027 ha
Function loss (HE)	0.0157 HE
Habitat loss (HE)	0.1985 HE
Offset area (remaining wetland)	0.9361 ha
Function gain through rehabilitation (HE)	0.1173 HE
Habitat gain through rehabilitation (HE)	1.0025 HE
Net function surplus (HE)	0.1016 HE
Net habitat surplus (HE)	0.8041 HE
Offset target PES	Upper Category C (minimum PES score 79%)

Current PES

Category D (largely modified)

The calculation confirms a net surplus in both ecological function and habitat terms following rehabilitation, indicating that the proposed offset exceeds the ecological loss associated with the development.

Key rehabilitation interventions comprise: removal of all foreign fill material and rubble, to be undertaken during the summer months; reshaping of the wetland to restore characteristic UVB slope profiles, including a central basin gradient of 0–1%; removal of alien invasive vegetation (pampas grass, Kikuyu, Port Jackson and Rooikrans); revegetation using a minimum of six locally indigenous wetland species at a planting density of four plants per square metre, targeting 80% vegetation cover within 8 to 12 months; and full implementation of the stormwater management measures set out in the Stormwater Management Plan.

The long-term protection of the offset area will be secured through registration of a conservation servitude 0.9361 ha offset wetland area as a title deed restriction, to be registered within six months of the issuance of Water Use Authorisation. This legal instrument will be complemented operationally by a council-approved **Co-Management Agreement** between the Overstrand Municipality and the Homeowners Association (HoA), as recommended by Cape Nature. Further engagement is to be undertaken with CapeNature, the Overstrand Municipality, and the Breede Olifants Catchment Management Agency (BOCMA) to formalise this co-management agreement, including securing the requisite Council approval and confirming the respective roles and responsibilities of the Municipality and the HoA in the long-term management of the offset site.

The appointed freshwater specialist (Delta Ecology) has concluded that the proposed offset is practically implementable and will result in substantial biodiversity gains relative to the current, degraded condition of the wetland, and supports approval of the development subject to implementation of the Wetland Offset, Rehabilitation and Management Plan as a condition of authorisation.

9. Municipal Services and Infrastructure

The Overstrand Municipality has confirmed sufficient spare, unallocated capacity for all services (Appendix K):

- Water: supply via existing 200 mm pipeline in Lynx Avenue from the Preekstoel Water Treatment Plant. No network upgrades required.
- Sewer: sufficient hydraulic capacity downstream. The existing 110 mm pipeline in Kolgans and Malmok Roads requires upgrading to 160 mm to accommodate the development. This upgrade takes place entirely within existing transformed road reserves and does not trigger additional listed activities.
- Electricity: connection to the existing municipal network in accordance with Overstrand Municipality specifications.
- Stormwater: comprehensive Stormwater Management Plan prepared. Post-development peak flows at the Lynx Avenue culvert increase marginally (Q100: 3.211 m³/s vs 3.107 m³/s pre-

development). The Low Impact Development measures (permeable paving and enhanced swale system) reduce this back to pre-development levels.

10. Long-Term Environmental Management and Governance

The long-term protection and management of the wetland, open space, and No-Go areas on Erf 1486 will be secured through a layered set of reinforcing legal, financial, and institutional mechanisms, rather than reliance on any single instrument:

- The retained wetland and open space area will be secured through a council-approved co-management agreement between the Overstrand Municipality and the Developer and / or future Homeowners Association (HoA), providing formal institutional standing for the area's long-term protection and management.
- A legally constituted HoA must be established prior to the transfer of any residential erven. The HoA constitution will include binding provisions for wetland protection, alien vegetation clearing, stormwater infrastructure maintenance, and enforcement of No-Go area restrictions, applicable to all current and future property owners.
- A dedicated environmental levy, collected through the HoA, will fund wetland rehabilitation activities, ongoing monitoring, alien vegetation clearance, and the appointment of ecological specialists where required.
- Five-yearly independent environmental audits will be undertaken using the WET-Health Version 2.0 methodology, to verify the ecological condition and management effectiveness of the retained wetland area over time.
- All fencing along the wetland boundary must be permeable, to facilitate faunal movement across the site; solid boundary walls are prohibited within the wetland area.

11. Key Recommended Conditions of Authorisation

- Full implementation of the Wetland Offset, Rehabilitation, and Management Plan (Appendix F8) as a condition of approval.
- All residential erven and associated infrastructure to remain outside the delineated permanent and seasonal wetland. No-Go areas must be fenced off before any vegetation clearance or construction commences.
- All dwellings to be raised a minimum of 1.0 m above wetland level. Raft foundations required to reduce subsurface flow impacts.
- Full implementation of the Stormwater Management Plan, including permeable paving, enhanced swale system, and rainwater harvesting tanks.
- Pre-construction nighttime Search and Rescue for faunal species — mandatory prior to any ground works. Sheraine van Wyk (Whale Coast Conservation) to be contracted for chameleon search and rescue.
- Search and Rescue for plant SoCC (including potential *Disa hallackii*) must be implemented prior to vegetation clearance.
- Establishment of the HoA, with approved constitution incorporating all environmental obligations, prior to transfer of any erf.

- Environmental Control Officer (ECO) to be appointed during construction; bi-weekly site visits initially, reducing once development areas are adequately defined.
- Use of herbicides, pesticides, and poisons in private gardens is strictly prohibited. The HoA is responsible for enforcement.
- Supplementary information regarding the wetland offset mechanism and proposed servitude holder to be submitted to DEA&DP with the final application, with a copy to Cape Nature.

12. EAP Opinion and Recommendation

The EAP recommends that Environmental Authorisation be granted for Alternative 4, subject to the conditions outlined above, including the following:

- Implementation of a Wetland Offset, Rehabilitation and Management Plan (WORMP), with clear method statements for construction-phase wetland protection and post-construction maintenance;
- Formal, legally enforceable protection of the retained open space and wetland area (approximately 9,361 m²) as a no-go zone during both the construction and operational phases; and
- Securing of the retained wetland area and associated open space through a council-approved co-management agreement between the Overstrand Municipality and the Homeowners' Association (HOA), providing the necessary long-term institutional and legal standing for the offset area's protection, management and maintenance beyond the development's construction phase.

The mitigation hierarchy has been applied throughout the iterative design process, resulting in a layout that avoids all permanent and seasonal wetland areas for residential erven, minimises unavoidable encroachment to access infrastructure only, and provides for formal, legally enforceable conservation of more than 58% of the site in perpetuity. The findings are based on various specialists since 2018 until 2026.

The wetland delineation informing this layout is founded on a consistent and independently corroborated body of specialist work undertaken over an extended period, rather than a single assessment. An initial delineation was undertaken by Joshua Gericke/EnviroSwift in 2018, followed by an aquatic biodiversity assessment and wetland delineation by Delta Ecology (Kimberley van Zyl, 2023), subsequently updated in 2025/2026. This delineation was independently peer-reviewed by EnviroSwift (Nick Steytler, 2025), which confirmed no material discrepancy between the two datasets. Kimberley van Zyl (Delta Ecology) has, in a formal motivation letter dated 6 September 2026 (Appendix E), confirmed that she stands by the delineation presented in the Aquatic Biodiversity Impact Assessment: Erf 1486, Vermont (V5.0, 2026) and the Wetland Offset, Rehabilitation and Management Plan: Erf 1486, Vermont (V2.0, 2026), both prepared by Delta Ecology. The motivation confirms that while the Delta Ecology delineation differs slightly from the EnviroSwift delineations of 2018 and 2025 in the precise positioning of wetland boundaries, all three assessments are broadly consistent in overall wetland extent and configuration, and were undertaken independently by three SACNASP-registered scientists over a number of years. The

Freshwater Consulting (2026) delineation, by contrast, differs materially from all three of these consistent, independently derived assessments.

The Delta Ecology delineation was undertaken in accordance with the field-based methodology described in the Manual for the Identification and Delineation of Wetlands and Riparian Areas (DWAF, 2008), based on the interpretation of wetland indicators observed during the site assessment, including terrain position, soil form, soil wetness and vegetation, and reflects the wetland extent supported by the field evidence present at the time of assessment. As confirmed in the specialist's motivation, a wetland delineation is required to reflect the extent supported by field indicators and site conditions at the time of assessment, rather than a hypothetical future extent based on anticipated changes in catchment land use or vegetation cover. While it is recognised that wetland delineation involves professional interpretation and that differences in professional opinion may arise between specialists, the compiling specialist has, having considered the available information and the findings of the assessments undertaken to date, confirmed that she remains confident in, and stands by the delineation presented in the Delta Ecology reports informing this application.

Alternative 4 has been specifically supported by CapeNature (6 November 2025), BOCMA, the Overstrand Municipality, and the Overberg District Municipality. The botanical, freshwater, and faunal specialists all confirm that the residual impacts of Alternative 4 are acceptable, with post-mitigation ratings at Low–Medium Negative across all significant environmental impact categories.

The proposed development aligns with the Overstrand SDF, the Overstrand IDP (2023/2024), and the PSDF objectives for infill densification within established urban edges. Erf 1486 represents one of the last remaining development opportunities within the Vermont urban edge and, importantly, offers a structured vehicle for securing the long-term rehabilitation and formal protection of the onsite wetland an outcome that cannot be reliably achieved under the No-Go scenario in the absence of funded management obligations.

IMPORTANT INFORMATION TO BE READ PRIOR TO COMPLETING THIS BASIC ASSESSMENT REPORT

1. **The purpose** of this template is to provide a format for the Basic Assessment report as set out in Appendix 1 of the National Environmental Management Act, 1998 (Act No. 107 of 1998) ("NEMA"), Environmental Impact Assessment ("EIA") Regulations, 2014 (as amended) in order to ultimately obtain Environmental Authorisation.
2. The Environmental Impact Assessment ("EIA") Regulations is defined in terms of Chapter 5 of the National Environmental Management Act, 1998 (Act No. 107 of 1998) ("NEMA") hereinafter referred to as the "NEMA EIA Regulations".
3. The required information must be typed within the spaces provided in this Basic Assessment Report ("BAR"). The sizes of the spaces provided are not necessarily indicative of the amount of information to be provided.
4. All applicable sections of this BAR must be completed.
5. Unless protected by law, all information contained in, and attached to this BAR, will become public information on receipt by the Competent Authority. If information is not submitted with this BAR

due to such information being protected by law, the applicant and/or Environmental Assessment Practitioner ("EAP") must declare such non-disclosure and provide the reasons for believing that the information is protected.

6. This BAR is current as of **November 2019**. It is the responsibility of the Applicant/ EAP to ascertain whether subsequent versions of the BAR have been released by the Department. Visit this Department's website at <http://www.westerncape.gov.za/eadp> to check for the latest version of this BAR.
7. This BAR is the standard format, which must be used in all instances when preparing a BAR for Basic Assessment applications for an environmental authorisation in terms of the NEMA EIA Regulations when the Western Cape Government Department of Environmental Affairs and Development Planning ("DEA&DP") is the Competent Authority.
8. Unless otherwise indicated by the Department, one hard copy and one electronic copy of this BAR must be submitted to the Department at the postal address given below or by delivery thereof to the Registry Office of the Department. Reasonable access to copies of this Report must be provided to the relevant Organs of State for consultation purposes, which may, if so indicated by the Department, include providing a printed copy to a specific Organ of State.
9. This BAR must be duly dated and originally signed by the Applicant, EAP (if applicable) and Specialist(s) and must be submitted to the Department at the details provided below.
10. The Department's latest Circulars pertaining to the "One Environmental Management System" and the EIA Regulations, any subsequent Circulars, and guidelines must be taken into account when completing this BAR.
11. Should a water use licence application be required in terms of the National Water Act, 1998 (Act No. 36 of 1998) ("NWA"), the "One Environmental System" is applicable, specifically in terms of the synchronisation of the consideration of the application in terms of the NEMA and the NWA. Refer to this Department's Circular EADP 0028/2014: One Environmental Management System.
12. Where Section 38 of the National Heritage Resources Act, 1999 (Act No. 25 of 1999) ("NHRA") is triggered, a copy of Heritage Western Cape's final comment must be attached to the BAR.
13. The Screening Tool developed by the National Department of Environmental Affairs must be used to generate a screening report. Please use the Screening Tool link <https://screening.environment.gov.za/screeningtool> to generate the Screening Tool Report. The screening tool report must be attached to this BAR.
14. Where this Department is also identified as the Licencing Authority to decide on applications under the National Environmental Management: Air Quality Act (Act No. 29 of 2004) ("NEM:AQA"), the submission of the Report must also be made as follows, for-
Waste Management Licence Applications, this report must also (i.e., another hard copy and electronic copy) be submitted for the attention of the Department's Waste Management Directorate (Tel: 021-483-2728/2705 and Fax: 021-483-4425) at the same postal address as the Cape Town Office.

Atmospheric Emissions Licence Applications, this report must also be (i.e., another hard copy and electronic copy) submitted for the attention of the Licensing Authority or this Department's Air Quality Management Directorate (Tel: 021 483 2888 and Fax: 021 483 4368) at the same postal address as the Cape Town Office.

DEPARTMENTAL DETAILS

CAPE TOWN OFFICE: REGION 1 and REGION 2 (Region 1: City of Cape Town, West Coast District) (Region 2: Cape Winelands District & Overberg District)	GEORGE OFFICE: REGION 3 (Central Karoo District & Garden Route District)
BAR must be sent to the following details: Western Cape Government Department of Environmental Affairs and Development Planning Attention: Directorate: Development Management (Region 1 or 2) Private Bag X 9086 Cape Town, 8000 Registry Office 1st Floor Utilitas Building 1 Dorp Street, Cape Town Queries should be directed to the Directorate: Development Management (Region 1 and 2) at: Tel: (021) 483-5829 Fax (021) 483-4372	BAR must be sent to the following details: Western Cape Government Department of Environmental Affairs and Development Planning Attention: Directorate: Development Management (Region 3) Private Bag X 6509 George, 6530 Registry Office 4th Floor, York Park Building 93 York Street George Queries should be directed to the Directorate: Development Management (Region 3) at: Tel: (044) 805-8600 Fax (044) 805 8650

MAPS

Provide a location map (see below) as Appendix A1 to this BAR that shows the location of the proposed development and associated structures and infrastructure on the property.	
Locality Map:	The scale of the locality map must be at least 1:50 000. For linear activities or development proposals of more than 25 kilometres, a smaller scale e.g., 1:250 000 can be used. The scale must be indicated on the map. The map must indicate the following: • an accurate indication of the project site position as well as the positions of the alternative sites, if any; • road names or numbers of all the major roads as well as the roads that provide access to the site(s) • a north arrow; • a legend; and • a linear scale. For ocean based or aquatic activity, the coordinates must be provided within which the activity is to be undertaken and a map at an appropriate scale clearly indicating the area within which the activity is to be undertaken. Where comment from the Western Cape Government: Transport and Public Works is required, a map illustrating the properties (owned by the Western Cape Government: Transport and Public Works) that will be affected by the proposed development must be included in the Report.
Site Plan:	Detailed site development plan(s) must be prepared for each alternative site or alternative activity. The site plans must contain or conform to the following: • The detailed site plan must preferably be at a scale of 1:500 or at an appropriate scale. The scale must be clearly indicated on the plan, preferably together with a linear scale. • The property boundaries and numbers of all the properties within 50m of the site must be indicated on the site plan. • On land where the property has not been defined, the co-ordinates of the area in which the proposed activity or development is proposed must be provided.

	- The current land use (not zoning) as well as the land use zoning of each of the adjoining properties must be clearly indicated on the site plan. - The position of each component of the proposed activity or development as well as any other structures on the site must be indicated on the site plan. - Services, including electricity supply cables (indicate aboveground or underground), water supply pipelines, boreholes, sewage pipelines, storm water infrastructure and access roads that will form part of the proposed development must be clearly indicated on the site plan. - Servitudes and an indication of the purpose of each servitude must be indicated on the site plan. - Sensitive environmental elements within 100m of the site must be included on the site plan, including (but not limited to): - Watercourses / Rivers / Wetlands - Flood lines (i.e., 1:100 year, 1:50 year and 1:10 year where applicable); - Coastal Risk Zones as delineated for the Western Cape by the Department of Environmental Affairs and Development Planning ("DEA&DP"); - Ridges; - Cultural and historical features/landscapes; - Areas with indigenous vegetation (even if degraded or infested with alien species). - Whenever the slope of the site exceeds 1:10, a contour map of the site must be submitted. - North arrow A map/site plan must also be provided at an appropriate scale, which superimposes the proposed development and its associated structures and infrastructure on the environmental sensitivities of the preferred and alternative sites indicating any areas that should be avoided, including buffer areas.
Site photographs	Colour photographs of the site that shows the overall condition of the site and its surroundings (taken on the site and taken from outside the site) with a description of each photograph. The vantage points from which the photographs were taken must be indicated on the site plan, or locality plan as applicable. If available, please also provide a recent aerial photograph. Photographs must be attached to this BAR as Appendix C. The aerial photograph(s) should be supplemented with additional photographs of relevant features on the site. Date of photographs must be included. Please note that the above requirements must be duplicated for all alternative sites.
Biodiversity Overlay Map:	A map of the relevant biodiversity information and conditions must be provided as an overlay map on the property/site plan. The Map must be attached to this BAR as Appendix D.
Linear activities or development and multiple properties	GPS co-ordinates must be provided in degrees, minutes and seconds using the Hartebeeshoek 94 WGS84 co-ordinate system. Where numerous properties/sites are involved (linear activities) you must attach a list of the Farm Name(s)/Portion(s)/Erf number(s) to this BAR as an Appendix. For linear activities that are longer than 500m, please provide a map with the co-ordinates taken every 100m along the route to this BAR as Appendix A3.

ACRONYMS

DAFF:	Department of Forestry and Fisheries
DEA:	Department of Environmental Affairs
DEA& DP:	Department of Environmental Affairs and Development Planning
DHS:	Department of Human Settlement
DoA:	Department of Agriculture
DoH:	Department of Health
DWS:	Department of Water and Sanitation
EMPr:	Environmental Management Programme
HWC:	Heritage Western Cape
NFEPA:	National Freshwater Ecosystem Protection Assessment
NSBA:	National Spatial Biodiversity Assessment
TOR:	Terms of Reference
WCBSP:	Western Cape Biodiversity Spatial Plan
WCG:	Western Cape Government

ATTACHMENTS

Note: The Appendices must be attached to the BAR as per the list below. Please use a ✓ (tick) or a x (cross) to indicate whether the Appendix is attached to the BAR.

The following checklist of attachments must be completed.

APPENDIX			(Tick) or x (cross)
Appendix A:	Maps		
	Appendix A1:	Locality Map	✓
	Appendix A2:	Coastal Risk Zones as delineated in terms of ICMA for the Western Cape by the Department of Environmental Affairs and Development Planning	
	Appendix A3:	Map with the GPS co-ordinates for linear activities	
Appendix B:	Appendix B:	Site development plan(s)	✓
	Appendix B	A map of appropriate scale, which superimposes the proposed development and its associated structures and infrastructure on the environmental sensitivities of the preferred site, indicating any areas that should be avoided, including buffer areas;	
Appendix C:	Photographs		✓
Appendix D:	Biodiversity overlay map		✓
Appendix :	Permit(s) / license(s) / exemption notice, agreements, comments from State Department/Organs of state and service letters from the municipality.		
	Appendix E:	Proof of PPP	
		Copy of comment from Cape Nature	SEE APPENDIX E
		Final Comment from BOCMA	SEE APPENDIX E
		Comment from the DEA: Oceans and Coast	N/A
		Comment from the DAFF	N/A
		Comment from WCG: DHS	N/A
		Comment from WCG: DoH	N/A

		Comment from DEA&DP: Pollution Management	N/A
		Comment from DEA&DP: Waste Management	N/A
		Comment from DEA&DP: Biodiversity	N/A
		Comment from the local authority	See Appendix E
		Comment from the District Municipality	See Appendix E
	Appendix E21:	Proof of land use rights	N/A
	Appendix E22:	Proof of public participation agreement for linear activities	N/A
Appendix E:	Public participation information: including a copy of the register of I&APs, the comments and responses Report, proof of notices, advertisements and any other public participation information as is required.		✓
Appendix F:	Specialist Report(s) APPENDIX F1: ENVIROSWIFT Freshwater Screening APPENDIX F2a: Aquatic Biodiversity Impact Assessment APPENDIX F2b: Risk Assessment Matrix Report APPENDIX F3: Botanical Impact Assessment APPENDIX F4: Botanical comment for Alternative 4 APPENDIX F5: Heritage Western Cape Comment APPENDIX F6a: Water and Sewer Line Alignment APPENDIX F6b: Services Report APPENDIX F7: Stormwater Management Plan APPENDIX F8: Wetland Offset, Rehabilitation and Management Plan APPENDIX F9a: Terrestrial Animal Site Sensitivity Verification Report and Species Specialist Assessment Report APPENDIX F9b: Terrestrial Animal Site Sensitivity Verification Report and Species Specialist Assessment Report Addendum. APPENDIX F10: Review Wetland Delineation		✓
Appendix G:	APPENDIX G1: EMPr APPENDIX G2: Regulated Areas Management Plan		✓
Appendix H:	APP H1: Screening tool report APP H2: SSVR		✓
Appendix I:	APP Ia Maintenance Management Plan APP Ib MMP Form		✓
Appendix J:	Historical Approval		✓
Appendix K:	Service letter from the Municipality		✓
Appendix L:	WULA		✓

SECTION A: ADMINISTRATIVE DETAILS

Highlight the Departmental Region in which the intended application will fall	CAPE TOWN OFFICE:		GEORGE OFFICE:
	REGION 1 (City of Cape Town, West Coast District)	REGION 2 (Cape Winelands District & Overberg District)	REGION 3 (Central Karoo District & Garden Route District)
Duplicate this section where there is more than one Proponent Name of Applicant/Proponent: Name of contact person for Applicant/Proponent (if other): Company/ Trading name/State Department/Organ of State: Company Registration Number: Postal address: Telephone: E-mail:	Elephant Ventures Africa cc		
	Craig Saunders		
	Elephant Ventures Africa CC		
	1999/013536/23		
	224 Cherrywood Street		
	Arabella Kleinmond		Postal code: 7195
			Cell: 083 306 3770
	babyjumbo@mweb.co.za		Fax: ()
	Lornay Environmental Consulting		
	Michelle Naylor		
Unit 5/1 F, Hemel and Aarde Wine Village, Hermanus			
Hermanus		Postal code: 7200	
083 245 6556		Cell:	
michelle@lornay.co.za		Fax: ()	
Master of Science (Rhodes University)			
EAPASA. 2019/698, SACNASP., IAIASA			
Duplicate this section where there is more than one landowner Name of landowner: Name of contact person for landowner (if other): Postal address: Telephone: E-mail:	As above		
	-		
	-		
	-		Postal code:-
	-		Cell:-
	-		Fax: -
	-		
Name of Person in control of the land: Name of contact person for person in control of the land: Postal address: Telephone: E-mail:	As above		
	-		
	-		
	-		Postal code:-
	-		Cell:-
	-		Fax: -
	-		
Duplicate this section where there is more than one Municipal Jurisdiction	Overstrand Municipality		

Municipality in whose area of jurisdiction the proposed activity will fall:			
Contact person:	Penelope Aplon		
Postal address:	PO Box 20		
	Hermanus	Postal code: 7200	
Telephone	028 313 8000	Cell:	
E-mail:	paplon@overstrand.gov.za	Fax: ()	

SECTION B: CONFIRMATION OF SPECIFIC PROJECT DETAILS AS INCLUDED IN THE APPLICATION FORM

1.	Is the proposed development (please tick):	New	☒	Expansion	
2.	Is the proposed site(s) a brownfield of greenfield site? Please explain.				
The proposed development site, Erf 1486, is located within the built-up suburb of Vermont, Hermanus, in the Western Cape. The site falls within the Overstrand Municipality's urban edge and is adjacent to existing residential infrastructure to the south. The property exhibits a mosaic of both transformed (brownfield) and relatively intact (greenfield) areas, making it best described as a partially transformed site. According to the Botanical Impact Assessment (Helme, 2023), the site supports remnants of Critically Endangered Hangklip Sand Fynbos, with varying levels of ecological integrity. Approximately 60% of the site consists of a delineated Unchanneled Valley-Bottom (UVB) wetland, although portions of this system have been ecologically degraded by historical excavation and fill activities and the spread of alien species, such as <i>Cenchrus clandestinus</i> (kikuyu grass) and <i>Cortaderia selloana</i> (pampas grass). Despite this, the wetland remains functionally important and hydrologically connected to the Vermont Salt Pan to the southeast, forming part of a broader ecological support area (ESA2) identified in the Western Cape Biodiversity Spatial Plan. The Faunal Assessment (Venter, 2024) confirms the presence of small mammals, amphibians, and bird species, as well as evidence of ecological connectivity between the former Hoek van der Berg Private Nature Reserve to the west and the Vermont Salt Pan. Notably, the wetland corridor is an active route for ground-dwelling species. Although no Species of Conservation Concern (SCC) were recorded during the field survey, the site may provide occasional foraging habitat for threatened animal species such as the Black Harrier (<i>Circus maurus</i>) and the African Marsh Harrier (<i>Circus ranivorus</i>). Additionally, the Cape Dwarf Chameleon (<i>Bradypodion pumilum</i>), listed as Near Threatened, may inhabit the area. Several previously disturbed areas on the property including the existing structures, access road, and southern edge exhibit characteristics typical of brownfield sites, with significant soil disturbance, alien vegetation, soil hardening and gardening activities evident. In contrast, other areas are intact, characterised by indigenous vegetation and some wetland zones with signs of ecological recovery.					



3.	For Linear activities or developments																		
3.1.	Provide the Farm(s)/Farm Portion(s)/Erf number(s) for all routes:																		
3.2.	Development footprint of the proposed development for all alternatives.											—m ²							
3.3.	Provide a description of the proposed development (e.g. for roads the length, width and width of the road reserve in the case of pipelines indicate the length and diameter) for all alternatives.																		
3.4.	Indicate how access to the proposed routes will be obtained for all alternatives.																		
3.5.	SG Digit codes of the Farms/Farm Portions/Erf numbers for all alternatives																		
3.6.	Starting point co-ordinates for all alternatives																		
	Latitude (S)	°										‘		"					
	Longitude (E)	°										‘		"					
	Middle-point co-ordinates for all alternatives																		
	Latitude (S)	°										‘		"					
	Longitude (E)	°										‘		"					

End point co-ordinates for all alternatives																																											
Latitude (S)		°	' "																																								
Longitude (E)		°	' "																																								
Note: For Linear activities or developments longer than 500m, a map indicating the co-ordinates for every 100m along the route must be attached to this BAR as Appendix A3.																																											
4.	Other developments																																										
4.1.	Property size(s) of all proposed site(s):	15079.9 m ² (1.5 ha)																																									
4.2.	Developed footprint of the existing facility and associated infrastructure (if applicable):	Existing building – 1800 m ² Existing road – 106 m ²																																									
4.3.	Development footprint of the proposed development and associated infrastructure size(s) for all alternatives: Final Preferred Alternative (Alternative 4):	Table 1: Development footprint of the proposed development and infrastructure size <table border="1"> <thead> <tr> <th>Erf</th> <th>Zoning</th> <th>Land Use</th> <th>Area</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>GR1</td> <td>Town Housing</td> <td>640m²</td> </tr> <tr> <td>2</td> <td>GR1</td> <td>Town Housing</td> <td>622m²</td> </tr> <tr> <td>3</td> <td>GR1</td> <td>Town Housing</td> <td>618m²</td> </tr> <tr> <td>4</td> <td>GR1</td> <td>Town Housing</td> <td>746m²</td> </tr> <tr> <td>5</td> <td>GR1</td> <td>Town Housing</td> <td>816m²</td> </tr> <tr> <td>6</td> <td>GR1</td> <td>Town Housing</td> <td>811m²</td> </tr> <tr> <td>7</td> <td>OS3</td> <td>Private Road</td> <td>1456m²</td> </tr> <tr> <td>8</td> <td>OS3</td> <td>Private Open Space</td> <td>9361m²</td> </tr> <tr> <td colspan="3">Total</td> <td>15070m²</td> </tr> </tbody> </table>		Erf	Zoning	Land Use	Area	1	GR1	Town Housing	640m ²	2	GR1	Town Housing	622m ²	3	GR1	Town Housing	618m ²	4	GR1	Town Housing	746m ²	5	GR1	Town Housing	816m ²	6	GR1	Town Housing	811m ²	7	OS3	Private Road	1456m ²	8	OS3	Private Open Space	9361m ²	Total			15070m²
Erf	Zoning	Land Use	Area																																								
1	GR1	Town Housing	640m ²																																								
2	GR1	Town Housing	622m ²																																								
3	GR1	Town Housing	618m ²																																								
4	GR1	Town Housing	746m ²																																								
5	GR1	Town Housing	816m ²																																								
6	GR1	Town Housing	811m ²																																								
7	OS3	Private Road	1456m ²																																								
8	OS3	Private Open Space	9361m ²																																								
Total			15070m²																																								
4.4.	Provide a detailed description of the proposed development and its associated infrastructure (This must include details of e.g. buildings, structures, infrastructure, storage facilities, sewage/effluent treatment and holding facilities).																																										

Background and Evolution of the Layout

The proposed development on Erf 1486, Vermont has been designed to provide residential opportunities while ensuring the long-term protection of the on-site wetland system and its ecological functioning. Following concerns raised by organs of state, particularly Cape Nature, as well as issues identified during previous rounds of the Public Participation Process (PPP), the original site development plan has undergone several refinements to address environmental sensitivities.

The previous preferred layout (Alternative 3) comprised twelve (12) erven, of which Erven 1–9 were intended for residential development, Erven 10–11 for access roads, and Erf 12 designated as no-development open space protected through a registered conservation servitude. Although portions of certain residential erven encroached into the seasonal wetland, these areas were identified as no-development zones and were to be protected through title deed restrictions and exclusion areas on private erven. However, Cape Nature following on from PPP 4, recommended that all encroachment into the seasonal wetland be excluded entirely from the site development plan, and that residential erven be repositioned to avoid the wetland system completely.

Changes to the Layout – Current Preferred Alternative (Alternative 4)

The current preferred layout (Alternative 4) fully addresses the concerns raised by commenting authorities. This alternative represents a refinement of previously assessed options (Alternatives 1–3) and results in a reduction in development intensity and an increase in protected open space with complete avoidance of the delineated wetland.

Alternative 4 provides for:

- A total of six (6) residential erven;
- One (1) internal access road (Erf 7); and
- A large open-space erf (Erf 8) designated as a no-development area.

All residential erven have been repositioned to avoid any encroachment into the seasonal wetland, thereby fully securing the wetland area and addressing key concerns raised during PPP. While limited encroachment of the access road into the seasonal wetland remains unavoidable, this impact has been accounted for in the Wetland Offset Rehabilitation and Management Plan, as recommended by the freshwater specialist.

The remainder of the property being the wetland (Erf 8) has increased in extent due to these layout changes and will be formally protected through a registered conservation servitude, ensuring long-term conservation and management of the wetland and associated buffer areas. Engagement with Nature Conservation authorities regarding this servitude is ongoing.

Development proposal

The proposed development entails the establishment of a residential development on Erf 1486, Vermont. The final preferred layout, Alternative 4, was informed by specialist input and public participation and was supported by the botanical, faunal, and freshwater specialists. This alternative represents the option with the least environmental impact, particularly with respect to maintaining ecological and hydrological connectivity across the site and to downstream systems, including the Vermont Salt Pan.

The layout incorporates a substantial open-space component that functions as an on-site wetland offset area. This open space will be protected in perpetuity through a conservation servitude registered against the title deed and managed by the Homeowners' Association (HOA).

The mitigation hierarchy has been applied throughout the design process, prioritising avoidance, followed by minimisation and management of environmental impacts. Rehabilitation measures will restore hydrological connectivity and enhance the ecological functioning of the wetland system.

The total development footprint under Alternative 4 is restricted to approximately **5 709 m²**, while approximately **9 361 m²** of the site will be retained as protected open space. This represents a substantial improvement compared to the previous preferred alternative.

Components of the Development

Residential Erven

- Six (6) erven will be developed for residential purposes.
- Total residential footprint approximately **4 253 m²**.

Private Road

- One internal access road will serve the residential erven and connect to Lynx Road to the east.
- Total road footprint: approximately **1 456 m²**.
- Erf 7: approximately 180 m × 8 m, including the road reserve.
- Erf 5 and Erf 6 access will be provided via an internal driveway, which will run between the two erven.

Open Space

- Total area: approximately **9 361 m²**.
- The open-space area includes the wetland and associated buffer zones.
- The open space will be secured through a council-approved co-management agreement between the Overstrand Municipality and the Homeowners' Association (HOA), providing the necessary long-term institutional and legal standing for the offset area's protection, management and maintenance beyond the development's construction phase.

Associated Infrastructure:

Electricity Supply

Electrical services will be supplied via a connection to the existing municipal electricity network. The installation will be done in line with the requirements and specifications of the Overstrand Municipality.

Water Supply

Potable water will be sourced from the Preekstoel Water Treatment Plant, via an existing 200 mm diameter pipeline located along Lynx Avenue. A new connection point will be established, and internal reticulation infrastructure will be constructed in accordance with municipal engineering standards. The Overstrand Municipality has confirmed sufficient capacity to accommodate the additional demand from the development (see attached **Appendix K**).

Sewer and Effluent Management

The proposed development will be connected to the municipal sewer system. Wastewater from all residential erven will be conveyed through:

- An existing sewer pipeline system off site of which a specific section of the outfall sewer in Malmok Crescent and Kolgans street, will be upgraded from 110 mm to 160 mm to accommodate the increased effluent load.
- The sewer line extension on site has been shifted to fall outside the wetland zone in the final preferred layout (Alternative 4).

Stormwater Management

A site-specific Stormwater Management Plan (SMP) has been developed for the proposed development to ensure that surface runoff is managed in an effective and sustainable manner. The plan seeks to mitigate potential negative impacts on the adjacent wetland system and its surrounding environment while ensuring that the development footprint itself remains adequately protected from flooding and erosion risks. The development site falls within a larger hydrological system, where runoff from Catchment Area 1 (CA1), situated north of the R43, drains downstream into Catchment Area 2 (CA2), which incorporates the proposed development site as well as the wetland. This hydrological connectivity highlights the importance of implementing appropriate stormwater interventions that not only address site-level impacts but also contribute to maintaining broader catchment functionality.

One of the primary interventions includes the installation of **2 x 900 mm diameter culvert pipes** (refer to Figure 3b). These culverts will convey stormwater from the R43 road culverts into a **Vegetated swale** that will be positioned north of the wetland, beyond the delineated wetland edge. The purpose of the swale is to provide a controlled pathway for stormwater flows from the culverts, while also enhancing water quality and attenuating velocities before the water eventually moves into the wetland. By slowing down the flow, encouraging infiltration, and allowing sediment and pollutants to settle out, the swale serves as both a conveyance and treatment feature within the stormwater system. This approach ensures that the wetland is not subjected to sudden or excessive inflows that could alter its hydrological balance.

To further support infiltration and flood attenuation, a **Permeable Paving System** will be incorporated along the private road situated south of the wetland, outside of the wetland edge. This system will capture and infiltrate runoff generated from hardened road surfaces into the subsurface. In doing so, the design reduces the volume and intensity of surface flows directed towards the wetland. The permeable paving solution also contributes to the long-term sustainability of the site by minimizing the risk of ponding or flooding in the southern portion of the property, where the building footprint is located.

In addition to these measures, the SMP makes provision for **three (3) outlet structures** that will regulate stormwater entry into the wetland system. Each outlet will be fitted with erosion control and litter-trapping measures to prevent sedimentation, scouring, and pollution of the sensitive wetland environment. The proposed outlet structures are as follows:

1. **Outlet 1:** Discharges stormwater originating from the mountain slopes north of the R43.
2. **Outlet 2:** for the permeable paving and stormwater in road
3. **Outlet 3:** Outlet for stormwater along road

All outlet structures will incorporate **gabion control measures**, designed to trap litter, dissipate flow energy, and stabilize the discharge points, thereby reducing the risk of erosion and sediment transport into the wetland.

To manage stormwater in the proposed development, Low Impact Development (LID) measures will be implemented:

Permeable Paving System (South of Wetland)

Designed to reduce surface runoff and promote infiltration:

- Surface Storage Depth: 50 mm
- Pavement Thickness: 80 mm
- Base Course Height: 400 mm (43% void ratio)
- Permeability (clogged): 360 mm/hr
- Outlet: 160 mm uPVC pipe
- Storage Volume: 140 m³

Enhanced Swale System (North of Wetland)

A vegetated swale to filter pollutants and slow runoff:

- Surface Storage Depth: 400 mm
- Swale Storage Depth: 750 mm
- Surface Slope: 0.5%
- Void Ratio: 0.43
- Vegetative Cover: 75%
- Conductivity: 120 mm/hr
- Storage Volume: 81 m³

Table 2: A summary of the development footprint and infrastructure sizes is provided below.




Figure 1a: Site development plan for the proposed development – Alternative 4.




Figure 1b: Site development plan showing the stormwater swale and stormwater outlets as well as the service infrastructure alignment.

4.5. Indicate how access to the proposed site(s) will be obtained for all alternatives.

Access to the subject property (Erf 1486, Vermont) is already established via an existing access point from Lynx Avenue, located along the eastern boundary of the property. The internal access road will originate from the existing entrance on site and extend northwards, providing vehicular access to the proposed residential erven located in the northern portion of the property. For the erven situated along the southern portion (Erf 5 and Erf 6), access will be provided via an internal driveway, which will run between the erven, in accordance with the layout and configuration of the southern boundary erven.




Figure 2: Location of the existing access road on the subject property.

4.6.	SG Digit code(s) of the proposed site(s) for all alternatives:	C	0	1	3	0	0	2	3	0	0	0	0	1	4	8	6	0	0	0	0	0
4.7.	Coordinates of the proposed site(s) for all alternatives:																					
	Latitude (S)								34°				24′				23.42″					
	Longitude (E)								19°				8′				52.57″					

SECTION C: LEGISLATION/POLICIES AND/OR GUIDELINES/PROTOCOLS

1. Exemption applied for in terms of the NEMA and the NEMA EIA Regulations

Has exemption been applied for in terms of the NEMA and the NEMA EIA Regulations. If yes, include a copy of the exemption notice in Appendix E18.	YES	NO x
---	-----	------

2. Is the following legislation applicable to the proposed activity or development.

The National Environmental Management: Integrated Coastal Management Act, 2008 (Act No. 24 of 2008) ("ICMA"). If yes, attach a copy of the comment from the relevant competent authority as Appendix E4 and the pre-approval for the reclamation of land as Appendix E19.	YES	NO x
The National Heritage Resources Act, 1999 (Act No. 25 of 1999) ("NHRA"). If yes, attach a copy of the comment from Heritage Western Cape as Appendix E1. A Notice of Intent has been submitted to HWC, and it was confirmed that no further heritage impact assessment is required for the proposed development of erf 1486 Vermont. See HWC comment attached as Appendix F5	YES x	NO
The National Water Act, 1998 (Act No. 36 of 1998) ("NWA"). If yes, attach a copy of the comment from the DWS as Appendix E3. Freshwater Specialist was appointed and risk matrix completed also completed. A Wate Use License Pre-Application was submitted. Proof of Submission is attached as Appendix L .	YES x	NO
The National Environmental Management: Air Quality Act, 2004 (Act No. 39 of 2004) ("NEM:AQA"). If yes, attach a copy of the comment from the relevant authorities as Appendix E13.	YES	NO X
The National Environmental Management Waste Act (Act No. 59 of 2008) ("NEM:WA")	YES	NO X
The National Environmental Management Biodiversity Act, 2004 (Act No. 10 of 2004 ("NEMBA"). The vegetation present onsite is Critically Endangered vegetation type. The development will only result in the loss of 500m ² of indigenous vegetation in areas mapped as high botanical sensitive.	YES x	NO
The National Environmental Management: Protected Areas Act, 2003 (Act No. 57 of 2003) ("NEMPAA").	YES	NO X
The Conservation of Agricultural Resources Act, 1983 (Act No. 43 of 1983). If yes, attach comment from the relevant competent authority as Appendix E5.	YES	NO X

3. Other legislation

List any other legislation that is applicable to the proposed activity or development.
-

4. Policies

Explain which policies were considered and how the proposed activity or development complies and responds to these policies.

The proposed development on Erf 1486, Vermont was assessed against applicable provincial and municipal spatial planning policies to ensure alignment with strategic objectives for sustainable settlement development, environmental protection, and efficient infrastructure use. The key policies considered include the Western Cape Provincial Spatial Development Framework (PSDF, 2014), the Overstrand Municipal Spatial Development Framework (SDF, 2020), and the Overstrand Integrated Development Plan (IDP, 2023/2024).

WESTERN CAPE PROVINCIAL SPATIAL DEVELOPMENT FRAMEWORK, 2014 (PSDF)

“3.3.4.2 SPATIAL IMPLICATIONS

The lack of integration, compaction and densification in urban areas in the Western Cape has serious negative consequences for municipal finances, for household livelihoods, for the environment, and the economy.

The PSDF provides principles to guide municipalities towards more efficient and sustainable spatial growth patterns. In order to secure a more sustainable future for the Province it is important that settlement planning and infrastructure investment achieves:

- i. higher densities*
- ii. a shift from a suburban to urban development model*
- iii. more compact settlement footprints to minimise environmental impacts, reduce the costs and time impacts of travel and enhance Provincial and Municipal financial sustainability in relation to the provision and maintenance of infrastructure, facilities and services.*
- iv. address apartheid spatial legacies by targeting investment in areas of high population concentration and socio-economic exclusion.*

By prioritising a more compact urban form through investment and development decisions, settlements in the Western Cape can become more inclusionary, widening the range of opportunities for all.”

Response and Compliance

The proposed development directly supports these principles by:

Being located within the existing urban edge of Vermont, thereby avoiding outward expansion into undeveloped or rural areas;

- Introducing judicious densification through the subdivision of the property into six (6) residential erven rather than low-density, single-dwelling development;
- Restricting the total development footprint to approximately 5 709 m², while retaining approximately 9 361 m² (over 60% of the site) as protected open space;
- Integrating the development with existing municipal infrastructure, thereby optimising service delivery and reducing long-term infrastructure costs.

The clustering of residential development and the permanent protection of the wetland area promote a compact and efficient land-use pattern, consistent with the PSDF’s objective of sustainable spatial growth.

“ 3.3.6.2 SPATIAL IMPLICATIONS

Investment in housing needs to ensure optimal returns on investment, while at the same time promoting settlement restructuring and integration.

In order to create integrated and sustainable communities with access to social and economic opportunities throughout the Province, the housing focus is being shifted towards diversifying typologies delivered and aligning housing projects with economic opportunities, increasing the supply and management of affordable rental accommodation, and also addressing the formal and informal sectors in one market.

The PSDF places less emphasis on delivering completed houses, and more emphasis on incrementally developing human settlements in partnership with other government departments, communities and the private sector. The focus is on improving the quality of the public environment of settlements.”

Response and Compliance

The proposed development contributes to these objectives by:

- Supporting incremental settlement development within an established residential suburb;
- Improving the quality of the surrounding environment through the formal protection and rehabilitation of the wetland system, which functions as a public environmental asset;
- Leveraging private sector investment to contribute to broader municipal objectives, including ecological protection and infrastructure upgrading (water, stormwater channel and sewer lines).

“PROVINCIAL SPATIAL POLICIES

POLICY S5: PROMOTE SUSTAINABLE, INTEGRATED AND INCLUSIVE HOUSING IN FORMAL AND INFORMAL MARKETS

The following policies must guide planning, project prioritisation, budgeting and performance management at a Provincial scale. These relate to housing delivery, planning and design, urban land markets and informality.

HOUSING PLANNING AND DESIGN

1. *Provide households with the residential environments, mobility and access to opportunities that support productive activities and reduce levels of exclusion from opportunity.*
2. *Increase densities of settlements and dwelling units in new housing projects.*
3. *Prioritise investment in community facilities, public infrastructure and public space, rather than an exclusive focus on housing or top structures.*
4. *Promote more mixed-income, mixed-use, inclusionary forms of development through incorporating various scales of economic opportunities within housing projects. “*

Response and Compliance

The development complies with Policy S5 through the following measures:

Locating within a serviced urban area with access to transport routes, employment opportunities, and public facilities;

- Increasing residential density in a controlled manner without compromising environmental integrity;
- Prioritising the protection of the wetland system as functional open space, enhancing both ecological value and residential amenity;
- Providing a form of development that is compatible with mixed residential typologies in the broader Vermont and Hermanus West area, thereby supporting inclusionary settlement patterns.

OVERSTRAND MUNICIPALITY SPATIAL DEVELOPMENT FRAMEWORK, 2020 (SDF)

VO 1*. The main urban, suburban and rural centres of the Overstrand's settlements continue to be the focal points of human activity and functions as social and economic hubs offering a variety of employment, retail, social and recreation opportunities and a range of community facilities:

- i. Encourage mixed use and high-density residential development within and adjacent to urban, suburban and rural centres.
- ii. Promote urban, suburban and rural centres as the primary commercial areas within settlements and suppress and limit commercial development outside of these centres.
- iii. Encourage the development and transformation of urban and rural centres into people orientated as opposed to function and production orientated places
- iv. Encourage and facilitate urban regeneration and restoration of under-utilised or decayed existing centres.

AO 4. The compact urban form and design of Overstrand's urban and rural settlements enables high levels of accessibility to key destinations such as employment, healthcare, education and recreation.

- i. Judicious densification and intensification in urban areas should be actively promoted.
- ii. Ensure effective integration between land-use and transportation planning and operations.

Hermanus

The total projected population of the Greater Hermanus amounted to 62 929 in 2019 based on a 5.2% projected growth per annum (Census 2001-2011). Based on the said projected growth, the town will consist of a population of 155 272 in 2031.

The town of Hermanus is for ease of reference and plan legibility, divided in three prominent areas, namely Hermanus West, Hermanus East and Hermanus Central (Refer Plans 30-32).

A survey in terms of the availability of vacant land was undertaken in 2019. A total of 1241 vacant residential erven were identified. A total amount of 92 343 additional people will need to be accommodated from 2019 to 2031, based on the aforementioned population total. Based on an average household size of 2.6 persons per household, this amounts to a total requirement of 35 517 additional dwelling units by 2031. The population figures have been influenced by the drastic population influx of 2018 and provision is made to accommodate similar influx peaks in the future.

The high-density residential suburb of Zwelihle is situated within Hermanus central. Zwelihle consisted of approximately 4261 informal settlements in 2018. According to (MPBS: Sept 2019), the future projected housing need, informed by the said number of informal structures, will amount to 7 127 by 2021 and 11 234 by 2031. This relates to a required land area of approximately 356 ha by 2021 and 562ha by 2031 based on a density of 20du/ha.

Hermanus West

Hermanus West consists of the area approximately 8km from the Hermanus CBD and includes the suburbs of Vermont, Onrus and Sandbaai.

Hermanus West is predominantly a residential area in nature with its spatial pattern / urban form dictated by the coastline to the south, the Onrus Mountains and the R43 to the north as well as the Onrus River that centrally bisects the area. The business areas within Hermanus West are typical small business nodes sparsely located within the neighbourhoods. The industrial area to the east of Hermanus and abutting Hermanus Central is prominent (Refer Hermanus Central).

The rocky and sandy shoreline, the coastal plateau and the Onrus Mountains have brought about, over time, environmental and heritage landscapes that are of particular quality. These landscapes are integrated along biodiversity corridors which originate in the mountainous areas, include pockets of municipal protected biodiversity rich land, and terminate at the coastline. The land which is included in these corridors is mainly protected by draft EMOZ protecting both public and municipal land (Refer Plan 30).

The central coastline of Hermanus West is also partially protected by the draft HPOZ, due to the presence of local heritage resources. In terms of services infrastructure provisions, the following should be noted:

- The R43 Provincial Road leading through Hermanus functions mostly at an acceptable service standard and has been upgraded in order to accommodate heavier traffic volumes. Internal roads function at acceptable levels of service.
- While the bulk water supply for Hermanus west is sufficient, additional sources are being investigated (i.e. new bore holes with treatment facilities). The water treatment works has relatively recently been upgraded. The water network servicing Onrus and Sandbaai is, however, in need of repair and upgrade. Additional bulk water sources are required in the interim. A recent feasibility study indicated seawater desalination to be the preferred option.
- The wastewater treatment work has sufficient capacity to service the area.
- Stormwater management infrastructure is moderate in terms of sufficiency and needs to be upgraded.
- The existing electricity supply and network adequately services the present demand of Hermanus West.
- Solid waste removal infrastructure and system are sufficiently provided for.

Response and Compliance

The proposed development aligns with the Overstrand SDF by:

- Being located within Hermanus West, a predominantly residential area identified for managed growth and densification;
- Supporting judicious densification within an established neighbourhood, consistent with SDF objectives for compact urban form;
- Avoiding development within identified biodiversity corridors by excluding residential erven from the wetland area and formally protecting it through a conservation servitude;
- Ensuring integration between land use and infrastructure planning, including stormwater, sewer, and road access, in line with municipal standards.

- The proposal recognises the environmental sensitivity of Hermanus West and responds by securing ecological connectivity and protecting the wetland system in perpetuity.

Overstrand Municipality Integrated Development Plan (2023/2024)

According to the Overstrand IDP 2023/2024, the Overstrand has a growing population that will increase the demand for housing, employment, service delivery and related infrastructure developments. The increased population growth will therefore place increased pressure on the municipal resources to develop new as well as maintain existing infrastructure. The ability to work from home has enabled households to move away from the economic hubs and settle in smaller towns such as Hermanus. This trend can be a valuable injection for the local economy as well as the municipality in terms of income generation, despite the increased demand for services (Source: Western Cape Provincial Treasury, MERO 2021 and SEP 2021).

Overstrand's 2023 projected forecast is 0.1 per cent economic growth, which is lower than both the District and Western Cape projection over the same period. In 2020, a total of 33 096 workers were employed in the Overstrand municipal area, contributing 27.4 per cent to Overberg District employment during the year. Between 2016 and 2020, the Overstrand municipal area experienced an average annual decline of 520 jobs. Estimates for 2021 indicate a further deterioration in Overstrand's employment, with a total of 1 475 jobs lost. Overall, the deterioration of the Overberg's labour market conditions in 2020 was due to the COVID-19 pandemic and the implantation of lockdown restrictions to contain its spread. Furthermore, restrictions in domestic and international travel greatly impacted activity in sectors related to tourism (Western Cape Provincial Treasury, MERO, 2022). Furthermore, load shedding in 2022 and 2023 are expected to further deteriorate employment prospects in the Overstrand municipal area. The estimated decline in employment opportunities is likely to result in a decline in household income, which in turn will continue to restrain municipal revenue and increase the demand for free basic services.

In alignment with the objectives outlined in the Overstrand IDP, the proposed development on Erf 1486, Vermont, seeks to contribute positively by providing new residential opportunities in a structured and environmentally sensitive manner. The development aims to accommodate a portion of the growing population through well-considered land use planning that supports sustainable densification without compromising environmental integrity. By doing so, the development helps meet the municipality's strategic goals of addressing housing demand, stimulating local economic activity, and contributing to long-term municipal sustainability through increased property rates and bulk infrastructure service contributions.

Response and Compliance

In alignment with the IDP, the proposed development:

- Contributes to addressing housing demand within the municipal area without requiring urban edge expansion;
- Supports local economic activity through construction-related employment and increased property rates income;
- Utilises existing bulk infrastructure capacity, thereby minimising additional strain on municipal resources;
- Promotes long-term sustainability by incorporating environmentally sensitive design and wetland protection measures.

Overall, the proposed development on Erf 1486, Vermont, demonstrates strong alignment with applicable provincial and municipal planning policies. It promotes compact, efficient urban development, supports sustainable housing delivery, protects critical environmental assets, and contributes positively to municipal growth objectives.

The proposal therefore complies with the intent and principles of the relevant spatial planning frameworks and represents an appropriate and policy-consistent development within the Overstrand municipal area.

5. Guidelines

List the guidelines which have been considered relevant to the proposed activity or development and explain how they have influenced the development proposal.

Guideline	Description
EIA Guideline and Information Document Series, dated March 2013: Applied to various components in the basic assessment process.	The following Guidelines were considered throughout this Basic Assessment Process: • Guideline for the Review of Specialist Input in the EIA process (June 2005); • Guideline for Environmental Management Plans (June 2005). • Guideline on Alternatives (March 2013) • Guideline on Need and Desirability • Guideline on Public Participation Process
Western Cape Biodiversity Spatial Plan Handbook and Guidelines (2023)	This guideline informed the assessment of the biodiversity context of the site. It was used to identify areas designated as Critical Biodiversity Areas (CBAs) and Ecological Support Areas (ESAs). The site was identified to be situated within the Ecological Support Area.
Wetland Offsets; A Best Practice Guideline for South Africa (2016)	This guideline informed the implementation of the Wetland Offset , Rehabilitation and Management Plan which was compiled by the freshwater specialist.

6. Protocols

Explain how the proposed activity or development complies with the requirements of the protocols referred to in the NOI and/or application form

Agriculture Theme – Medium Sensitivity – The site is located within the urban edge of Vermont and does not support active or high-potential agricultural land. As the development constitutes an urban infill project and is surrounded by existing residential uses, no agricultural specialist assessment is required. The project is therefore compliant with the Agricultural Protocol.

Animal Species Theme – High Sensitivity – The Screening Tool has identified the site as highly sensitive for several animal species of concern. A total of eight species of concern were identified through the screening tool (Naylor 2024, Table 2), with an additional species of conservation concern (SCC) identified during the desktop study. The following section evaluates the site's importance for these species, the probability of their presence within the development area, and the potential risk associated with the proposed development.

The Western Cape Biodiversity Plan (Pool-Stanvliet et al. 2017) identifies an Ecological Support Area (ESA2) linking the Whale Coast Private Nature Reserve to the west with the Vermont Salt Pan to the east, forming part of the primary water source for the pan (Helme 2023; Van Zyl et al. 2023). This ecological corridor is essential for the

movement of ground-dwelling species between natural reserves and wetland areas. The inclusion of private open space in the current development design provides critical connectivity.

While the development footprint results in minor encroachments into the ESA2 corridor mainly due to the placement of residential erven and the internal access road these infringements are significantly reduced compared to earlier alternatives. Accordingly, the overall risk to faunal connectivity is considered 'medium'.

Although not listed as an SCC in the screening report, the Cape dwarf chameleon is present in the immediate vicinity of the site and is classified as Near Threatened due to habitat fragmentation and decline (Tolley 2023). The species occurs across various vegetation types, including Fynbos, forested riparian areas, and peri-urban gardens (Tolley and Burger 2004), and several iNaturalist and GBIF records indicate its presence adjacent to the development site.

During the site visit, the species was not observed; however, the habitat at the site is highly suitable for breeding and foraging. Some habitat loss and disturbance during construction are inevitable, but the adjacent nature reserve and wetland system provide refuge, allowing the species to persist. A search and rescue operation is recommended prior to construction. Considering the mitigation measures proposed, the potential impact on *B. pumilum* is classified as low-medium.

Aquatic Biodiversity Theme – Very High Sensitivity – An Aquatic Biodiversity Impact Assessment was conducted, confirming the presence of a transformed Unchanneled Valley-Bottom (UVB) wetland on site. The development layout has been amended (Alternative 4) to minimise encroachment, with only minor intrusion from internal roads. A Wetland Offset, Rehabilitation and Management Plan has been compiled and will be implemented alongside the establishment of a wetland conservation servitude. The medium risk identified for residual wetland loss is addressed through a Wetland Offset Rehabilitation and Management Plan.

Archaeological and Cultural Heritage Impact Assessment – Low Sensitivity - Although the development is not extensive, potential impacts on archaeological and cultural heritage have been considered through submission of the NID to the Heritage Western Cape. Confirmation from the Heritage Western Cape (HWC) indicates that no additional heritage assessment is required. Mitigation measures are available in the EMP for implementation during construction if any finds are uncovered. No further actions required.

Civil Aviation Theme – High Sensitivity - The proposed development does not fall within any controlled civil aviation zones and is therefore not expected to interfere with aviation operations. No further assessment is required.

Defence Theme – Low Sensitivity - The subject property does not fall within any designated military or defence zones. As such, no conflict with national defence interests is anticipated and no further investigation is required.

Palaeontology Theme – Low Sensitivity – Consistent with the Archaeological and Cultural Heritage Impact Assessment, the proposed development's scale does not require additional assessment beyond potential mitigation measures during construction. Confirmation from the Heritage Western Cape (HWC) indicates that no additional heritage assessment is required. No further actions required.

Plant Species Theme – High Sensitivity – A Terrestrial Biodiversity Impact Assessment was undertaken by Nick Helme Botanical Surveys, acknowledging the transformation of parts of the site. This assessment also addresses plant species considerations adequately. The Botanical Specialist assessed the likelihood of Species of Conservation Concern (SoCC) and concluded that no such species were recorded on site, although one plant SoCC may occur in low numbers. The search and rescue operation for floral SoCC is recommended prior to construction.

Terrestrial Biodiversity Theme – Very High Sensitivity – The development occurs in one of the last remaining open erven in Vermont and aligns with surrounding development. A Terrestrial Biodiversity Impact Assessment was undertaken by Nick Helme Botanical Surveys (2023), in accordance with the Terrestrial Protocol. The assessment confirmed that approximately 70% of the site supports Hangklip Sand Fynbos, a threatened vegetation type. The proposed residential erven now exclude most of the High sensitivity areas (as required in my first bullet point of

mitigation), and it is estimated that less than 500m² of high sensitivity habitat will now be lost. The private access road now does not need to cross the wetland, as there will now be two access roads instead of one (also a requirement in bullet points one of my mitigation sections). Some 58% of the total erf will now be conservation area (Private Open Space), up from an original 36%. The proposed development phase of the project has now been reduced from an unacceptable High negative (Alternative 2) to an acceptable Low to Medium negative (Alternative 4), based on the botanical specialist opinion.

SECTION D: APPLICABLE LISTED ACTIVITIES

List the applicable activities in terms of the NEMA EIA Regulations

Activity No(s):	Provide the relevant Basic Assessment Activity(ies) as set out in Listing Notice 1	Describe the portion of the proposed development to which the applicable listed activity relates.
12	The development of dams or weirs, where the dam or weir, including infrastructure and water surface area, exceeds 100 square metres; or infrastructure or structures with a physical footprint of 100 square metres or more; where such development occurs (a) within a watercourse; (b) in front of a development setback; or (c) if no development setback exists, within 32 metres of a watercourse, measured from the edge of a watercourse	Internal access roads will encroach on a seasonal wetland, resulting in the loss of approximately 240 m ² of seasonal wetland area. Additionally, outlet structures which will be in the form of gabions will be positioned on the northern and southeastern edge of the seasonal wetland.
19	The infilling or depositing of any material of more than 10 cubic metres into, or the dredging, excavation, removal or moving of soil, sand, shells, shell grit, pebbles or rock of more than 10 cubic metres from (i) a watercourse;	The internal access roads under the preferred layout (Alternative 4) will encroach on the seasonal wetland, resulting in the loss of approximately 240 m² of seasonal wetland area. Construction of these roads will necessarily involve excavation and the movement of soil within this watercourse area in excess of the 10 m³ threshold. Stormwater outlet structures, in the form of gabions, are proposed on the northern and southeastern edges of the seasonal wetland, requiring the placement of material within the watercourse. The wetland rehabilitation works associated with the Wetland Offset, Rehabilitation and Management Plan will further involve the removal of existing foreign fill material from within the wetland as part of restoring the

		site's characteristic slope and hydrological profile. Accordingly, both the construction-phase infrastructure (access roads and gabion outlet structures) and the rehabilitation works within the retained wetland area trigger Activity 19 of Listing Notice 1, and this activity is addressed as part of the current application.
Activity No(s):	Provide the relevant Basic Assessment Activity(ies) as set out in Listing Notice 3	Describe the portion of the proposed development to which the applicable listed activity relates.
12	The clearance of an area of 300 square metres or more of indigenous vegetation i. Western Cape i. Within any critically endangered or endangered ecosystem listed in terms of section 52 of the NEMBA or prior to the publication of such a list, within an area that has been identified as critically endangered in the National Spatial Biodiversity Assessment 2004	More than 300 m ² of indigenous vegetation (Hangklip Sand Fynbos) will be removed to accommodate the residential development.
14	The development of infrastructure or structures with a physical footprint of 10 square metres or more where such development occurs within a watercourse; which have i. Outside urban areas; (ff) Critical Biodiversity areas or ecosystem service areas as identified in systematic biodiversity plans adopted by the competent authority or in bioregional plans;	The internal access roads under the preferred layout (Alternative 4) will encroach on the seasonal wetland, resulting in the loss of approximately 240 m ² of seasonal wetland area — a footprint well in excess of the 10 m ² threshold. Stormwater outlet structures, in the form of gabions, are proposed on the northern and southeastern edges of the seasonal wetland, constituting further infrastructure development within the watercourse.
Note: - The listed activities specified above must reconcile with activities applied for in the application form. The onus is on the Applicant to ensure that all applicable listed activities are included in the application. If a specific listed activity is not included in an Environmental Authorisation, a new application for Environmental Authorisation will have to be submitted. - Where additional listed activities have been identified, that have not been included in the application form, and amended application form must be submitted to the competent authority.		

The upgrade of the existing municipal line in Kolgans / Malmok street, replace 110 mm to 160 mm - will not trigger any listed activities because:

- No upgrade to the WWTW capacity is required.
- Because the upgraded pipe will have a diameter of 0.15m and the peak flow from the development will be approximately 0.13lt/sec.
- The capacity of upgraded 160 mm diameter pipeline will be approximately 16 liter/sec

The proposed stormwater pipeline from the R43 to the wetland is less than 1000m in length and is only about 100m long, therefore this listed activity is not applicable.

List the applicable waste management listed activities in terms of the NEM:WA

Activity No(s):	Provide the relevant Basic Assessment Activity(ies) as set out in Category A	Describe the portion of the proposed development to which the applicable listed activity relates:

List the applicable listed activities in terms of the NEM:AQA

Activity No(s):	Provide the relevant Listed Activity(ies)	Describe the portion of the proposed development to which the applicable listed activity relates:

SECTION E: PLANNING CONTEXT AND NEED AND DESIRABILITY

1.	Provide a description of the preferred alternative.
The preferred alternative (Alternative 4) for the proposed development on Erf 1486, Vermont represents the outcome of an iterative planning and assessment process informed by specialist studies, public participation, and comments received from relevant organs of state, particularly CapeNature. This alternative was selected as it achieves the most appropriate balance between accommodating residential development within the existing urban edge and ensuring the long-term protection and ecological functioning of the on-site wetland system. Alternative 4 provides for a reduced development footprint and lower development intensity when compared to previously assessed alternatives. The layout consists of six (6) residential erven, a single internal access road, and a large open space erf that incorporates the wetland and associated buffer areas. All residential erven have been repositioned to avoid any encroachment into the seasonal wetland, thereby directly addressing concerns raised during the Public Participation Process and by environmental authorities regarding wetland integrity and ecological connectivity. A key feature of the preferred alternative is the formal designation of the open space erf as a no-development area, which will be protected in perpetuity through a registered conservation servitude and managed by a Homeowners' Association. This open space forms part of the on-site wetland offset, ensuring the long-term conservation, rehabilitation, and management of the wetland system and its linkage to downstream ecological infrastructure, including the Vermont Salt Pan. The internal access road has been optimally aligned to minimise disturbance to sensitive areas. Where limited encroachment into the wetland is unavoidable, such impacts have been fully assessed and mitigated through the Wetland Offset Rehabilitation and Management Plan, in accordance with specialist recommendations. From a planning perspective, the preferred alternative supports compact urban development within an established residential area, in line with provincial and municipal spatial planning policies. The clustering of residential erven within a defined portion of the site enables efficient use of existing municipal infrastructure, while avoiding unnecessary urban sprawl. Approximately 5 709 m² of the site will be developed, while approximately 9 361 m² (the majority of the property) will be retained as protected open space, representing a significant improvement over earlier layout options. The preferred alternative applies the mitigation hierarchy, prioritising avoidance of sensitive environmental features, minimisation of impacts through reduced density and footprint, and long-term management through legally	

enforceable conservation mechanisms. Rehabilitation measures included in the proposal aim to restore hydrological connectivity and enhance the ecological functioning of the wetland system.

Components of the development – Alternative 4

Residential Erven

- Six (6) erven will be developed for residential purposes.
- Total residential footprint: approximately **4 253 m²**.

Private Road

- One internal access road will serve the residential erven and connect to Lynx Road to the east.
- Total road footprint: approximately **1 456 m²**.
- Erf 7: approximately 180 m × 8 m, including the road reserve.
- It is important to note that the two erven situated on the southern boundary (Erf 5 and Erf 6) will not be accessed via the main internal access road (Erf 7), but via a driveway that is within Erf 5.
- Additionally, it is noted that there is a culvert on the southern portion of the property which returns water into the wetland. However, the culvert will be left undisturbed by the proposed development, and attenuation for new stormwater runoff generated by the development will be provided by means of permeable paving and swales, ensuring that the culvert's existing function in sustaining the wetland is not compromised.

Open Space

- Total area: approximately **9 361 m²**.
- The open-space area includes the wetland and associated buffer zones.
- The open space will be secured through a council-approved co-management agreement between the Overstrand Municipality and the Homeowners' Association (HOA), providing the necessary long-term institutional and legal standing for the offset area's protection, management and maintenance beyond the development's construction phase.

Associated Infrastructure:

Electricity Supply

Electrical services will be supplied via a connection to the municipal electricity network. The installation will be done in line with the requirements and specifications of the Overstrand Municipality.

Water Supply

Potable water will be sourced from the Preekstoel Water Treatment Plant, via a 200 mm diameter pipeline located along Lynx Avenue. A new connection point will be established, and internal reticulation infrastructure will be constructed in accordance with municipal engineering standards. The Overstrand Municipality has confirmed sufficient capacity to accommodate the additional demand from the development.

Sewer and Effluent Management

The proposed development will be connected to the municipal sewer system. A specific section of the existing outfall sewer in Malmok / Kogans Crescent (existing roads) will be upgraded from 110 mm to 160 mm to accommodate the

increased effluent load as part of the developers' bulk contributions, the remainder of the existing municipal line will remain as is. The extension of the sewer line onto the site, has evolved to avoid the delineated wetland area and placed on the north of the erven with both new extensions falling outside of the wetland.

Stormwater Management

Given the site's proximity to a delineated wetland, a comprehensive Stormwater Management Plan has been prepared to effectively control and manage surface water received from upstream areas and the development itself in order to better manage and reduce the risks associated with the proposed development. The site forms part of a larger hydrological catchment where runoff from Catchment Area 1 (CA1), located north of the R43, drains into Catchment Area 2 (CA2), which encompasses the development site and the wetland system. One of these culverts discharge towards Erf 1486, Vermont and should be controlled to protect the properties from flooding. The specific culvert is indicated as follows with a red circle. It is important to note that given the above, the site already experiences increased inflow from surrounding hardened surfaces.



Figure 3a: Culvert Runoff to Erf 1486, Vermont

It is proposed that the stormwater runoff through the 2 x 750mm x 500mm culvert that discharge through Lynx Avenue be controlled by the provision of 2 x 900mm diameter Stormwater pipes through Erf 1486, Vermont at the following position (indicated with red arrow):



Figure 3b. Position of proposed stormwater control through development.




Figure 3c: Proposed location of Permeable Paving and Enhanced Swale.

The size of the pipe system is proposed on the northern section of the wetland as indicated by the red arrow in **Figure 3b** will be as follows:

- 2 x 900 mm diameter pipes

Runoff from the R43 culverts will be conveyed into the enhanced swale positioned north of the wetland (out of the wetland edge). This swale will facilitate the controlled flow of stormwater from the two culverts, channelling it through the enhanced swale system and along the stormwater drainage network integrated with the private roads. This will slow down flows, promote infiltration, and improve water quality before reaching the wetland.

To further control water entering the wetland post-development and to protect the building footprint located on the southern portion of the property from potential flooding, a permeable paving system has been incorporated along the

private road south of the wetland (outside the wetland edge). This system will promote infiltration into the subsurface, thereby reducing direct runoff and attenuating flows before discharging toward the wetland environment.

To manage stormwater in the proposed development Low Impact Development (LID) measures will be implemented, as illustrated in **Figure 3c**:

Permeable Paving System (South of Wetland)

Designed to reduce surface runoff and promote infiltration:

- Surface Storage Depth: 50 mm
- Pavement Thickness: 80 mm
- Base Course Height: 400 mm (43% void ratio)
- Permeability (clogged): 360 mm/hr
- Outlet: 160 mm uPVC pipe
- Storage Volume: 140 m³.

Enhanced Swale System (North of Wetland)

A vegetated swale to filter pollutants and slow runoff:

- Surface Storage Depth: 400 mm
- Swale Storage Depth: 750 mm
- Surface Slope: 0.5%
- Void Ratio: 0.43
- Vegetative Cover: 75%
- Conductivity: 120 mm/hr
- Storage Volume: 81 m³

Table 3: A summary of the development footprint and infrastructure sizes is provided below:

Erf	Zoning	Land Use	Area
1	GR1	Town Housing	640m ²
2	GR1	Town Housing	622m ²
3	GR1	Town Housing	618m ²
4	GR1	Town Housing	746m ²
5	GR1	Town Housing	816m ²
6	GR1	Town Housing	811m ²
7	OS3	Private Road	1456m ²
8	OS3	Private Open Space	9361m ²
Total			15070m²




Figure 4: Site development plan for the proposed development.

2. Explain how the proposed development is in line with the existing land use rights of the property as you have indicated in the NOI and application form? Include the proof of the existing land use rights granted in Appendix E21.

The erf is zoned as Residential Zone 1 for Residential use. The subject property abuts a residential complex to the south and is in line with the land use rights of the property for residential development. The property will be subdivided to accommodate residential erven, open space and internal road.

3. Explain how potential conflict with respect to existing approvals for the proposed site (as indicated in the NOI/and or application form) and the proposed development have been resolved.

N/A

4. Explain how the proposed development will be in line with the following?

- 4.1 The Provincial Spatial Development Framework.

Western Cape Spatial Development Framework (WCSDF, 2014)

The Western Cape Spatial Development Framework (WCSDF,2014) emphasizes three spatial themes aimed at ensuring the sustainable use of spatial assets, opening up opportunities in the provincial space-economy, and developing integrated and sustainable settlements. The proposed development supports these objectives by:

- **Sustainable use of spatial assets:** The development utilises an existing, serviced erf within the established, built-up residential suburb of Vermont, situated within the Overstrand urban edge, rather than extending development into unserviced or peripheral land.
- **Opportunities in the provincial space-economy:** The development creates residential opportunities responsive to housing demand in the Hermanus/Vermont area, consistent with the province's economic and settlement objectives, while the associated construction and operational phases contribute to local economic activity.
- **Integrated and sustainable settlement:** Development under the preferred layout, Alternative 4, has been designed to avoid the delineated permanent and seasonal wetland areas, with the retained wetland (0.9361 ha) formally protected as open space and secured through a conservation servitude and a council-approved co-management agreement between the Overstrand Municipality and the Homeowners Association. This approach integrates the settlement outcome with the long-term rehabilitation and management of the site's biodiversity and hydrological assets, consistent with the WCSDF's emphasis on sustainability rather than treating environmental protection and development as mutually exclusive.

The proposed development adheres to the investment strategies articulated in MSDFs by:

- Prioritizing investment in designated Priority Investment Areas within the municipality, such as the proposed development site on Lynx Avenue and R43.
- Addressing upgrading areas by improving infrastructure and urban environments to meet acceptable standards.
- Supporting restructuring or integration zones by promoting residential development and social housing initiatives, contributing to spatial justice and urban cohesion.
- Ensuring consolidation areas are adequately serviced and maintained to fulfill their functions effectively.
- Identifying medium to long-term growth areas for future development potential, aligning with municipal objectives for sustainable expansion.
- Considering spatial planning categories to guide appropriate development and protection measures, especially concerning biodiversity preservation.

4.2 The Integrated Development Plan of the local municipality.

The proposed development closely aligns with the Integrated Development Plan (IDP) of the Overstrand Local Municipality by prioritizing infill development, densification, and the creation of mixed-use nodes within the urban area of Vermont.

The development focuses on establishing the number of housing units per hectare within the built-up urban area of Vermont. By utilizing available land within existing urban boundaries, the project contributes to infill development objectives outlined in the IDP. This strategy helps accommodate population growth without necessitating significant land expansion, thus promoting a more compact and efficient urban form as advocated by the municipality.

By creating residential erven and providing housing opportunities within the built-up urban area, the development directly addresses the municipality's goal of meeting the housing needs of its residents. This aligns with the IDP's emphasis on developing vacant or underutilized land within existing urban areas to enhance housing accessibility and affordability.

The proposed development also supports the IDP's aim of reducing urban sprawl and the need for new infrastructure by concentrating development within established urban areas. By infilling gaps between existing buildings and redeveloping brownfield sites, the project contributes to creating a more compact and efficient urban form, thereby fostering sustainable urban growth.

4.3. The Spatial Development Framework of the local municipality.

Extracted from Overstrand Municipality Spatial Development Framework (2020)

“The total projected population of the Greater Hermanus amounted to 62 929 in 2019 based on a 5.2% projected growth per annum (Census 2001-2011). Based on the said projected growth, the town will consist of a population of 155 272 in 2031. The town of Hermanus is for ease of reference and plan legibility, divided in three prominent areas, namely Hermanus West, Hermanus East and Hermanus Central. A survey in terms of the availability of vacant land was undertaken in 2019. A total of 1241 vacant residential erven were identified. A total amount of 92 343 additional people will need to be accommodated from 2019 to 2031, based on the aforementioned population total. Based on an average household size of 2.6 persons per household, this amounts to a total requirement of 35 517 additional dwelling units by 2031. The population figures have been influenced by the drastic population influx of 2018 and provision is made to accommodate similar influx peaks in the future.

Hermanus West is predominantly a residential area in nature with its spatial pattern /urban form dictated by the coastline to the south, the Onrus Mountains and the R43 to the north as well as the Onrus River that centrally bisects the area. The business areas within Hermanus West are typical small business nodes sparsely located within the neighbourhoods. The industrial area to the east of Hermanus and abutting Hermanus Central is prominent (Refer Hermanus Central). The rocky and sandy shoreline, the coastal plateau and the Onrus Mountains have brought about, over time, environmental and heritage landscapes that are of particular quality. These landscapes are integrated along biodiversity corridors which originate in the mountainous areas, include pockets of municipal protected biodiversity rich land, and terminate at the coastline. The land which is included in these corridors is mainly protected by draft EMOZ protecting both public and municipal land.

The central coastline of Hermanus West is also partially protected by the draft HPOZ, due to the presence of local heritage resources. In terms of services infrastructure provisions, the following should be noted:

- *The R43 Provincial Road leading through Hermanus functions mostly at an acceptable service standard and has been upgraded in order to accommodate heavier traffic volumes. Internal roads function at acceptable levels of service.*
- *While the bulk water supply for Hermanus west is sufficient, additional sources are being investigated (i.e. new bore holes with treatment facilities). The water treatment works has relatively recently been upgraded. The water network servicing Onrus and Sandbaai is, however, in need of repair and upgrade. Additional bulk water sources are required in the interim. A recent feasibility study indicated seawater desalination to be the preferred option.*
- *The wastewater treatment work has sufficient capacity to service the area.*
- *Stormwater management infrastructure is moderate in terms of sufficiency and needs to be upgraded.*
- *The existing electricity supply and network adequately services the present demand of Hermanus West.*
- *Solid waste removal infrastructure and system are sufficiently provided for.”*

In this context, the proposed development is the type of infill development within the built-up suburb area of Vermont which contributes to addressing the housing demand in a strategic manner. While the proposed 6 residential erven may represent a fraction of the overall housing demand, it represents a proactive step towards addressing future challenges associated with population growth in the region.

The Spatial Development Framework advocates for environmentally aware development, investment in the area, and the management of remainder land for conservation. The proposed development adheres to these principles by

integrating measures to mitigate environmental impacts, stimulating investment in the local area, and managing land for conservation purposes.

Furthermore, the development aligns with the vision for sustainable urban development by promoting infill development within the built-up urban area. This approach fosters denser, compact communities, maximizing land use efficiency and minimizing urban sprawl. By providing additional residential opportunities within existing urban boundaries, the development contributes to the overall well-being and resilience of the Overstrand region.

4.4. The Environmental Management Framework applicable to the area.

The subject property, Erf 1486 in Vermont, is located in an ecologically sensitive area directly adjacent to the Whale Coast Nature Reserve. It also forms part of a critical ecological linkage, identified as an Ecological Support Area (ESA2) in the Western Cape Biodiversity Spatial Plan, (2017). This ESA2 corridor plays a vital role in connecting the nature reserve to the Vermont Salt Pan to the east, supporting faunal movement and the functioning of local wetland systems. According to the Draft Environmental Management Overlay Zones (EMOZs) adopted by the Overstrand Municipality, Erf 1486 falls within the Urban Conservation category (EMOZ Category D).

The proposed development has been aligned with the objectives of both the Environmental Management Framework (EMF) and the EMOZ Category D guidelines. The layout of the development has been refined through several iterations based on input from freshwater and botanical specialists. This includes careful consideration of the site's environmental sensitivities, particularly the presence of a natural unchanneled valley-bottom wetland, critically endangered Hangklip Sand Fynbos and ecological corridor traversing the site. The site, as highlighted by the faunal assessment, is likely to support species of conservation concern, including the Cape dwarf chameleon, and likely one plant species of conservation concern, although none were identified during the site survey.

To address these environmental constraints, the development incorporates several key mitigation and enhancement measures as well as a complete avoidance of the permanent wetland. These include the preservation of approximately 9361 m² of open space corresponding with the delineated wetland, through an establishment of a formal wetland conservation servitude in this area. A Wetland Offset, Rehabilitation and Management Plan will be implemented to restore ecological function and improve wetland condition. Additionally, this "private open space" as included in the development layout will remain as a No-go area to maintain ecological connectivity across the site. This space is particularly important for facilitating the movement of ground-dwelling fauna between the adjacent nature reserve and the wetland system. Special attention is also being given to vulnerable species, such as the Cape dwarf chameleon, for which a search-and-rescue operation is planned prior to construction. Long-term management measures, such as alien vegetation control, revegetation, prevention of illegal dumping, and restriction of free-roaming pets, will also be enforced to protect the ecological integrity of the conserved areas.



Figure 5: The property is mapped as urban conservation EMOZ, Category D.

- | | |
|----|--|
| 5. | Explain how comments from the relevant authorities and/or specialist(s) with respect to biodiversity have influenced the proposed development. |
|----|--|

Public Participation Process 1 – 22/03/2023 to 24/04/2023

The comments received from relevant authorities and biodiversity specialists during the first round of pre-application public participation, conducted on 23 March 2023, significantly influenced the planning and refinement of the proposed development on Erf 1486, Vermont. The feedback led to revisions in the project layout, triggered additional specialist studies, and ensured that the development approach was better aligned with the area's environmental sensitivities.

The Department of Environmental Affairs and Development Planning (DEA&DP) raised concerns about insufficient detail in the draft Basic Assessment Report (BAR), particularly regarding wetland rehabilitation and compliance with national biodiversity reporting protocols. As a result, the activity description was revised to include information about the planned wetland rehabilitation and offset procedure. DEA&DP also requested that gaps in Biodiversity Assessment be addressed through the inclusion of an Aquatic Biodiversity Impact Assessment, confirmation of peat presence, and evaluation of the impacts of vegetation loss, particularly concerning critically endangered vegetation types. These matters have been addressed in the subsequent revisions of the report.

Cape Nature provided detailed input regarding the biodiversity implications of the proposed development. They highlighted the presence of Hangklip Sand Fynbos classified as Critically Endangered on the site, as well as the importance of existing wetland systems. Cape Nature emphasized the need to explore alternative layouts that would better minimize impacts on these sensitive ecological features. Their input directly informed the refinement of the layout to reduce the development footprint within sensitive areas.

Whale Coast Conservation submitted comments emphasizing the importance of accurate wetland delineation and assessing the full ecological role of the wetland within the broader ecosystem. They expressed concerns about cumulative impacts on the Vermont Salt Pan (located approximately 820 m east of the site), highlighted the inadequate treatment of climate change in the BAR, and called for more robust biodiversity assessments and mitigation strategies. These inputs were influential in motivating the inclusion of both a Freshwater Impact Assessment and a Botanical Impact Assessment in the revised BAR.

The Vermont Ratepayers' Association supported the protection of the wetland and proposed that the Environmental Management Programme (EMPr) be integrated into the constitution of the future Homeowners' Association to ensure long-term compliance. They suggested several site-specific measures, including stormwater management, environmentally sensitive construction methods, and pet control. Their recommendation for a Maintenance Management Plan to support wetland conservation was also taken into consideration.

The Breede-Olifants Catchment Management Agency (BOCMA) noted the absence of a Risk Matrix in the freshwater screening, which limited their ability to comment comprehensively. They emphasized the need for responsible water resource management and requested further engagement upon submission of the required documentation. Their feedback led to the compilation of a formal Risk Assessment matrix for the development.

Additional critical feedback came from individuals and local conservation bodies and representatives from the adjacent Hoek van der Berg Nature Reserve. These stakeholders voiced strong opposition to the proposed encroachment on seasonal wetlands and raised concerns about property placements within the 30-metre flood line. They called for additional specialist studies to understand the impact of adjacent alien vegetation clearing and the extent of the onsite wetland.

Public participation Round Two – 17/05/2024 to 17/06/2024

The second round of “out of process” public participation was undertaken from 17 May 2024 to 17 June 2024. During this phase, three layout alternatives were presented: Alternative 1 (non-preferred), Alternative 2 (the previously preferred layout), and Alternative 3 (the newly proposed preferred layout).

This round was specifically designed to address concerns raised during the first round of consultation, particularly the need to protect the wetland system, manage stormwater effectively, and reduce ecological impacts. In response, additional specialist studies were commissioned, including a full Aquatic Biodiversity Impact Assessment and Risk Matrix by Delta Ecology, and a Faunal Assessment to evaluate potential impacts on fauna.

Based on the findings of these studies and stakeholder input, Alternative 3 was developed as a refinement of the proposal. This layout avoids all permanent wetland areas, reduces encroachment into seasonal wetlands by designating “No Development Zones” within erven, and incorporates measures to maintain ecological connectivity across the site. These no-go areas will be secured through the Regulated Areas Management Plan (Appendix G2), compiled as an addendum to the EMPr, to ensure long-term protection and management.

Furthermore, in direct response to public concerns, a Stormwater Management Plan was commissioned to address flood risks and hydrological functioning, while a Wetland Offset and Rehabilitation Management Plan was prepared to provide for the restoration and long-term management of wetland ecological processes. Both plans have been integrated into Alternative 3 and were supported by the specialist team as essential interventions to mitigate impacts.

This additional round of out-of-process consultation was undertaken to present the new preferred alternative and supporting management plans, as well as to address the requirement for a minor upgrade of the existing sewer

pipeline in Kolgans Street. The evolution of Alternative 3 therefore reflects a collaborative process that integrates specialist guidance, regulatory requirements, and stakeholder concerns, resulting in a layout with significantly reduced environmental impacts while meeting the development objectives.

Public Participation Round 3 - In Process Public Participation

Alternative 3 was identified as the most viable option on-site and was submitted along with the Application Form. During the public participation process, several comments were received highlighting the need for an additional wetland delineation to be undertaken by an independent freshwater specialist. As a result, EnviroSwift was appointed to conduct a further delineation. The findings of this specialist study confirmed that the wetland delineation conducted by Delta Ecology in 2024 was accurate, with no material differences identified. Minor discrepancies were attributed to differences in mapping tools and methodology rather than ecological interpretation. The 2025 EnviroSwift delineation therefore endorses and supports the Delta delineation, providing further assurance of the accuracy of the wetland boundary for planning and decision-making purposes.

Additionally, a concern was raised during the public participation process regarding the potential loss of faunal habitat, with specific reference to the Cape Dwarf Chameleon (*Bradypodion pumilum*). However, the faunal specialist confirmed that Layout Alternative 3, as the preferred option, shows an improvement from the previous alternatives and that the provision of an open space facilitates a more functional corridor Cape dwarf chameleon, *Bradypodion pumilum* and species movement, resulting to a low - medium impact rating after mitigation.

CapeNature noted that the sewer pipeline would traverse the wetland in the northern portion of the property and therefore recommended further investigation of an alternative alignment that avoids the wetland. It is important to note that most of the property is covered by wetland habitat; however, some alternative options for the placement of certain infrastructure may require minor infringement within the seasonal wetland. In line with CapeNature's recommendation, the layout (Alternative 3– previously preferred) now proposes that the sewer pipeline run parallel to the water pipeline route, thereby completely avoiding the wetland area. This represents a significant improvement in the current layout compared to the previous alternatives, as it ensures that the sewer pipeline no longer infringes on the wetland area.

Another concern raised during the public participation process related to the placement of the proposed swale system within the seasonal wetland area. Stakeholders highlighted the risks associated with locating stormwater infrastructure directly within sensitive wetland habitats, including potential disturbance of wetland functionality, changes in hydrological patterns, and long-term maintenance challenges. In response to these comments, the project team revised the layout in Alternative 3 (the previously preferred option). In this design, the enhanced swale system has been shifted outside of the wetland edge, thereby avoiding direct intrusion into the seasonal wetland. This amendment reflects a significant improvement compared to the earlier layout alternatives, as it both addresses stakeholder concerns and strengthens the environmental sustainability of the proposal.

Moreover, other concerns raised by Cape Nature was regarding the feasibility of maintaining the wetland sections within the private residential erven in terms of both habitat condition and ecological function and connectivity. This will be managed through a formal servitude which will be enforced into the title deed in ensuring that the development does not occur within the no-go areas. Additionally, the area will require to be demarcated with bollard fencing to further allow the ecological connectivity and faunal movement.

Public Participation Round 4 – Final Public Participation Process

This Public Participation Process was regarded as a final and last round of Public Participation Process prior to the submission of the Final BAR to the competent authority for decision-making. During this round, it became evident that outstanding concerns remained in relation to the previously preferred layout (Alternative 3). As a result, these concerns were reassessed and addressed through further refinement of the site development layout, which ultimately informed the identification of a revised and final preferred alternative (Alternative 4).

In particular, concerns were raised regarding the proximity of certain residential erven to the seasonal wetland, the potential for indirect impacts associated with human activity (such as disturbance, informal access, and edge effects), and the enforceability of wetland protection measures where portions of erven extended into no-development areas. CapeNature indicated that, although avoidance measures were proposed under Alternative 3, the layout did not sufficiently eliminate the risk of incremental encroachment into the wetland system over time.

In response to these concerns, the development layout was reassessed in consultation with the specialist team, and further refinements were undertaken to ensure that the wetland and its associated buffer areas are fully excluded from residential erven. This process resulted in the identification of a revised preferred alternative, Alternative 4, which significantly reduces the development footprint, relocates all residential erven outside of the wetland area, and consolidates the wetland and buffer areas into a single, formally protected open space erf.

The revised layout also provides for the wetland area to be secured in perpetuity through a registered conservation servitude, supported by clear management responsibilities assigned to the Homeowners' Association. These measures address the concerns raised during the final public participation round and provide greater certainty regarding the long-term protection, rehabilitation, and ecological functioning of the wetland system.

Moreover, the additional public participation process provided Interested and Affected Parties (I&APs) with an opportunity to review the updated wetland delineation and the final refinements to the preferred layout, specifically in relation to:

- Revisions to the stormwater management strategy, including the relocation of the newly required sewer line to a position outside the delineated seasonal wetland;
- The removal of swales previously proposed within the delineated wetland area; and
- An independent external wetland delineation undertaken by Mr Nick Steytler, which informed the final layout adjustments.

Public Participation Process 5 – Final

The proposed development on Erf 1486, Vermont, has undergone a number of layout iterations in response to environmental constraints, specialist recommendations, comments received from commenting authorities and input received through the Public Participation Process (PPP). In particular, biodiversity-related comments have significantly influenced the evolution of the development layout, with emphasis placed on the avoidance and minimisation of impacts to the wetland system, retention of ecological connectivity, protection of wetland habitat, stormwater management, and the long-term management and securing of the retained wetland areas.

The mitigation hierarchy has been repeatedly applied during the planning and assessment process. The number of proposed residential erven has been reduced from the original 14 erven to the current six residential erven, while a substantial portion of the property is retained as protected private open space/no-go area. Approximately 9,361 m² of on-site wetland is proposed to be retained and protected in the long term. The current preferred Alternative 4

therefore represents an evolution of the layout intended to avoid the permanent wetland and minimise unavoidable impacts associated primarily with linear access infrastructure.

Overberg District Municipality (ODM)

The Overberg District Municipality acknowledged the amendments made to the development layout in response to specialist recommendations, stakeholder input and environmental constraints. ODM supported Alternative 4 on the basis that it minimises impacts on the seasonal wetland by relocating the residential development outside the wetland area, limiting residual impacts primarily to the proposed access crossing, and providing for rehabilitation and long-term protection of the retained wetland.

ODM further supported the principle of implementing a wetland biodiversity offset together with associated rehabilitation and management measures. The Municipality indicated that the retained wetland should be secured through appropriate conservation and long-term management measures and raised no objection to the application subject to the implementation of the relevant mitigation, rehabilitation, biodiversity offset and environmental management measures.

Influence on the proposed development:

The ODM comments supported the continued use of Alternative 4 as the preferred layout and reinforced the requirement for the retained wetland to be protected and managed in the long term. Consequently, the layout retains a defined open-space/no-go area, while rehabilitation, management and offset measures have been incorporated into the environmental management framework. It is noted that the applicable offset is specifically a wetland offset, and no separate terrestrial biodiversity offset was required.

Department of Environmental Affairs and Development Planning (DEA&DP)

DEA&DP identified the presence of a wetland on the property and noted that the site is mapped as containing Hangklip Sand Fynbos, classified as Critically Endangered. The Department also requested clarification regarding the applicable listed activities, inclusion of all stormwater infrastructure in the site development plan, and comment from BOCMA regarding the proposed wetland offset.

The Department's comments therefore reinforced the need for the wetland-related infrastructure, including the stormwater swales, outlet structures and associated gabions, to be properly incorporated into the development layout and assessed as part of the application.

Influence on the proposed development:

The comments resulted in the relevant development components and stormwater infrastructure being incorporated into the assessment and site development plan. The BAR was also updated to include the required confirmation and supporting information relating to the listed activities, public participation, electricity supply and construction duration. The wetland offset was further referred to BOCMA for consideration. The final layout and EMPr accordingly provide for stormwater management and mitigation measures intended to manage runoff, erosion and potential downstream impacts.

Cape Nature

Cape Nature has provided comments on several previous versions of the BAR, with its primary concern historically relating to the encroachment of the proposed development into the wetland linking the Vermont Pan and the Whale Coast Nature Reserve. Following successive layout revisions, the residential erven were repositioned so that they avoid the wetland as delineated in the aquatic biodiversity assessment, with only minor encroachments associated with permeable access infrastructure. CapeNature previously indicated that this revised layout addressed its concerns regarding residential encroachment into the delineated wetland.

Cape Nature subsequently raised concerns regarding an independent privately commissioned wetland delineation undertaken in July 2026, which indicated a substantially greater wetland extent across Erf 1486. CapeNature requested that this additional information be taken into account and indicated that, should the revised delineation be verified, it could materially alter the development constraints and the associated wetland offset requirements. CapeNature also recommended that the mitigation hierarchy be sufficiently addressed before determining the final offset requirement.

Cape Nature further advised that its stewardship programme was not considered the appropriate mechanism for securing the proposed wetland offset and recommended further engagement between the applicant, CapeNature, the Overstrand Municipality and BOCMA regarding an appropriate mechanism for securing and managing the offset area.

Influence on the proposed development:

CapeNature's comments have been a significant driver in the evolution of the development layout. The mitigation hierarchy was reapplied, resulting in the progressive reduction and repositioning of development footprints and the current preferred Alternative 4. The preferred layout avoids the permanent wetland and minimises infringement into the seasonal wetland, while retaining a substantial open-space area to maintain ecological connectivity. The potable water and sewer infrastructure has also been routed outside the delineated wetland wherever practicable.

The comments further influenced the approach to securing the wetland offset. A council-approved co-management agreement between the Overstrand Municipality and the Homeowners' Association has been identified as a potential mechanism, with further engagement with CapeNature, the Municipality and BOCMA required to formalise the long-term management and responsibilities associated with the offset area.

Breede-Olifants Catchment Management Agency (BOCMA)

BOCMA identified the ecological and hydrological value of the unchannelled valley-bottom wetland despite its ecological transformation. BOCMA confirmed that a Water Use Licence is required due to the proposed encroachment into the wetland and supported the reinstatement of the ecological corridor linking the Hoek van der Berg area with the Vermont Salt Pan through implementation of the Wetland Offset, Rehabilitation and Management Plan. BOCMA further required clear method statements, implementation timeframes, accountability measures, ongoing monitoring and adaptive management.

BOCMA also highlighted the need for the Stormwater Management Plan to account for the site-specific hydrological dynamics associated with the wetland and surrounding catchment.

Influence on the proposed development:

BOCMA's comments have influenced both the design and management framework of the development. The wetland is retained as an important ecological and hydrological feature, while the Stormwater Management Plan has been

incorporated into the development design to attenuate and manage stormwater runoff. The Wetland Offset, Rehabilitation and Management Plan provides for the rehabilitation, long-term management and monitoring of the retained wetland area, with adaptive management measures where required. The WULA has also been updated to reflect the current preferred Alternative 4.

Whale Coast Conservation (WCC)

Whale Coast Conservation raised concerns regarding the extent and future expansion of the wetland, the ecological corridor function of Erf 1486, hydrological connectivity, stormwater and flooding risks, and the adequacy of the wetland offset. WCC also highlighted the importance of considering the property within the broader wetland system linking the upper catchment with the Vermont Salt Pan.

Influence on the proposed development:

The comments reinforced the need to minimise the development footprint and retain substantial areas of the property as open space. The evolution of the layout from the original proposal to the current six-erven Alternative 4 represents successive application of the mitigation hierarchy. The development footprint has consequently been reduced, while approximately 9,361 m² of on-site wetland is proposed for long-term protection.

The concerns regarding hydrological connectivity and downstream impacts have also informed the Stormwater Management Plan, which provides for attenuation and controlled management of stormwater runoff. The proposed culvert on the southern portion of the property will remain undisturbed, while permeable paving and swales will be used to attenuate additional stormwater generated by the development.

The proposed Co management agreement between Overstrand and the Developer provides a financed long-term protection of more than half of the property which should be considered as positive contribution towards the vision for the reinstatement of the Vermont-Salt Pan to Botrivier Wetland Link.

Overall influence of biodiversity-related comments on the proposed development

Overall, comments from the relevant authorities, appointed specialists, independent reviewers and Interested and Affected Parties have materially influenced the proposed development on Erf 1486. The development has evolved through successive iterations in response to identified wetland and biodiversity constraints.

The principal biodiversity-related changes include:

- reduction of the proposed residential erven from the original 14 erven to six erven;
- repositioning of the residential erven to avoid the delineated permanent wetland and minimise impacts on the seasonal wetland;
- retention of approximately 9,361 m² of on-site wetland/open space for long-term protection;
- establishment of defined no-go areas during both construction and operation;
- routing of potable water and sewer infrastructure outside the delineated wetland wherever practicable;
- incorporation of stormwater attenuation and management measures informed by the site's wetland and catchment characteristics;
- incorporation of aquatic biodiversity protection measures into the EMPr;
- preparation and implementation of a Wetland Offset, Rehabilitation and Management Plan;
- provision for long-term monitoring, management and adaptive management of the retained wetland;
- updating of the WULA to reflect the current preferred Alternative 4; and

- Proposed Co-Management Agreement between Overstrand Municipality and the Developer, endorsed by council, enforcing the long-term management and protection of the delineated permanent and temporary wetland.

Accordingly, the current preferred Alternative 4 represents the outcome of the iterative application of the mitigation hierarchy, specialist input and engagement with commenting authorities and stakeholders. The layout seeks to avoid the most sensitive wetland areas, minimise unavoidable impacts, retain ecological connectivity and secure the long-term protection and management of the retained wetland system.

6.	Explain how the Western Cape Biodiversity Spatial Plan (including the guidelines in the handbook) has influenced the proposed development.
----	--

The proposed development on Erf 1486, Vermont has been informed by and complies with the principles outlined in the Western Cape Biodiversity Spatial Plan (WCBSP), particularly the 2017 version. It is important to note that the project planning and initial specialist studies were undertaken prior to the promulgation of the 2023 BSP in December 2024 and therefore much of the development planning was based on the 2017 BSP.

According to the WCBSP (2017) and as mapped in the CapeNature Spatial Biodiversity Plan referenced in the Botanical Impact Assessment, the subject property is located within an Ecological Support Area 2 (ESA2). This zone forms an important ecological linkage between the Walker Bay Nature Reserve (Former Hoek van der Berg) to the west and the Vermont Salt Pan to the east. As such, the site supports ecological process continuity, hydrological function, and biodiversity connectivity particularly for wetland-dependent and mobile fauna.

A natural Unchanneled Valley Bottom (UVB) wetland was identified and delineated on site by the freshwater specialist. Although the wetland is considered ecologically transformed due to historical infill and the presence of alien invasive vegetation, roads and other development on the site, it retains functional hydrological and ecological value. Specialist assessments confirmed the presence of faunal and botanical diversity on site. While no Species of Conservation Concern (SoCC) were confirmed during the surveys, the presence of faunal species such as frogs and the Cape Dwarf Chameleon (*Bradypodion pumilum*) are considered likely to be present onsite based on indirect observations (e.g., frog calls and suitable habitat features).

The Western Cape Biodiversity Spatial Plan Handbook and Guideline (2023) provide guidelines for land-use within mapped ESAs, highlighting that these areas may already have some form of development (cultivation, mining or even buildings and infrastructure) but should be providing ecosystem services. The handbook further highlights that, where possible, the current land-uses should be withdrawn, and rehabilitation undertaken, or where unavoidable, that development must be designed to retain ecological functionality and ensure that ecological corridors remain intact (WCBSP Handbook and Guideline, 2023). The proposed development on Erf 1486, is in line with the above provision as the proposal not only avoid the seasonal and permanent wetland areas but provides for a secure mechanism to rehabilitate the onsite wetland, conserve it in perpetuity through a conservation servitude and indirectly assist in the broader goal to reinstate the ecological corridor link from the Walker Bay Nature Reserve to the Vermont Salt Pan through the implementation of the onsite Wetland Offset, Rehabilitation and Management Plan. Alternative 4 reduces the development footprint significantly with a larger proportion of the site (9361 m²) being allocated as an open space.

Furthermore, the Botanical specialist in his revised addendum supports the revised layout, stating that it represents a substantial improvement in ecological terms and reduces the project's impact from “unacceptable High negative” (under a previous layout versions) to an “acceptable Low – Medium negative” under Alternative 4.

In addition, a Wetland Offset, Rehabilitation and Management Plan will guide restoration and long-term management of the conservation area, aligning with the ESA objectives. Note that the 2023 Biodiversity Spatial Plan (BSP) maps the property as a Critical Biodiversity Area (CBA1: Terrestrial). The Western Cape Biodiversity Spatial Plan Handbook and Guidelines (2023) indicates that such areas should be maintained in a natural or near-natural state with no further loss of habitat. It further highlights that only low-impact, biodiversity -sensitive land uses area appropriate. The development of Erf 1486 aims to achieve a low impact type development within the context of both the built-up urban area of Vermont and within a site identified as sensitive.	
7.	Explain how the proposed development is in line with the intention/purpose of the relevant zones as defined in the ICMA.
N/A	
8.	Explain whether the screening report has changed from the one submitted together with the application form. The screening report must be attached as Appendix I.
N/A	
9.	Explain how the proposed development will optimise vacant land available within an urban area.
The subject property is located within the built-up urban edge of Vermont and is one of the last remaining large properties available for development in the area. The site presents a valuable opportunity to address the high demand for residential offerings in Vermont, Hermanus and the Overberg in general. By developing this vacant land, the proposed development will help meet the housing needs of the community while minimizing the need for further expansion into undeveloped, serviced areas outside the urban edge. This approach aligns with principles of sustainable urban development by promoting infill development over urban sprawl and densification within established urban boundaries. Overall, the proposed development optimizes vacant land within the urban area to provide housing options in response to high demand.	
10.	Explain how the proposed development will optimise the use of existing resources and infrastructure.
The erf is located within the built-up residential area of Vermont, with municipal services already available. The proposal presents a continuation of infill residential development within the area. GLS Consulting conducted the capacity analysis for the proposal and concluded the following: → The developer of Erf 1486 in Vermont may be liable for the payment of a Development Contribution (as calculated by the Overstrand Municipality) for bulk water and sewer infrastructure as per Council Policy. There is sufficient capacity in the existing water reticulation system to accommodate the proposed development, and no network upgrades will be required. There is sufficient hydraulic spare capacity in the existing small bore sewer reticulation system downstream of the proposed development to accommodate the proposed development. → Accommodation of the development on Erf 1486 on the existing small-bore system is not supported in its current state, due to operational problems that are experienced with smaller diameter sewer systems, specifically frequent sewer blockages. The requirements to accommodate the proposed development in the existing sewer system are therefore link services item 1 and master plan item OHS11.12 to reinforce the existing Onrus Main PS sewer reticulation system. Mr Ricardo Andrew from the Overstrand Municipality has confirmed that the North-south section of the 110 mm diameter existing pipeline will need to be upgraded to a 160 mm diameter pipeline as indicated in yellow in Figure below. The upgrade will take place within the	

roads of Kolgans and Malmok, Vermont, only, therefore disturbance will be confined to the road and transformed road reserve only.




Figure 6: Showing upgrade required to accommodate the proposed development.

The upgrade will be done in existing roads and within the path of the existing line as follows:

Excavation

Excavation equipment such as backhoes or excavators is used to dig a trench along the path of the existing sewer pipe. The road surface will need to be cut and broken up. The trench width will be in the order of 800 mm. The depth is not currently known, but typically it's in the order of 1.5 meters.

Removal of existing pipe

Once the trench is dug, the existing sewer pipe is exposed and removed. This may involve cutting the pipe into manageable sections for removal. To maintain existing sewer flow, it may be necessary to install temporary structures and make use of pumps to bypass existing sewer flow.

Installation of new pipe

The new larger 160 mm diameter pipe is installed in the trench on appropriate compacted bedding material and connected to the existing sewer system at existing manholes using appropriate connectors and sealing materials.

Backfilling

Once the pipe is installed and connections secured, a bedding material is installed followed by backfill material and compacted. The pipe is tested (pressure and mirror). In the case where the pipe is installed in the road, the road layer works will need to be reinstated as well as the surface (asphalt, paving etc.).

Photos of where the existing line is located and where it needs to be upgraded. These sites are completely transformed and will constitute a normal like for like upgrade to increase the pipe diameter from 110 to 160 mm.




Figure 7.1-A. Northwards upgrade area.



Figure 7.1-B Looking south along Kolgans Street – servitude in road.




Figure 7.2-B. North wards along Kolgans – upgrade to take place in the road



Figure 7.3-A. Manhole on existing pipeline along Malmok.



Figure 7.3-B - Manhole on existing pipeline along Kolgans – upgrade required.

- | | |
|-----|--|
| 11. | Explain whether the necessary services are available and whether the local authority has confirmed sufficient, spare, unallocated service capacity. (Confirmation of all services must be included in Appendix F). |
|-----|--|

The erf will connect to existing services in the Vermont suburb at the cost of the developer. See **Appendix F** for Service Reports:

Associated infrastructure

Water services:

- The development will connect to the existing Vermont reservoir distribution zone via a 200 mm diameter pipeline in Lynx Avenue.
- The existing Vermont reservoir network has sufficient capacity to accommodate the proposed development's water demand, calculated at an Annual Average Daily Demand (AADD) of 5.4 kL/d for 9 single residential units and a fire flow of 15 L/s at 7 m pressure.
- The bulk supply system from the Preekstoel Water Treatment Plant (WTP) to the Vermont reservoirs has sufficient capacity.
- There is adequate reservoir storage capacity in the existing Vermont reservoirs.
- No network upgrades are required for the water reticulation system, confirming that the existing infrastructure can fully support the proposed development.

Sewer Services:

- The existing 110 mm small bore sewer system from Erf 1486 to Malmok Street, and a small section of 110 mm sewer in Malmok Street, have sufficient hydraulic spare capacity to the peak sewage flow from the proposed development – with the size upgrade required in Kolgans and Malmok as described above.
- The Onrus Main PS and the downstream Hermanus Wastewater Treatment Plant (WWTP) have sufficient spare capacity to accommodate the sewage flow from the development.

The north south section on Kolgans and Malmok road will require upgrade as follows:

Excavation

Excavation equipment such as backhoes or excavators is used to dig a trench along the path of the existing sewer pipe. Where the pipe is situated in a surfaced road, the surface will need to be cut and broken up and the unsuitable material spoiled. The trench width will be in the order of 800 mm. The depth is not currently known, but typically it's in the order of 1,5 meters.

Removal of existing pipe

Once the trench is dug, the existing sewer pipe is exposed and removed. This may involve cutting the pipe into manageable sections for removal. To maintain existing sewer flow, it may be necessary to install temporary structures and make use of pumps to bypass existing sewer flow.

Installation of new pipe

The new 160 mm diameter pipe is installed in the trench on appropriate compacted bedding material and connected to the existing sewer system at existing manholes using appropriate connectors and sealing materials.

Backfilling

Once the pipe is installed and connections secured, a bedding material is installed followed by backfill material and compacted. The pipe is tested (pressure and mirror). In the case where the pipe is installed in the road, the road layer works will need to be reinstated as well as the surface (asphalt, paving etc.).

No vegetation will be disturbed or removed, and upgrade involves the upgrade from the existing 110 mm pipe to the 160 mm pipeline with the existing road surfaces of Kolgans and Malmok Streets.

12.	In addition to the above, explain the need and desirability of the proposed activity or development in terms of this Department's guideline on Need and Desirability (March 2013) or the DEA's Integrated Environmental Management Guideline on Need and Desirability. This may be attached to this BAR as Appendix K.
-----	--

In addition to the environmental considerations outlined above, the proposed development aligns with the Department of Environmental Affairs' Integrated Environmental Management Guideline on Need and Desirability, particularly regarding the need and desirability of the project.

Need

- The proposed development addresses the continual and rising demand for housing in the Hermanus, Vermont area. By creating residential erven, the project directly responds to the need for additional housing units.
- With the urban population of Vermont steadily growing, there is an inherent need for expansion and the provision of housing options to accommodate the increasing number of residents.
- The proposed development addresses the continual and rising demand for housing in the Hermanus, Vermont area. By creating residential erven, the project directly responds to the need for additional housing units.
- The development is tailored to meet the needs of first-time homeowners and single families, recognising the diversity in household structures within the community.
- Construction activities and subsequent habitation of the residential erven stimulate economic growth. Job creation during the construction phase and potential expansion of local businesses due to increased population density contribute to the economic well-being of the community.
- The development will contribute to revitalising the urban area, enhancing its attractiveness to both current residents and visitors, in line with the need to improve the quality of life in urban areas.
- The site's on-site wetland and associated Critically Endangered Hangklip Sand Fynbos vegetation currently have no formal, legally binding mechanism securing their long-term protection. In the absence of a regulated development process, there is no comparable means of establishing the conservation servitude and council-approved co-management agreement proposed under this application, which would otherwise leave the site's biodiversity assets exposed to uncontrolled degradation, alien vegetation encroachment, and incremental habitat loss over time.

Desirability

- By locating the development within an existing urban area, the project promotes urban infill, optimizing the utilization of available land within established communities in a sustainable manner.

- Placing residential units within the existing urban fabric improves access to amenities, public services, and transportation, enhancing the overall desirability of the location.
- The creation of residential units fosters social connectivity, contributing to the formation of a cohesive and vibrant community where residents can benefit from shared spaces and community interactions.
- The development also includes the creation of open space, prioritizing the protection of aquatic and terrestrial ecosystems. This further enhances the desirability of the project by preserving valuable natural environments and promoting sustainable land use practices.
- The preferred layout (Alternative 4) reflects the outcome of an iterative application of the mitigation hierarchy through five rounds of public participation since 2023, during which the number of proposed development sites was reduced from an original 13 to 6, avoiding the delineated permanent wetland and confining seasonal wetland infringement to essential access infrastructure only.
- The residual impact of the development on the site's critically endangered Hangklip Sand Fynbos vegetation has been assessed by the appointed botanical specialist as low–medium negative following mitigation, which falls below the threshold for a biodiversity offset under the western cape biodiversity offset guidelines (2023).
- Approximately 9,361 m² of on-site wetland is proposed for formal, long-term protection as a no-go/open space area, to be secured through a council-approved co-management agreement between the Overstrand municipality and the homeowners' association, providing a durable governance mechanism for the site's biodiversity assets beyond what an undeveloped, unregulated site would otherwise have.
- The appointed faunal specialist has confirmed that the retained open space under alternative 4 is adequate to preserve ecological connectivity and support continued faunal movement across the site, consistent with its role within the broader ecological corridor recognised under the Overstrand municipality's environmental management overlay zone (EMOZ).
- A dedicated stormwater management plan has been developed for the site, designed to attenuate and manage post-development runoff and mitigate the risk of altered hydrology, erosion, and downstream flooding within the site's wetland catchment context.
- Taken together, the proposed layout represents a considered response to the site's designation as a critical biodiversity area (CBA1) and ecological support area (ESA2) under the western cape biodiversity spatial plan, achieving avoidance-led design and long-term conservation outcomes for the retained wetland and habitat that would not otherwise be secured in the absence of a regulated development application.

SECTION F: PUBLIC PARTICIPATION

The Public Participation Process ("PPP") must fulfil the requirements as outlined in the NEMA EIA Regulations and must be attached as Appendix F. Please note that If the NEM: WA and/or the NEM: AQA is applicable to the proposed development, an advertisement must be placed in at least two newspapers.

1. Exclusively for linear activities: Indicate what PPP was agreed to by the competent authority. Include proof of this agreement in Appendix E22.
2. Confirm that the PPP as indicated in the application form has been complied with. All the PPP must be included in Appendix F.

Proof of public participation attached hereto, conducted in line with the NEMA requirements.

Five rounds of public participation have been conducted to date. This will be the sixth and final round of public participation conducted on the final round of the Basic Assessment Report.

3. Confirm which of the State Departments and Organs of State indicated in the Notice of Intent/application form were consulted with.

DEA&DP
CAPE NATURE
OVERSTRAND MUNICIPALITY
OVERBERG DISTRICT MUNICIPALITY
BOCMA

4. If any of the State Departments and Organs of State were not consulted, indicate which and why.

N/A


5. If any of the State Departments and Organs of State did not respond, indicate which.

N/A

6. Provide a summary of the issues raised by I&APs and an indication of the manner in which the issues were incorporated into the development proposal.

Name/ Organization	Comments	Response
PUBLIC PARTICIPATION 1		
Petro Steere (I&AP/ Neighbour)	- Properties 1 to 7 lie in the seasonal wetland- not acceptable. - Assumes that the thin blue line on the diagram is the 30m floodline. As I understand it, no building within this line. Only erf 3,4,5,6 and 9 fall outside this line - Erf 9 to 13 are below 600sq m also not acceptable	- Comment regarding seasonal wetland is noted – the Alternative 3 – the new preferred alternative is now assessed and has been informed by specialist input. This alternative avoids sensitive areas to an acceptable impact level - Development within these areas require the applicant to undergo the Environmental Authorisation process, for decision can be taken by the competent authority. Note that the new preferred alternative, Alternative 3, now only contains 9 erven. Previously preferred alternative layout 2 has 13 residential erven and the access road crossed the wetland alongside Lynx Avenue. - The land use parameters are in line with the Overstrand Municipality bylaws and also require a approval process through the municipal town planning processes.
Mary Ann Verster (Hermanus Botanical Society)	- The BAR and Site Verification Report assert that the site is "highly transformed" and lacks indigenous vegetation. - However, this conclusion is made without conducting a formal Plant Species Assessment, which was flagged as a requirement in the Screening Tool Report (page 10). - Without a proper field-based flora assessment, the presence of rare, endangered, or endemic plant species (such as <i>Disa halackii</i>, recently discovered nearby) cannot be ruled out. This omission is seen as a critical flaw, compromising the integrity of the biodiversity assessment. - The preferred development proposal (Alternative 2) places all 12 residential units over areas identified as seasonal or temporary wetlands. - Erven 1 and 8 are 100% overlapped by wetland - Erven 2 and 7 show extensive overlap. - Erven 3–6 show minor but notable overlap. - The site plan likely underestimates the extent of wetland areas, due to:	A Botanical Impact Assessment as well as a full Freshwater Impact Assessment has been conducted. The findings of these studies have led to the evolution of a fourth alternative, with a reduced number of erven, shifted away from sensitive areas on site. Alternative 3 was the previous preferred alternative. A Terrestrial Biodiversity Impact Assessment was prepared, and it covers the plant species theme. A full Wetland Impact Assessment has been undertaken to inform the evolution of alternatives. The findings and recommendations from this study, as well as the Botanical Impact Assessment, has resulted in the evolution of the Final Preferred Alternative which avoids all permanent and seasonal wetlands.

	• Ongoing removal of Eucalyptus trees from the adjacent Hoek van die Berg Nature Reserve, expected to significantly increase water flow into the wetland. • Climate change impacts, specifically more intense storm systems increasing runoff from surrounding mountains. • The only mitigation mentioned is rainwater harvesting schemes which is considered inadequate in light of the site's environmental sensitivity and hydrological context. • The development on these areas may result in serious ecological and infrastructure risks. • The Basic Assessment Report (BAR) refers to the long-term development and management of the wetland as a potential positive outcome of implementing the preferred development proposal (Alternative 2). However, no specific details are provided regarding the proposed wetland management plan, including the methods, objectives, or the entity responsible for its implementation and long-term oversight. As a result, it is not possible to assess the feasibility or likely effectiveness of the proposed wetland rehabilitation and management. • Additionally, the statement on page 32 of the BAR—"Development in close proximity to wetland may pose risks to the wetland, however the status quo is much worse. Opportunity for rehabilitation"—is unclear. The document does not explain what the current "status quo" entails or how rehabilitation will be practically achieved. • The Hermanus Botanical Society suggest that the points raised are serious limitations to the BAR and should be addressed before the EIA is accepted.	Noted Noted. The Wetland Offset Rehabilitation Management Plan was undertaken. As above. A Homeowners Association will be formed, and they will be responsible for the long-term conservation and management of the Wetland area. This will form part of the condition of approval, should it be granted. Onsite Wetland Offset and Rehabilitation has been included in the process. The wetland offset area will be via a conservation servitude. The BAR has been updated inline with the final preferred layout.
Bernadette Osborne (DEADP)	• Clarification is required regarding the legal status of the existing buildings and road on the property prior to submission of the application for Environmental Authorisation.	• The appointed Town Planning consulting on the project investigated the matter at the Overstrand Municipal offices and found that building plans for the existing store were approved in 1994. An amendment to the approved plan was submitted in 2002, to add a Single layer screening wall. The building was therefore constructed pre NEMA.

	• The BAR indicates wetland rehabilitation will take place (page 23), but no details have been provided. A detailed description of this activity must be included • The application must comply with the relevant protocols as published in Government Notice No. 320 (20 March 2020). • The Terrestrial Biodiversity protocol requirements have not been met. A compliance statement or full specialist assessment is required, depending on confirmed sensitivity. • The Freshwater Report does not meet protocol requirements. It must include ecological status, importance and sensitivity of each watercourse, and assess impacts of the proposed development. • A comprehensive Freshwater Impact Assessment Report must be included in the BAR. • Confirmation is needed on whether peat is present in the watercourse and whether it will be removed. This must be confirmed by the aquatic specialist. • The site contains Hangklip Sand Fynbos.	 <table data-bbox="1217 701 1425 813"><tr><td>AB</td><td>80m</td><td>DB</td><td>1550m</td></tr><tr><td>BC</td><td>76m</td><td>DC</td><td>1024m</td></tr><tr><td>CD</td><td>145m</td><td>CE</td><td>1454m</td></tr><tr><td>DE</td><td>139m</td><td>EF</td><td>2440m</td></tr><tr><td>FD</td><td></td><td>FE</td><td>7740m</td></tr></table> • The residential development will be gated and managed through a Homeowners Association. The Freshwater specialist will provide information relating to the rehabilitation and long-term management of the site. • These sections are now amended. The Terrestrial Biodiversity Impact Assessment has been completed. • A Freshwater Impact Assessment has been undertaken in line with the requirements and is attached to the Draft BAR. In addition, a Botanical / Terrestrial Impact Assessment has also been undertaken, this report also speaks to the Animal / Terrestrial theme. The findings of these reports have resulted in the evolution of the layout alternatives. • The Aquatic Biodiversity Impact Assessment Report indicated that peat is not present on the site. • A full Botanical Impact Assessment has	AB	80m	DB	1550m	BC	76m	DC	1024m	CD	145m	CE	1454m	DE	139m	EF	2440m	FD		FE	7740m
AB	80m	DB	1550m																			
BC	76m	DC	1024m																			
CD	145m	CE	1454m																			
DE	139m	EF	2440m																			
FD		FE	7740m																			

	which is classified as Critically Endangered. The loss of this vegetation must be clearly identified and assessed in the BAR. - Sections 4.1 to 4.3 have not been adequately addressed and must be revised to include detailed responses. - Written confirmation from Heritage Western Cape (HWC) must be obtained regarding the requirement for Landscape/Visual, Archaeological, Paleontological, and Cultural Heritage Impact Assessments. - The BAR incorrectly states that the National Water Act is not applicable, despite the presence of wetlands on site. This must be corrected, and input from the relevant water authority must be obtained. - If the applicant is not the landowner, landowner consent must be provided with the final application. - As Activity 19 of Listing Notice 1 is triggered, a Maintenance Management Plan should be incorporated into the EMP to manage future maintenance activities. - Official comment from CapeNature must be obtained and included in the BAR. - Written confirmation is required from the Overstrand Municipality that adequate capacity exists for potable water, effluent, waste, and electricity supply for the development. - Participation Plan and the requirements of Regulation 41 of the NEMA EIA Regulations, 2014, and proof of compliance with all the steps undertaken must be included in the BAR	been undertaken; the impact assessment findings have resulted in the evolution of Alternative 3. - These sections have been amended. - Confirmation from Heritage Western Cape has been received and no further heritage assessment is required. See Appendix F. - Noted. Amended accordingly, NWA is applicable and the Risk Matrix has been completed along with the Freshwater Impact Assessment. Noted. - MMP compiled - Included below. - The Overstrand's Engineers have conducted the services report, as attached under Appendix F (GLS report). The upgrade of the Kolgans sewer pipeline is required and is described in the Basic Assessment Report - Participation Plan and the requirements of Regulation 41 of the NEMA EIA Regulations, 2014, and proof of compliance with all the steps undertaken must be included in the BAR
Cape Nature (Rhett Smart)	- CapeNature has reported the omission of the wetland in the NBA mapping to SANBI. - No terrestrial biodiversity assessment was undertaken, despite the site's classification. Justification that the proposed	A Full Aquatic Impact Assessment as well as a Botanical Impact Assessment has been undertaken and has informed the evolution of Alternative 3 – which is now the preferred alternative. A full Botanical Impact Assessment was undertaken.

	development aligns with surrounding development is not accepted as it does not address biodiversity concerns. Given nearby endangered species (notably on Erf 1492), at minimum, a terrestrial biodiversity and plant species compliance statement is required. • The freshwater screening study functioned as a constraints analysis only. • A full freshwater ecology impact assessment must be conducted to assess the development's potential impacts. • Alternative 2 (with an open space buffer) is preferred over Alternative 1 but is still unacceptable, as several erven encroach on the delineated seasonal wetland. • The layout should be refined to fully avoid the wetland and incorporate specialist recommendations • No details provided regarding service provision (e.g. sewage, roads), which could significantly affect freshwater ecology. • Proper consideration of wastewater impacts and water flow is required. The mitigation hierarchy must be applied. • The BAR incorrectly states that the National Water Act does not apply. • Since the development is within a watercourse, authorisation under the National Water Act is required. • The EIA and Water Use License Application (WULA) processes must be synchronised. • CapeNature does not support the proposed development in its current form. • Support is conditional upon: • A revised layout that responds to identified environmental constraints. • Submission of a freshwater impact assessment. • Submission of a terrestrial biodiversity and plant species compliance statement.	• A Freshwater Impact Assessment has been undertaken and has resulted in the evolution of Alternative 3 – the new preferred alternative. Noted. • This section has been updated. • Proof of Submission is attached as Appendix L. • The new preferred alternative (Alternative 3) removes the access road which cut the link of the wetland between the Lynx Avenue and Erf 1486. • Amended – A full Freshwater Impact Assessment has been conducted as well as a Risk Matrix, this will enable the specialist to apply for the appropriate licenses and / or General Authorizations in line with the requirements of the National Water Act.
Duncan Heard - Vermont Ratepayers Association - (I&AP)	• The EMPr should be embedded in the constitution of the future Homeowners' Association (HoA) as a condition of Environmental Authorisation (EA). • The HoA must be responsible for implementing EA conditions during the operational phase.	• Noted • Noted.

	- The following ongoing management actions must be implemented to protect the wetland: - Prevent ecological degradation of the conserved wetland area. - Monitor water quality entering and leaving the wetland regularly to detect pollution. - Implement an eco-sensitive stormwater management system, including: - Vegetated swales - Polishing ponds - Use of raft foundations for all buildings. - Require permeable paving on all uncovered paved areas.	These recommendations have been added to the Basic Assessment Report and EMP.
Giorgio Lambardi (I&AP)	- The BAR claim that “only very limited areas will be developed” is misleading: - Approximately 65% of the site will be developed, and only 35% retained as open space. - The erf is not “largely transformed” as claimed, and is adjacent to a nature reserve, in a sensitive ecological area. - The required 30m buffer around wetlands is not provided. - Many of the proposed residential erven fall directly within the delineated seasonal wetland: - Example: Erf 8 is 100% within the wetland; others range from 10% to 80% coverage. - No vegetation studies were conducted despite the site falling within Critical Biodiversity Areas and containing Endangered Hangklip Sand Fynbos. - A Plant Species Assessment and Animal Species Assessment were unjustifiably dismissed, rendering the BAR fatally flawed. - A wetland specialist should assess the: - Present Ecological State (PES) - Ecological Importance and Sensitivity (EIS). - Specific threats to wetland health.	- A Freshwater Impact Assessment as well as a Botanical Impact Assessment have been undertaken and have resulted in the evolution of a new preferred Alternative – Alternative 3. The alternative sees a reduction in the number of erven, reduced encroachment into the erven, realignment of access roads to avoid the wetland area and sensitive botanical areas on site. - A 32m buffer around the wetland is provided. - A new preferred layout alternative has evolved in line with specialist impact assessment findings. - A Terrestrial Biodiversity Impact has been undertaken. - Terrestrial Biodiversity Impact which involved the plant species theme was undertaken. - The Aquatic Biodiversity Impact Assessment undertaken had assessed all these.
Whale Coast Conservation (I&AP)	- Discrepancies exist between the site plan (dated 14 March 2019) and the BAR regarding the areas of subdivided erven, despite the total area aligning. - The BAR’s claim that only “very limited areas” will be developed is misleading, as 65% of the site is proposed for development	The new layout design ensures that the developable erven are outside the identified seasonal/temporal zones, with the areas encroaching on the seasonal/temporal wetland areas will remain as a No-go conservation area.

	(single residential: 34%, town housing: 11%, private road: 20%), with only 35% retained as private open space (wetland area). • The BAR incorrectly states that internal access is mostly in place, omitting the existing gravel road from the site plan. • Misleading descriptions portray the site as within a “built-up residential suburb” despite its location at the north-western edge of Vermont, adjacent to a nature reserve, and as “largely transformed and impacted” despite minimal disturbance beyond a derelict building and gravel road. • Two design proposals (dated 14 March 2019) were generated, with Alternative 1 deemed environmentally unviable and Alternative 2 claimed to consider the wetland system but lacking detailed rehabilitation or management plans. • The BAR understates the impact on the seasonal/temporary wetland, with 12 residential stands encroaching on it to varying degrees, contrary to claims of minimal impact. • The BAR’s cursory treatment of climate change ignores increased runoff from stronger storms, which will expand the seasonal wetland, affecting the proposed layout. • The Freshwater Screening Study (FSS) by EnviroSwift (2018) is outdated, relying on a 2006 study and a single-day site visit, failing to account for dynamic wetland boundaries influenced by surrounding conditions. • The FSS’s restriction to Erf 1486’s boundaries ignores the impact of alien invasive vegetation (AIV) clearance in the adjacent Hoek van der Berg Private Nature Reserve, which will significantly increase the wetland’s extent due to reduced water consumption by eucalyptus trees (200–1000 liters/day per tree).	• The existing access road has been referred to in the BAR. • The property is located within the designated urban edge of Vermont and forms part of the broader residential planning context for the area. While the site occurs along the north-western edge of the suburb and adjacent to a nature reserve, it remains surrounded by existing residential development and associated infrastructure and is therefore not considered isolated from the built-up environment. • In terms of site condition, the description of the property as partially disturbed remains applicable. Existing disturbances include the presence of a derelict structure, an internal gravel access road, areas historically affected by clearing activities, and the spread of alien invasive vegetation in portions of the site. These features indicate that the site has not remained entirely pristine. • Noted. • Notwithstanding these external restoration initiatives, the wetland delineation on Erf 1486 reflects the best available site-specific information at the time of the specialist investigation. The delineated wetland and associated buffer areas informed the refinement of the preferred layout, which seeks to avoid permanent wetland areas and conserve the majority of seasonal and temporary wetland habitat through the designation of no-development areas, open space management, and long-term protection measures. The Environmental Management Programme (EMPr), Maintenance Management Plan, and Wetland Offset and Rehabilitation Plan collectively provide mechanisms for adaptive
--	---	---

	• The FSS incorrectly asserts the wetland originates on Erf 1486, whereas it is part of a larger system originating at Paddavlei in Hawston, with historical seasonal overflows affecting wetland dynamics. • The central wetland depression is described as “excavated” without evidence, despite soil and vegetation indicators suggesting a natural feature. • The FSS underestimates the wetland’s extent, likely to increase due to AIV clearance and planned rehabilitation of nearby Paradise Park, rendering the delineation unreliable. • The BAR dismisses the applicability of the National Water Act (NWA) and National Environmental Management Biodiversity Act (NEM:BA), despite the erf’s location within a 500m wetland buffer and Critical Biodiversity Areas (CBAs). • The “no net loss” wetland policy and the need for an Environmental Authorisation due to disturbance within 32m of a watercourse are ignored. • No consideration is given to the 100-year floodline or increased runoff risks from climate change-induced storms. • The BAR falsely claims the site is “highly transformed” without a vegetation study, ignoring the presence of indigenous hydrophytic plants (e.g., <i>Juncus kraussi</i>, <i>Cyperus textilis</i>) and the discovery of an endangered orchid (<i>Disa halackii</i>) on a nearby similar site. • The site, within Critically Endangered Southwest Sand Fynbos and an aquatic Ecological Support Area, is surrounded by CBAs and a nature reserve, and development will compromise ecological functioning. • The Vermont Pan, part of the larger wetland system, is already impacted by insensitive development, and this proposal will exacerbate water flow and habitat issues. • No corridor for flora and fauna movement is provided, despite claims, as the proposed open space will be under housing. • The wetland delineation is fatally flawed due to its reliance on a single-day	management should wetland conditions change over time as a result of landscape-scale rehabilitation and alien clearing in adjacent areas. • Noted. Refer to the Stormwater Management Plan which included analysis of the runoff. • A full Freshwater Impact Assessment has been undertaken in line with both the NEMA and NWA requirements. • A Botanical Impact Assessment and a Freshwater Impact Assessment have been undertaken and have resulted in the evolution of the alternative, Alternative 3. • Rehabilitation and protection of sensitive areas on private land requires funding and management, the Home Owners Association will be tasked with the long-term management of the wetland area, guided by specialist input and conditions of the Environmental Authorisation – should it be granted. • As per the requirements of NEMA and
--	---	--

	assessment and failure to account for AIV clearance impacts, rendering the proposed layout void. - Dismissal of specialist studies and legislative requirements is unjustified and flimsy. - The BAR is poorly prepared, with inaccuracies, misinformation, and bias, suggesting a tick-box exercise rather than a rigorous assessment. - WCC suspects the proposal may seek approval to later demand wetland drainage, violating environmental protections. - WCC recommends rejecting the BAR and denying authorization for the development due to its significant environmental risks and inadequate assessment.	NWA, a full Freshwater Impact Assessment has been undertaken and is attached in the revised BAR – the findings of this report has resulted in the evolution of a new preferred alternative - The Botanical and Freshwater Impact Assessments have resulted in the evolution of a new preferred alternative – Alternative 3. - As above, - The BAR has been updated and amended in line with updated specialist input. - The report has been revised and updated in line with the new Specialist impact assessment reports. An Additional pre-application public participation is provided for prior to the in- process public participation commences. This is to ensure that issues and concerns are adequately addressed before initiating the in- process applications.
Michael Raimando - <i>Director of UVA Properties</i>	- Fully Supports the comments raised by the Whale Coast Conservation and Vermont Conservation Trust. - Raised the concern regarding the clearance of alien vegetation along the R43 and in the adjacent property (Hoek van Der Berg Private Nature Reserve). - UVA Properties opposes any further development on Erf 1486, as it will adversely affect the wetland system, particularly given the anticipated expansion due to ongoing invasive plant removal.	Noted. No further actions required.
Dennis Brandjes (I&AP)	- Properties 1 to 7 lie in the seasonal wetland. This is not acceptable. - Assume the thin blue line on the diagram is the 30m floodline. As we understand it, no building within this line. Only erf 3,4,5,6 and 9 fall outside this line. - Erf 9 to 13 are below 600sqm in size. This is not acceptable. - I failed to see the biodiversity report – as I believe that there is protected aquatic and other life forms dependant on the salt pan water mass.	The newly conducted Botanical Impact Assessment and Freshwater Impact Assessment Reports have resulted in the evolution of the preferred alternative and the creation of a new preferred alternative being Alternative 3.

Samantha Hogg-Brandjes (I&AP/Neighbour)	Opposed to the proposed development for the reasons related.	Noted.
Fabion Smith – BOCMA (Organ of State)	- The Freshwater Screening Study by EnviroSwift (dated 20 August 2018) does not include a Risk Matrix, which is essential for assessing the proposed development's impact on water resources. - Due to the absence of a Risk Matrix, BOCMA is unable to offer specific guidance or direction on the proposed development. - Almost the entire site/study area of Erf 1486 falls within 500 meters of a regulated area, as defined under relevant water resource management regulations, including the layout proposed in the preferred Alternative 2 (dated 14 March 2019 by Interactive Town and Regional Planning). - BOCMA advises that a Risk Matrix for the proposed development be submitted to enable a concise and precise assessment, after which specific feedback can be provided. - BOCMA notes the concerns raised by Cape Nature in their email dated 24 April 2023, indicating alignment with other stakeholders' apprehensions regarding the development.	A full Freshwater Impact Assessment and Risk Matrix is now included in the Basic Assessment Report. Noted. Noted. Noted. Concerns raised by Cape Nature have been addressed in the updated BAR.
PUBLIC PARTICIPATION 2		
Samantha Hogg (I&AP)	Opposes to the proposed development	Noted.
Michael Raimando (I&AP)	- Requested information about the servitude - Highlighted that it is against the urban law to build 2m from the perimeter of the fence.	Noted. No further actions required.
Rob Crank (I&AP)	Telephone call received in support of the proposed development on Erf 1486 Vermont	Noted. No further actions required.
Peter Hodgskin (I&AP)	Requested a copy of the BAR	Information sent, no further actions required.
Paul Pfister (I&AP)	Not comfortable having his email address distributed in public.	Noted.
Marleine Badenhorst (I&AP)	Requested to be informed about the development as a neighbour.	Noted. No further actions required.
Denis Branjies (I&AP)	Requested documentations	Information sent, no further actions required.
Paul Verhoef and Janice Yvonne Verhoef	Requested to be included in the I&AP list	Registered as I&AP

(I&AP) Rulien Volschenk – <i>Overberg District Municipality</i> (Organ of State)	• ODM supports the preferred layout as it promotes the protection of a wetland system.	Noted. No further actions required.
Paul Slabbert <i>PHS Consulting</i> (I&AP)	• Advised that the development should only be on the current development footprint and that the rest of the site should be restored as a functional ecological corridor. • A 2006 Freshwater Consulting Group (FCG) study for Overstrand Municipality delineated wetland boundaries and buffers, recommending a minimum 30m buffer to limit development and protect wetlands (Figure 2). • Provided comment that the Aquatic Assessment report recommended that the	• It should be noted that the layout design (Alternative 3) excluded development in areas that are situated outside the seasonal/temporal wetland areas. Therefore, the plan is to include the No-go area in the undevelopable areas. • Freshwater specialist response: <i>“The previous studies are noted. It is the specialist’s recommendation that the single residential dwellings within the northern subdivided Erven should avoid the delineated wetland as far as possible, as per recommendations in the Aquatic Impact Assessment Report (Delta Ecology, 2023), and implement all listed mitigation measures in the report, including SW management and implementation of a Rehabilitation and Management Plan for the onsite wetland area. Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 1) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings).</i> <i>The wetland area coinciding with the proposed southern Erven (to be zoned for town housing) (adjacent to current housing along the southern boundary) (Figure 1), will likely encroach on approximately 255 m2 of the seasonal wetland area. This is considered acceptable, considering the Rehabilitation, appropriate Management and Protection of the remnant onsite wetland as an Offset, by the Homeowners Association (HoA or similar).”</i> Freshwater Specialist response: <i>“Agreed, future development inside the urban edge that are located along the slopes of the mountains should</i>

	future development inside the urban edge that is located along the slopes of the mountains should include provisions to ensure a natural delivery of water via natural drainages. Also added that this should be supported by the specialist investigation looking at both the impacts within the site as well as the impacts this might have on the identified wetlands in the larger area. • A 2008–2010 Basic Assessment process for a previous development application on Erf 1486 lapsed due to wetland extent restrictions, with FCG (2008) deeming the site unfit for development expansion beyond the existing footprint (Figure 3). • A 2012 FCG study for the approved Hoek van de Berg development (RE/572) confirmed Erf 1486's wetland as part of an extensive <i>Juncus cf. krausii</i> valley-bottom wetland, linked to Paddavlei (Hawston) and Vermont Pan, fed by surface and subsurface flows (Figure 4). • The 2012 study noted alien vegetation	<i>include provisions to ensure a natural delivery of water via natural drainages. In the Delta Ecology Report (2023), the onsite wetland was rated to be of Moderate to Moderately High Functionality / Ecological Importance and Sensitivity (EIS) largely due to the hydrological connection to downstream wetland areas of importance (including the Vermont Salt Pan). The historical wetland vegetation type (Southwest Sand Fynbos) is also Critically Endangered (CR) and therefore the specialist supports the Rehabilitation of the wetland to an improved ecological state.</i> <i>In terms of natural drainages, there is an overflow pipe which crosses beneath Lynx Road and flows into the wetland on the far side, creating a hydrological link between the wetlands within the study Erf, and the greater wetland to the southeast. The Delta Ecology Report (2023) has been updated to recommend that the status quo in terms of hydrological connection to the downstream system must be maintained / should not be impacted as a result of the proposed development.</i> <i>During the specialist assessment, it was determined that given the implementation of the recommended mitigation measures, there should not be any impact on the wetland system downstream, as a result of the proposed development.</i> <i>There may potentially be a slight increase of flow due to the hardened surfaces as a result of the housing development. This is seen to be of "Low significance" to the onsite wetland, given the implementation of mitigation measures such as implementing rainwater harvesting schemes that may reduce runoff intensity, and mitigate the potential impact of catchment hardening.</i> <i>To ensure the implementation of recommendations in the Aquatic Impact Assessment Report (Delta Ecology, 2023), the report has been updated to specify that an Aquatic Ecologist must be consulted during the design of the onsite Residential Dwellings and Town Housing unit, and an Environmental Control Officer (ECO) should be appointed during the Construction of the Town Housing development in the south."</i>
--	--	---


	(<i>Acacia saligna</i>, <i>Eucalyptus</i> spp.) reduced functional wetland area through droughting and shading, with remnant vegetation indicating a potential mixed estia/sedge/grass community. • The 2012 study recommended a groundwater study to assess aquifers, groundwater flow, and sub-catchment boundaries (e.g., Sub-catchment C1) to determine appropriate wetland setbacks and impacts (Figure 5). • In August 2018 EnviroSwift study delineated the wetland on Erf 1486 based on saturated soils and hydrophytic vegetation, acknowledging the outdated 2006 delineation but not clarifying how southern housing developments altered the wetland (Figure 6). • EnviroSwift concluded that development within the wetland would likely require a Water Use Licence Application (WULA) and wetland offset scheme (high risk), adjacent development would require a WULA (medium/high risk), and development with a buffer zone would have low/medium risk requiring registration or a WULA. • A November 2023 Delta Ecology study confirmed an Unchanneled Valley-Bottom (UVB) wetland, with the proposed layout minimizing overlap but still requiring a WULA and wetland offset/rehabilitation plan due to moderate risk from limited wetland loss and degradation. • The Delta Ecology report concludes that the proposed layout has gone through alterations, however, wetland loss will fall within high Category	• Freshwater specialist response: <i>“Previous studies and outcomes are noted. Flow on Erf 1486 was noted to be in a south easterly direction during the site assessment (Delta Ecology, 2023), flowing through the outlet beneath Lynx Road.”</i> Freshwater specialist response: <i>“Wetland boundaries may vary with time, and it is noted that the housing development to the south (built 2007 – 2012) may have resulted in additional stormwater input within the Erf 1486. There is a SW outlet located in the southeastern corner of the Erf 1486, which discharges runoff from the southern housing development into the wetland on Erf 1486, as noted in Figure 2 of the EnviroSwift screening study in 2018. This, in combination with varying climate conditions from year to year could account for the slight increase in delineation extent during the 2023 assessment.”</i> Freshwater specialist response: <i>“Delta Ecology (2023) reiterated the results of this screening assessment done by EnviroSwift in 2018. Due to the development within the wetland being of minimal extent (encroachment on approximately 255 - 500 m2 of the seasonal wetland area); the Rating was determined to be of Medium Significance and would require a full WULA and a Wetland Offset, Rehabilitation, and Management Plan.”</i> Noted. Noted. A stormwater management plan was compiled and includes the calculations of the stormwater runoff before and after construction of Erf 1486
--	---	---

	• Suggested that appropriately raft foundations may significantly reduce the impact on subsurface flow and therefore reduce risk. • Rainwater harvesting schemes that may reduce runoff intensity and thereby mitigate the impact of catchment hardening. • Stormwater polishing infrastructure such as artificial wetlands that may mitigate water quality impacts • The Delta Ecology report concluded that the proposed layout has been revised multiple times to minimize overlap with the delineated wetland. While wetland loss typically carries a high impact rating, the small extent of loss and the degraded condition of the wetland have reduced the overall significance of the impact. • The narrative of the studies conducted since 2006 and the next to erf 1486 stipulates that there is a critical ecological link corridor and that impacts on the large wetland area must be considered. The surface and subsurface waterflow from the west to east passing through erf 1486 was noted. • Highlights that the report states that the wetland boundaries do vary with time clearly depicted in the change in delimitation over the years most probably due to manmade intervention like stormwater additions, further infilling after	• Freshwater specialist response: <i>“Delta Ecology (2023) reiterated the results of this screening assessment done by EnviroSwift in 2018. Due to the development within the wetland being of minimal extent (encroachment on approximately 255 - 500 m2 of the seasonal wetland area); the Rating was determined to be of Medium Significance and would require a full WULA and a Wetland Offset, Rehabilitation, and Management Plan.”</i> • Freshwater specialist response: <i>“The Delta Ecology report (2018) has been updated to specify that an Aquatic Ecologist should be consulted during the design specifications of the Residential Dwellings and Town Housing unit on the site, and an ECO should be appointed during the Construction of the Town Housing development in the south. The stormwater management plan must take into account the recommendations from the aquatic specialist reports, both the EnviroSwift Screening (2018) and the Delta Ecology (2023), specifically relating to the design of SW outlets to minimize erosion and water quality” impairment within the wetland.”</i> • Additionally, to the above, it is important to note that raft foundations have been included in the report as recommendations. • Freshwater specialist response: <i>“The most recent layout (Figure 1) has been amended to include a larger private open space area (conserved wetland area). The private access road now does not need to cross the wetland, as there will now be two access roads instead of one.”</i> • Freshwater Specialist response: <i>“The comment is acknowledged, and it is recommended that changes in the wetland boundary should be monitored by the HoA. The recommendation to monitor the potential expansion in the</i>
--	---	---

	2006, run-off from the mountains, floods and alien clearance. It is questioned how the wetland boundaries are likely to change in future. • Notes that there is alien clearing programme taking place in the Hoek van der Berg Nature Reserve, which included the clearance of the wetland area in the northeast corner of the nature reserve. They added that the tempo and volumes of water feed need to be considered after alien removal. • They made observations on RE/572 and noted that the water level in the wetland has drastically increased as per photo evidence below, due to the reduction of alien vegetation. • Notes that the most recent wetland studies haven't considered the increase in wetland run-off and feed from RE/572 to the Vermont Pan due to the current alien clearing efforts. • Neither has the additional run-off from the mountains been considered where additional clearing of alien vegetation is taking place and directly north where landowners will be forced to clear aliens. • On the RE/572 site the wetland area already expanded as per photo 3, 4 & 5 below. This extend will have a direct impact on the wetland extent on erf 1486 and it's likely the site will become wetter in future. This coupled with climate change and extreme events occurring more frequently, more surface and sub-surface flow will originate from catchment C1. • The BAR has not considered the changing circumstances in particular the effect of alien clearance and climate change on the proposed development. • Advised that all residential erven be located outside the seasonal wetland to avoid development impacts on the ecosystem. • Recommended that a geohydrological/hydrological/hydropedology study in conjunction with a stormwater	onsite wetland boundary overtime will be included in the Wetland Management Plan. However, as per the above comment, the change in flow regime to the wetland due to the proposed development will be minimal and can be adequately mitigated. The scope of the recent studies (specifically EnviroSwift, 2018 and Delta Ecology, 2023), included assessment of the present state of the onsite wetland to be potentially impacted by the proposed development, and the impacts of the proposed development. Assessing activities, and the potential impacts thereof, undertaken on adjacent land was not the scope or aim of the Aquatic Impact Assessment Report (Delta Ecology, 2023)." • Freshwater specialist response: <i>"The specialist agrees that there is potential need for a hydrological assessment to determine the impact of clearing AIS on Hoek van de Berg Nature Reserve on the downstream wetland system."</i> <i>It is questioned whether the entity undertaking the AIPS clearing is not responsible for assessing potential impacts that may occur as a result of the clearing, such as increased flow to downstream land. There are many landowners downstream that could be affected if increased flow does occur, not only the property immediately downstream."</i> • <i>The Delta Ecology (2023) report's scope does not include assessing the potential impact of climate change, adjacent changes in land use, or any other potential catchment transformation that may occur in the future; and how (if applicable) the boundary of the wetland will change as a result of such changes. The report has been updated to include this exclusion in the Limitation Section 1.2. of the report (Delta Ecology, 2023)."</i> • Freshwater specialist response: <i>"The comment is acknowledged, and it is recommended that changes in the</i>
--	---	--

	master plan be conducted to inform the freshwater impact assessment in order to understand what the impacts of the increase in surface and subsurface water flow will have on the system and in specific the wetland on erf 1486. A development alternative should be presented and assessed as part of the process that avoid the CE vegetation and the seasonal wetland areas completely. UVA does not support the development in its current format until the required additional studies are conducted.	wetland boundary should be monitored by the HoA. The recommendation to monitor the potential expansion in the onsite wetland boundary over time will be included in the Wetland Management Plan.” - Freshwater specialist response: “However, the scope of the recent studies (specifically EnviroSwift, 2018 and Delta Ecology, 2023), included assessment of the present state of the onsite wetland determined to be At-Risk of the proposed development, and subsequently the potential impacts of the proposed development on this wetland.” - Noted
Paul Pfister (I&AP)	- The “activities” referred to do not indicate the intentions of the proposed developer regarding the dwellings, outbuildings, entrance and exit routes et etcetera. - Given the following it was considered that there should be no additional development other than that of the existing footprint: - Consideration should be given to the fact that since the development application by the previous owner, the wetland area has extended substantially; - It is also essential that any development and Environmental Authorization (EA) of the proposed nature should form part of a Home- owner’s Association (HOA) or Sectional Title constitution. In this way the significance of the wetland and the conservation thereof would be maintained;	- Noted. The description states that the proposed development is the establishment of residential development which will include the single residential dwellings and town housing. - Noted. - The conservation of the wetland area through an establishment of a conservation servitude in this area will be included as a condition of authorisation.
Denis Brandjes & Samantha Hogg-Brandjes (I&AP)	- Highlights from their previous comments below concerns have been addressed: - Properties 1 to 7 are situated in the seasonal wetland, which is deemed unacceptable. - Concerns are raised regarding buildings within the 30m floodline, with only erf 3, 4, 5, 6, and 9 falling outside this line. - Erven 9 to 13 are below 600sqm in size, which is considered unacceptable. - Request for the inclusion of a biodiversity report, highlighting potential protected aquatic life forms dependent on the salt pan water mass.	Noted.

	Notes that their concerns relate to the wetland and the fact that RE/572 through to erf 1486 has and is enlarging since the initial reports of March 2023 and sites inspections of mid-2023, based on their observations seasonal wetland floodline was apparent for some time after the floods. This relates specifically to your proposed development of Erf 7,8 & 9 of 'APP B3 Development Proposal Alternative Four Final Preferred'. If developed, these erven will severely impact and be impacted by the enlarging wetland.	- The layout (Alternative 3) was specifically designed to avoid development within the permanent wetland area and to minimize intrusion into the seasonal/temporary wetland zones. While portions of Erven 7, 8, and 9 are located near the edge of the mapped seasonal wetland, development within these erven will be strictly confined to areas outside the delineated wetland boundary. Furthermore, these wetland-edge zones have been designated as no-go areas, meaning they will not be disturbed during construction or occupied by any built infrastructure. In addition, a Wetland Offset and Rehabilitation Management Plan has been developed to guide mitigation efforts, which includes the restoration of degraded wetland areas and measures to ensure long- term protection of the wetland's ecological function and connectivity, including with the Vermont Salt Pan. - Furthermore, a Stormwater Management Plan has been compiled and will be implemented to ensure that post- development runoff is appropriately managed. This plan is designed to mimic the natural hydrological regime, attenuate stormwater flow, and prevent any adverse impacts on the adjacent wetland areas, particularly during extreme rainfall events. The plan aligns with the principles of Low Impact Development (LID) and includes mitigation measures such as placement of Permeable Paving System as well as Enhanced swales, and controlled discharge points to protect downstream watercourses and the Vermont Salt Pan.
--	--	--

Bernadette Osborne DEADP (Organ of State)	Confirmation is required as to when the buildings and road were developed on the site. Furthermore, the width and length of the road and as well as the use and footprint of the existing buildings must be confirmed. Confirmation is also required whether the buildings were developed within or within 32m of a watercourse.	- The appointed Town Planning consulting on the project investigated the matter at the Overstrand Municipal offices and found that building plans for the existing store were approved in 1994. An amendment to the approved plan was submitted in 2002, to add a Single layer screening wall. The building was therefore construction pre NEMA and the screening wall did not trigger any listed activities in terms of NEMA. See Appendix F.  - Clarity must be provided regarding the sewer pipe in Kolganns Street and whether the replacement of the pipeline will also trigger Activity 19 of Listing Notice 1. Additionally, a freshwater impact assessment must be updated to include impacts associated with the sewer pipeline. - It is noted that the activity description does not include details of the width and length of the private roads. The applicability of Activity 24 of Listing Notice 1 and/or Activity 4 of Listing Notice 3 must be confirmed and the activity description must be updated to include the details of the road. - Written confirmation from the Overstrand Municipality is required that sufficient, spare, unallocated capacity is available for potable water supply, effluent management and waste management - Three layout alternatives and the no-go alternative is therefore considered. The preferred layout alternative should therefore be included as Layout Alternative 3 - Confirmation from the Department of Water and Sanitation ("DWS") / Breede-Olifants Catchment Management Agency
	- Refer to Section E.10 of the BAR. An aquatic Biodiversity Impact Assessment was updated. - This was amended. The preferred layout alternative is now referred to as Alternative 3 (Preferred). - The proposed development includes two private roads of approximately 180m and 75m length, each with a width of 8 metres (inclusive of the road reserve), situated entirely within an urban area. - GLS Report is attached. - This has been amended. - A comment was received during public participation phase. A Water Use License	

	("BOCMA") must be obtained as to whether a general authorisation or a water use license application in terms of the National Water Act, 1998 (Act No. 36 of 1998) is required • Comment must also be obtained from BOCMA regarding the development within and within 32m of a watercourse. • Since Activity 19 of Listing Notice 1 is triggered, and future maintenance related work may be required, the Department recommends that a Maintenance Management Plan ("MMP") forms a component of the Environmental Management Programme ("EMPr"). • Comment must be obtained from CapeNature regarding the revised layout.	is required. • Comment was received during the first round of public participation and will be notified during the In process public participation. • An MMP is incorporated into the EMP. • Cape Nature's comment is attached herein.
Penelope Aplon <i>Overstrand Municipality</i>	• The proposed site layout Alternative 3 is supported as it enables the least disturbance to the delineated wetland footprint on the development site. • It is recommended that the mitigation measures proposed in the Aquatic Biodiversity Impact Assessment, table 10 -2 Summary of impact/risk assessment results (with mitigation), should be implemented • If an EA is issued, the developer must inform the Environmental Management Section regarding the appointment of the onsite ECO, as per the Construction EMP and Operational EMP. • The applicant should give an indication of when a rehabilitation plan will be drawn up and implemented. • It is advised that the expertise of WCC be drawn upon for the search and rescue of chameleons on site.	• Noted. • Noted. • Noted. • The wetland Offset, rehabilitation and management plan was compiled and is attached. • Noted. Search and Rescue will be undertaken onsite prior to construction, and this mitigation is included as a condition of authorisation

Rhett Smart Cape Nature	• No explanation is however provided for the change in the delineation of the extent of the wetland between the screening study and the impact assessment. • Further clarification is therefore required regarding the revised wetland delineation and should take into account the likely wetland extent once alien clearing on adjacent properties is complete • Several impacts associated with the proposed development were identified in the aquatic biodiversity impact assessment for which the impact significance was identified as low- medium negative or less except for the loss of wetland habitat for which the impact was rated as medium negative. No mitigation measures were identified for this impact. • Recommended that group housing/townhouse complexes should only be considered on erven which have no encroachment into the wetlands. • Motivation will need to be provided as to why it is not possible to avoid the loss of wetland why this is not feasible and a wetland offset must be implemented in accordance with the wetland offset best practice guideline. • CapeNature recommends that a wetland offset plan is required in accordance with the wetland offset guideline. The wetland offset calculator must be used to determine the offset requirements which may require actions on wetland off-site. In this regard we wish to recommend that the broader wetland system stretching westwards from Vermont Pan to beyond Erf 1486 must be taken into account. • Recommended that regardless of whether an offset is implemented or not, the management of the open space area needs to be addressed as part of the application, including management of alien invasive species, prevention of pollution of the wetland.	• Freshwater specialist response: <i>“Wetland boundaries may vary with time, and it is noted that the housing development to the south (built 2007 – 2012) may have resulted in additional stormwater input within the Erf 1486. There is a SW outlet located in the southeastern corner of the Erf 1486, which discharges runoff from the southern housing development into the wetland on Erf 1486, as noted in Figure 2 of the EnviroSwift screening study in 2018. This, in combination with varying climate conditions from year to year could account for the slight increase in delineation extent during the 2023 assessment.”</i> • Freshwater specialist response: “Comment is noted. Further investigation will be conducted of full avoidance of both the permanent and seasonal/ephemeral wetland for the residential erven; • All the developable areas will be outside of the seasonal and wetland areas, however, areas encroaching on the wetland will be regarded as a no-go area and this will be added as a condition of authorisation. • Freshwater specialist response: <i>“Comment is noted. Should the offset calculator show that the onsite offset is not adequate, the broader wetland system must be taken into account.”</i> • The mitigation hierarchy process was followed, based on the extent of the wetland onsite, it is not possible to avoid the avoid the loss of the wetland. However, the Wetland Offset, Rehabilitation Management Plan was compiled and will mitigate the impact and promote positive outcome for the rehabilitation of the open space area.
------------------------------------	---	--

Pat Miller Whale Coast Conservation (Organ of State)	• The environmental context of erf 1486 has now changed. The most important changes are: ○ wetlands now have legal protection, ○ the adjacent property on the western boundary which is now a registered private nature reserve is removing all of its very many AIPs. ○ Climate change is no longer a future probability, but is affecting rainfall patterns in the area and will have a marked impact on the wetland • With regard to the first contextual change, it is unlikely that the OM would have been able to approve the land encompassing the wetland system for sale should it have wished to do so now. The fact that it was able to do in the past and accept development that has harmed the wetland system does not mean that this pattern can or should continue. The extent of the wetland system and its manifestation on erf 1486 has naturally been affected by these harmful developments that have included infilling and drainage infrastructure.	• Freshwater specialist response: <i>“The most recent layout (Figure 1) has been amended to include a larger private open space area (conserved wetland area). The private access road now does not need to cross the wetland, as there will now be two access roads instead of one.</i> <i>It is the specialist’s recommendation that the single residential dwellings within the northern subdivided Erven should avoid the delineated wetland as far as possible, as per recommendations in the Aquatic Impact Assessment Report (Delta Ecology, 2023), and implement all listed mitigation measures in the report, including SW management and implementation of a Rehabilitation and Management Plan for the onsite wetland area. Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 1) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings).</i> <i>The wetland area coinciding with the proposed southern Erven (to be zoned for town housing) (adjacent to current housing along the southern boundary) (Figure 1), will likely encroach on approximately 255 m2 of the seasonal wetland area.</i> <i>Due to the encroachment within the wetland being of minimal extent (approximately 255 - 500 m2 of the seasonal wetland area); the Rating was determined to be of Medium Significance and would require a full WULA and a Wetland Offset, Rehabilitation, and Management Plan.</i> <i>This is considered acceptable from our perspective, considering the Rehabilitation, appropriate Management and Protection of the remnant onsite wetland as an Offset, managed by the Homeowners Association (HoA or similar). The wetland will need to be managed in such a way to ensure that it maintains an appropriate Ecological State, ideally an improved condition from its current</i>
---	--	--

	• With regard to the second contextual change, work has continued apace on AIP removal from the property adjacent to the west. AIP removal close to the boundary with erf 1486 has resulted in the predicted re-emergence of a wide wetland area following the course of the larger wetland system. The area correlates with the area determined in the 2006 study, extending on the north to the R43 and thus would completely encompass erf 1486. • Many AIPs on the adjacent property remain and are targeted for removal, thus this process of wetland re-establishment can be expected to continue. The predicted impact on the wetland on erf 1486 noted in WCC's previous comment has indeed materialised, and an increase in wetland area from the initial BAR comment to the present is already very evident. • With regard to the third contextual change, climate change predictions are that although the area will become drier, it will experience more frequent and more violent storms. The Overstrand is already experiencing the disruptive effects of these changing weather patterns, most recently (September 2023) with disastrous consequences for both public and private infrastructure. In this context, natural systems for dispersing this increased intermittent flow of water (both surface and sub-surface) become vitally important and their protection is essential. • The Aquatic Biodiversity report concluded that the impact of the proposed revised development layout would be minimal and that the limited area of loss of a degraded wetland reduces the significance of this impact. It confirms that a Water Use Licence will be required as well as an offset and is of the opinion that the rehabilitation of the remnant wetland on the site, as well as a rehabilitation and management plan for it, will suffice for this. However, WCC disputes this conclusion.	state.” <i>Freshwater specialist response: “The Delta Ecology (2023) report’s scope does not include assessing the potential impact of climate change, adjacent changes in land use, or any other potential catchment transformation that may occur in the future; and how the boundary of the wetland will change as a result of such, should this occur. The report has been updated to include this exclusion in the Limitation Section 1.2. of the report.</i> <i>The scope of the recent studies (specifically EnviroSwift, 2018 and Delta Ecology, 2023), included assessment of the present delineation and state of the onsite wetland determined to be At-Risk of the proposed development, and subsequently the potential impacts of the proposed development on this wetland.”</i> • Freshwater specialist response: “The Delta Ecology (2023) report’s scope does not include assessing the potential impact of climate change, adjacent changes in land use, or any other potential catchment transformation that may occur in the future; and how the boundary of the wetland will change as a result of such, should this occur. The report has been updated to include this exclusion in the Limitation Section 1.2. of the report. <i>Freshwater specialist response: “The scope of the recent studies (specifically EnviroSwift, 2018 and Delta Ecology, 2023), included assessment of the present state - and therefore present delineation of the onsite wetland - to be potentially impacted by the proposed development, and the impacts of the proposed development.”</i> <i>Freshwater Specialist response: “The scope of the Aquatic Impact Assessment deals with the proposed development at hand. Should there be additional Water Use activities proposed at a later stage by the developer, these would need to be assessed as and if necessary, by a separate application presumably.”</i>
--	---	---

	- It is highly probable that if permission is granted the developer will introduce drainage systems that will divert this flow away from the property. - It must be borne in mind that the currently manifest boundaries of the wetland on site have been drastically affected by past interference in order to construct the now derelict buildings. This interference has naturally also affected and degraded the vegetation markers. The true extent of the wetland on site and the larger wetland system of which it is a part could only be determined were these to be removed and a few seasons allowed to pass for stabilisation before measuring. However, in the context of climate change and its inevitable effect on the water flow through the system, determining the boundaries with any level of accuracy will be challenging. - Minor changes have been made to the layout of the development and to some of the specialist studies undertaken for the original BAR. However, the proposal continues to assume that the context of the site will remain as it was when the necessary specialist studies were undertaken for the original BAR. WCC still contends that this is not the case.	- Freshwater specialist response: <i>“The scope of the recent studies (specifically EnviroSwift, 2018 and Delta Ecology, 2023), included assessment of the present state - and therefore present delineation of the onsite wetland - to be potentially impacted by the proposed development, and the impacts of the proposed development.”</i> - Alternative 3 addressed the site specific features of concern in the project areas, including the existing ecological link, marked as an open space on the layout to allow ecosystem connectivity.
PUBLIC PARTICIPATION PROCESS 3		
Overberg District Municipality <i>(Organ of State)</i>	- The ODM fully supports and actively promotes the rehabilitation plan of environmentally degraded areas. In this regard, the proposed wetland rehabilitation plan is welcomed and strongly endorsed, as it aligns with the ODM’s commitment to restoring ecological integrity and enhancing biodiversity. - Layout 3 is considered the most appropriate option, as it best supports the conservation objectives and minimizes ecological disturbance.	- Noted. No further actions required. - Noted. No further actions required.

DEADP <i>(Organ of State)</i>	• Confirmation whether the site was zoned residential prior to 5 March 2012 is required. • Please confirm when the road was developed and provide the width of the road. • Please note that comment must be obtained from BOCMA regarding the offset proposal and whether they support the proposed offset. • Noted that two options for stormwater control measures have been proposed: the installation of two 900 mm diameter culvert pipes, or a 1.3 m wide × 0.7 m high trapezoidal concrete-lined channel to manage upstream flow. However, the preferred alternative has not been indicated. Please note that the preferred alternative must be clearly stipulated in the final BAR. • CapeNature and I&APs indicated that alien clearing on the adjacent property may affect the extent of the wetland. However, this was not considered by the Freshwater Specialist. Please note that this potential impact must be assessed by the Freshwater Specialist, who must also confirm whether there will be any additional impacts on the watercourses.	• Aerial imagery provided in Appendix J indicates that site works, including the existing building and the road commenced in 1997. The existing road is approximately 105 m in length and 4 m in width. It is important to note that the existing road predates the implementation of NEMA and therefore did not trigger the applicable environmental authorisation requirements at the time. • BOCMA supports the updated layout and the Wetland Offset, refer to BOCMA's comments below. • The Stormwater Management Plan has been updated, the preferred option for the stormwater control measures from R43 will be controlled by the provision of 2 x 900mm diameter of approximately 50 m in length stormwater pipelines. • The boundaries of the wetland have been delineated using the accepted best practice method for delineating watercourses in South Africa, required by GN 509, which specifies that key indicators obtained in the field are used to determine the wetland's current edge. This is the same methodology applied consistently across the country for all applications. It is not feasible for the Department of Water and Sanitation (DWS), DEADP, or Cape Nature to require that delineations or impacts assessed in EIA reports, be based on speculative future scenarios - such as the possibility that a wetland may expand over time due to adjacent land uses or climate change - without quantifiable data to define "by how much" or "where." If such an approach were adopted, the same uncertainty would apply to every future development. The EIA process is therefore correctly based on real- time field conditions and verified indicators at the time of assessment, which provides the defensible basis for decision-making. The presence of alien invasive species was explicitly considered during the assessment. At the time of the fieldwork, dense stands of alien vegetation were present and were therefore incorporated into the immediate surrounds and catchment of the wetland as part of the Present Ecological State (PES) assessment.
--	--	--

	• Written confirmation must be obtained from the Overstrand Municipality that they have sufficient, spare, unallocated capacity for potable water supply, effluent management, waste management and electrical supply for the proposed development. • It is noted that a water use license application in terms of the National Water Act, 1998 (Act No. 36 of 1998) is required. Proof of the submission thereof to the relevant water authority should be included in the Final BAR.	However, if specialists were required to account for every possible future land-use change, this would imply assuming, for every project, that all alien invasive vegetation has been cleared and that all unlawful water uses (such as illegal dams) have been rectified. Such assumptions are not realistic and cannot be applied with a high degree of confidence. The EIA process is therefore correctly based on actual conditions observed at the time of assessment, in line with best practice and methodological guidance. DEADP should note that what has been requested is comparable to asking the specialist to estimate the extent of the wetland on the assumption that the surrounding areas were in a pristine reference state. While this might be conceptually useful when considering the presumed natural reference state of the system for a PES assessment, it does not make sense for delineating the boundaries of the present-day wetland. It should be explicitly noted that freshwater ecological assessments do not delineate or assess wetlands on the basis of assumed pristine conditions. Rather, wetlands are delineated and assessed using current, real-time field indicators, and the present condition is then compared against an appropriate reference state to inform the PES outcome. • Service confirmation letters are attached as Appendix K. • Proof of submission is attached as Appendix L.
Cape Nature (<i>Organ of State</i>)	• The preferred development layout presented in the current version of the BAR is the same as presented in the previous version and hence has not addressed the concern regarding the encroachment into the wetland. The response to our comments in the comments and response report by the aquatic ecologist indicates that there will be further investigation of	• The layout incorporates both areas suitable for development and non-developable areas on site, with the latter forming part of the proposed wetland offset area. These non-developable areas will be managed and monitored by the Homeowners' Association (HOA) and will be subject to title deed restrictions to ensure their long-term protection. As

	full avoidance the wetland, however this has not been included in the final BAR. The environmental assessment practitioner indicates that there is full avoidance of the permanent wetland, however this is insufficient, as there should be full avoidance of the seasonal/temporary wetland as well. • Note that the sewer pipeline will traverse the wetland in the north of the property, and we recommend there should be further investigation of an alternative alignment which avoids the wetland. • Confirmation should be provided that the sewer pipeline upgrades within the suburb of Vermont to accommodate the development will occur within existing transformed areas and will not require additional environmental controls to	indicated in the specialist report and the BAR, it is not possible to fully avoid encroachment into the wetland due to the extent of the wetland area covering the larger portion of the site. While portions of the erven extend into the seasonal wetland areas, the built footprint of houses will be confined to designated development zones, with the remaining areas formally restricted as no-go development zones. These no-go areas will be secured through title deed restrictions and incorporated into the wetland offset plan. The construction of the access road will result in a minor loss of seasonal wetland area, which has been fully accounted for in the wetland offset calculation. Encroachment is limited to micro-intrusions into the seasonal wetland for road construction, which has been explicitly quantified and accounted for in the Wetland Offset, Rehabilitation, and Management Plan, supported by BOCMA. Portions of erven extending into the seasonal wetland will be designated as no-go areas, legally enforced through title deed restrictions and managed by the Homeowner's Association to prevent any future construction. It should be noted that there are no feasible alternatives for the alignment of the road due to safety and visibility requirements. The site is located at the corner of the R43, where line-of-sight considerations dictate the current road placement. • Alternative 3 was updated and revised to address this concern. The sewer pipeline has now been realigned to run parallel to the water pipeline route (Refer to Appendix F6a and F6b), thereby completely avoiding the wetland area. This revision represents a major improvement compared to the previous alternatives and is in line with CapeNature's recommendation to prevent negative impacts on the wetland system. • The sewer pipeline upgrades within the suburb of Vermont will take place entirely within existing transformed road reserves and disturbed areas. As such, no additional encroachment into natural wetland habitat will occur, and the works will not require further
--	--	---

	minimize the impact. • No solid boundary walls should be permitted as this will impact on the hydrology of the wetland, in particular along the western boundary. • Cape Nature further wishes to respond to the responses regarding the change in the wetland extent that it was primarily along the western boundary where extensive clearing of gum trees has taken place on the neighbouring property and not along the south-eastern boundary where the stormwater outlet is located. • Note however that the layout plan in the stormwater management plan differs from the preferred layout plan in the BAR and is not included in any of the other reports. The access road to the southern node is located to the north of the units and traverses the wetland. • Permeable paving is proposed for the section of road which traverses the wetland, and a swale is proposed along the southern edge of the erven in the northern residential node. These features have not been assessed in the aquatic biodiversity assessment. Either the stormwater management plan or the aquatic biodiversity assessment and BAR must be amended to reflect the current preferred layout plan, neither of which are currently supported due to the encroachment into the wetland. • CapeNature wishes to query the feasibility of maintaining the wetland sections within the private residential erven in terms of both habitat condition and ecological function and connectivity. • With regards to the first two steps of the mitigation hierarchy of avoid and minimize,	environmental controls beyond standard best practice construction measures already included in the EMPr. • Solid boundary walls will not be permitted along the wetland area. Instead, only permeable fencing (e.g., bollards, post-and-rail or wire mesh designs) will be allowed to ensure that natural hydrological flows and faunal movement within the wetland are not impeded. This restriction will be incorporated into the design guidelines, title deed conditions, and the EMPr, and will be enforced by the Homeowners' Association. • Noted. • The layout development plan in the Stormwater Management Plan has been updated. • Permeable paving is supported. The wetland offset report has been updated as required. The portions which are falling within the wetland areas will be protected through a formal servitude that will be enforced in the title deed. Additionally, the wetland area will be demarcated with bollard fencing to allow the ecological connectivity and faunal movement onsite. • The most practical and feasible option to maintain the wetland sections as described above will involve fencing off the wetland area with low post-and-rail or wire mesh designs as this will maintain the ecological connectivity for the wetland onsite and faunal movement. • The portions of the residential erven that fall within the delineated seasonal
--	---	--

	the residential erven should be located fully outside of the delineated wetland. Should it not be possible for the residential erven to fully avoid the wetland, additional motivation will be required, and the encroachments will need to be added to the impacted wetland which must be offset. • In terms of the offset target area, there is sufficient remaining wetland habitat on the on-site wetland to meet these targets. However, further motivation must be provided regarding the calculations and as discussed discrepancies/ miscalculations were identified.	wetland areas will be restricted from any form of development. All housing development will be located outside of the wetland areas. Furthermore, the areas within the wetland will be formally protected through a servitude, which will be monitored by the Homeowners Association (HoA) and enforced as a title deed restriction to prevent any future development within these sensitive areas. The protection methodology also includes bollard fencing which will clearly define them as no-go areas and to prevent the disturbance of ecological connectivity and faunal movement across the whole property. The most practical and feasible option to maintain the wetland sections as described above will involve fencing off the wetland area with low post-and-rail or wire mesh designs as this will maintain the ecological connectivity for the wetland onsite and faunal movement. • Establishing an on-site wetland offset is generally preferable, as it maintains ecological connectivity, provides an obvious like-for-like outcome (which can be very difficult to achieve with offsite offsets), and avoids the practical and administrative complications often associated with organising an offsite offset. • It is acknowledged that best practice offset methodologies require offsets to deliver additional conservation outcomes and cannot simply involve the protection of wetland areas that would remain intact regardless of development. However, in this case the offset is not limited to conserving the remaining wetland; it involves a rehabilitation plan designed to improve the condition of the existing degraded wetland from a Category D ("largely modified") state to Category C ("moderately modified"). Such measurable improvement represents an additional conservation outcome consistent with the principles set out in best practise guidelines. On-site offsets of this nature are supported in best practice guidelines. The proposal is therefore
--	--	--

	• A suitable entity in favour of whom the conservation servitude will be signed must be identified e.g. a non-governmental organisation such as the Overberg Renosterveld Trust, although the latter only focuses on renosterveld remnants Other equivalent protection mechanisms can be investigated which are most appropriate to the site context. We recommend further consultation with CapeNature regarding the protection mechanism for the wetland offset. • Further detail is required regarding the removal of rubble and fill, including the current extent and depth of rubble and fill.	consistent with recognised offset methodology, provided that rehabilitation is implemented and monitored to demonstrate the anticipated ecological gains (please note that monitoring of this is included in the Plan). • Agreed. The goals and objectives of the offset study do include securing the wetland under a conservation servitude; however, we acknowledge that further detail regarding the mechanism and the entity in whose favour the servitude would be signed must be provided. Options such as a suitable non-governmental organisation or other equivalent entities will be investigated, and consultation with CapeNature will be undertaken to ensure that the most appropriate and effective protection mechanism is applied in the site context. • Agreed. The proposed rehabilitation interventions have been strengthened by linking them to clear, measurable targets and defined timeframes to ensure that rehabilitation goals are achieved. Refer to Appendix B. The end goal of rehabilitation will be explicitly set out and aligned with each intervention, and success will only be confirmed once these goals are met. The plan has been updated to ensure that a suitably quality restoration ecologist should oversee each step in the rehabilitation process. Further detail has been provided on the removal of rubble and fill, including its current extent and depth, and the potential implications for site hydrodynamics has been considered. The plan has been updated to highlight that a suitably qualified restoration ecologist with a proven track record in wetland restoration (including but not limited to the revegetation component) will be appointed to lead implementation. It is agreed with that the Maintenance Management Plan (MMP) should be fully aligned with the Wetland Offset, Rehabilitation and Management Plan to
--	---	--

	- It is noted that a water use license application (WULA) is required for the proposed development, however no further information is provided regarding the WULA. - The fauna impact assessment for the preferred development layout is rated as medium significance after mitigation and therefore falls within the thresholds requiring a biodiversity offset in accordance with the National Biodiversity Offset Guidelines (DFFE,2023). - Cape Nature recommends that there is further investigation of the mitigation hierarchy in this regard and that an additional offset is investigated for animal species, specifically focusing on Cape dwarf chameleons.	ensure consistency and accountability. - Proof of WULA pre-application submission is attached as Appendix L. - There are no triggers for a biodiversity offset. Both the Terrestrial Biodiversity Impact Assessment and the Faunal Specialist Assessment have been updated in line with the revised preferred layout (Alternative 3), which incorporates concerns raised during. - Mitigation hierarchy was investigated further, refer to the mitigating hierarchy section in the BAR.
Whale Coast Conservation	- Erf 1486 is largely unsuitable for development due to ecological sensitivity – approximately 0.9 ha of the 1.5 ha site is wetland (permanent and seasonal). - The site forms part of a larger wetland system from Bot River to Vermont Pan, with critical hydrological and ecological functions.	- The site is located within the designated urban edge and is zoned for single residential land use in terms of the Overstrand Municipality's Spatial Development Framework and zoning scheme. In recognition of the ecological sensitivity, a small portion of the wetland area will be lost to road construction and has been accounted for in a Wetland Offset, Rehabilitation, and Management Plan that has been compiled to ensure the protection, rehabilitation, and long-term management of the wetland areas. Furthermore, the updated layout ensures that residential development will be located outside of the delineated wetland areas, with the wetland portions formally protected through servitudes and title deed restrictions to prevent any future disturbance. - Upstream wetland areas that are unaffected by the proposed development are not required to be included within the scope of work. However, the broader system context was considered through reference to the downslope linkage with the Vermont Salt Pan (see Figure 5-15 from the

	freshwater assessment report). The Aquatic Impact Assessment Report also considered the broader system in its evaluation when considering potential impacts, please refer to the Delta Report Version 4. Furthermore, as the wetland is connected to the broader downslope system, it is reasonable to assume that any rehabilitation undertaken on the site in question will contribute to improving the functioning of the overall system. However, this potential benefit was not included in the offset calculation in order to take a conservative approach and also because this area is not owned by the applicant – thereby increasing complexities in the offset process.
Wetland boundaries are uncertain and likely underestimated due to climate change impacts and alien invasive plant (AIP) removal; this undermines the accuracy of the delineation used in the BAR.	The boundaries of the wetland can be delineated accurately, and this has been undertaken by the numerous specialists, as well as the current specialist in accordance with the prescribed best practise methodology. This is the same methodology applied consistently across the country for all applications. It is not feasible for the Department of Water and Sanitation (DWS), DEADP, or Cape Nature to require that delineations be based on speculative future scenarios - such as the possibility that a wetland may expand over time due to adjacent land uses or climate change - without quantifiable data to define “by how much” or “where.” If such an approach were adopted, the same uncertainty would apply to every future development. The EIA process is therefore correctly based on real- time field conditions and verified indicators at the time of assessment, which provides the defensible basis for decision-making.
Vegetation is Critically Endangered Hangklip Sand Fynbos; the erf is mapped as Critical Biodiversity Area 1 (CBA1), within an Ecological Support Area (ESA2), and an Environmental Management Overlay Zone (EMOZ).	Noted. This has been addressed in the BAR.
The wetland remains functional, hydrologically connected, and is showing signs of recovery; it is a vital ecological corridor for ground-dwelling species. Recent Global Wetland Outlook 2025	Noted. The functionality and connectivity of the wetland will be maintained under Alternative 3. The wetland areas will be excluded from development and formally protected through servitudes and title deed

	findings emphasise that wetland loss/degradation is severe; prevention is more effective than restoration – this proposal conflicts with these principles and national biodiversity targets. • Climate change and local storm patterns will likely increase water flows to the site, raising flood and hydrological risks. • BSP 2023 guidelines recommend withdrawing development from ESAs and CBA1 areas; residential housing is not a suitable land use. • Aquatic Assessment and Offset Plan is flawed: • Study area limited to erf boundaries without considering wider system	restrictions. In addition, permeable fencing and ecological design considerations will ensure continued movement of ground-dwelling species, thereby safeguarding the corridor function and supporting the ongoing recovery of the wetland system. • A Stormwater Management Plan has been implemented to address potential flood and hydrological risks, before and after development has been completed. The plan incorporates the stormwater management designs to accommodate increased water volumes associated with climate change and local storm patterns, ensuring that stormwater is effectively attenuated, managed, and discharged without negatively impacting the wetland system or adjacent properties (refer to an updated Stormwater Management Plan under Appendix F7). In addition, specialist input has been incorporated into the layout to minimize risks and maintain the natural hydrological functioning of the site. • The WCBSP (2023) guidelines do provide for the avoidance of development in ESAs and CBA1 areas; however, they also include provisions for low-impact development within CBA1 areas under certain circumstances. It is important to note that this proposal was initiated prior to the release of the 2023 WCBSP update, and therefore considers the 2017 WCBSP, which primarily designated the site as ESA2. In particular, the wetland boundary is identified as ESA2, while certain areas of the site remain unmapped. The proposed development layout has been designed to minimize encroachment on sensitive ecological areas and aligns with both the legacy and current biodiversity planning frameworks. The proposal, following the Alternative 3 option, has been supported by the specialist through detailed assessments, confirming that the development footprint avoids significant ecological impacts while allowing for ecological connectivity and faunal movement onsite, refer to the updated specialists reports under Appendix F. • This statement is noted; however, the specialist cannot agree with it. The Aquatic Assessment and Offset have been undertaken using the prescribed methodology and within the defined scope
--	--	--

	impacts. • Suggestion to offset wetland loss by rehabilitating remaining onsite wetland is invalid (“specious”) as both loss and rehabilitation are developer-driven. • Proposal would still result in unavoidable wetland loss, complicating Water Use Authorisation.	of work. The process followed is consistent with best practice and relevant policy guidance. The offset has only been proposed after applying the full mitigation hierarchy - avoidance, minimisation, and mitigation - and is designed to address the small portion of residual wetland loss that is unavoidable for the project to remain viable. The delineation and assessment were undertaken in accordance with the DWS wetland delineation guidelines. Upstream, unaffected (by the development proposal at hand) wetlands are not required to be included in the scope of work; however, the broader system context was considered through reference to the downslope linkage with the Vermont Salt Pan (see Figure 5-15, extracted from the freshwater assessment report). It is also noted that this wetland does not exist in a pristine or fully natural state. This reality formed part of the specialist assessment, which applied the recognised WET-Health methodology (Macfarlane et al., 2020) to evaluate the current condition and extent of modification. This ensures that the assessment and offset proposals are based on actual ecological condition rather than an assumptions. The specialist recommended that the majority of the wetland is designated it as a No-Go area, and by recommended rehabilitation, protection, and detailed mitigation measures for the proposed development, there is acceptable levels of impact. Please note that as with all developments, the success of these measures depends not only on the actions of the developer but also on appropriate monitoring and enforceable conditions of approval.
	• Biodiversity offset requirements (for ~500 m² loss of critically endangered vegetation) are not addressed. • Development will cause permanent loss of natural/semi-natural vegetation, wetland area, ecological connectivity, and faunal habitat, with impacts during both	• The Terrestrial Biodiversity Impact Assessment and Animal Species Assessment have been updated the impact rating is low to medium after mitigation, therefore no biodiversity offset is required. • Noted. The impact on vegetation loss has been reduced to low – medium residual impact which is acceptable from the botanical specialist perspective.

	construction and operation. - Claims of eco-sensitivity are considered “greenwashing”; inclusion of seasonal wetlands within erf boundaries undermines protection. - Reliance on a Home Owners’ Association for environmental management is inadequate; EMPr measures are suggestive rather than enforceable.	- The portions of the erven falling within the wetland areas will be formally demarcated as no-go areas and excluded from any development activities. These areas will be managed through the registration of a servitude, which will be legally enforced in the title deed to ensure long-term protection and ecological integrity. - In addition to management by the Home Owners’ Association (HOA), the seasonal wetland No-Go areas will be physically demarcated using bollard fencing. This measure will provide a clear visual and physical barrier to help protect these areas and reduce the likelihood of encroachment, complementing the HOA’s management role.
BOCMA <i>(Organ of State)</i>	- Notes Preferred Alternative 3 was informed by freshwater, botanical, and faunal specialist input. - This alternative is considered to have the least environmental impact. - A Risk Assessment Matrix has now been completed (previously absent), showing a LOW/MEDIUM risk rating with high confidence. - Any activity within the 1:100-year flood line, 100 m of a watercourse, or 500 m of a wetland/pan triggers a water use activity under Section 21(c) & (i) of the National Water Act (NWA, 1998) — appropriate mitigation measures are required. - A full Water Use License will be required due to wetland encroachment. - The ecologically transformed unchanneled valley-bottom wetland retains ecological and hydrological value. - Supports reinstatement of the ecological corridor from Hoek van der Berg to Vermont Salt Pan through implementation of the Wetland Offset, Rehabilitation and Management Plan. - Plan must include: - Clear method statements for construction and maintenance. - Timelines and accountability for implementation. - Ongoing monitoring of	- Noted. No further actions required. - Noted - Noted Noted. - Proof of application submission is attached as Appendix L. - Noted.

	wetland health and offset success. ○ Adaptive management if targets are not achieved. • Stormwater Management Plan must account for site-specific hydrology influenced by the wetland and surrounding catchment. • Construction must comply with all other applicable provisions of the NWA (1998).	• The stormwater Management Plan accounts for the hydrology that will be received onsite from the surrounding, including from the mountains and from R43, which will be facilitate through the site through stormwater management designs, refer to the updated Stormwater Management Plan under Appendix F7. • Noted.
PUBLIC PARTICIPATION PROCESS 4		
Paul Slabbert (Representing M. Raimondo / Neighbour)	• UVA opposes any development within wetland areas. In this case, seasonal wetlands have been included within privately owned erven, separated from the permanent wetlands by property boundaries and fencing. Instead of excluding all wetland areas from the development footprint, the proposal includes numerous rules and human-managed interventions as mitigation measures. • UVA Prop also reserves the right to appoint a freshwater ecologist to verify the actual wetland delineation during the winter season, particularly in light of the expanding wetland boundary caused by ongoing alien vegetation clearance in the catchment area.	• The updated preferred layout (Alternative 4) has been specifically designed to respond to concerns raised by stakeholders, including the objection to development within wetland areas. Compared to the earlier layout alternatives, Alternative 4 significantly reduces encroachment into the seasonal wetland and avoids development within the permanent wetland zone. The majority of the wetland system is now incorporated into a consolidated open space area that will remain undeveloped and managed for ecological purposes. - Only a very minor and unavoidable infringement into the seasonal wetland edge remains, associated with the access road infrastructure and very little portions of erven. • Noted.

Michael Raimondo	- Plan still includes development within the wetland area. - Strongly oppose any development within this wetland area. It is critical that the freshwater ecologist verifies the actual wetland delimitation during the peak winter season - this has not happened yet.	Concerns raised have been noted. The final preferred layout does not fall within the delineated wetland. A revised delineation of the UVB wetland has been undertaken by the review specialist (Nick Steytler).
Whale Coast Conservation	- Highlights the ecological context of the site: - Much of the erf is designated as a wetland - the wetland boundaries will fluctuate and the ware of the wetland will increase, possibly dramatically. - The erf's vegetation is Hangklip Sand Fynbos (some 70%), designated as Critically Endangered - The erf is part of a critically important ecological corridor - The erf is a section of an important and extensive wetland system - The erf forms part of an Environmental Overlay Zone (EMOZ) - The erf is classified as a Critical Biodiversity Area (CBA1) - The erf is part of a broader Ecological Support Area (ESA2) of the Western Cape Biodiversity Spatial Plan. - A rational consideration of the full context of the erf will remove it from potential development. - An addendum to the specialist report on the terrestrial botanical impact of the proposal dated August 2025 updates the assessment following sight of the third iteration of the development design. It notes that the final version is an improvement on the second design, on which the specialist's original assessment was based. The specialist now assesses the risk as low to medium negative and opines that the development may now proceed "without undue ecological impact", provided that his recommended	- The final preferred layout has been reduced in number and size and falls entirely outside the wetland area. - The concern is noted, However, through multiple refinements of the layout Alternatives, there is no encroachment into the seasonal wetland except where the access road is required – aligned with the existing Lynx avenue. - Noted.

	mitigation measures are complied with. • This revised assessment is nothing more than rearranging the proverbial deckchairs on this Titanic of a development proposal. It should be noted that a rating of low to medium negative (from high negative) in an area of critically endangered vegetation still means that the proposal will require an offset under the Biodiversity Offset Guidelines. • Continually referring to the so-called “no-go areas” as an offset for the loss of protected vegetation and wetland functionality is disingenuous and misleading. Although the mitigation hierarchy is referred to in the FBAR as a guiding principle for the development, an offset as the result of inadequacy of the various progressive steps of the hierarchy to protect against the loss of valued habitat has very specific requirements. Such an offset will require the purchase of land on a like-for like basis to be used as a proxy for the loss in an area that can be guaranteed future protection in perpetuity, using a formula that will multiply the area concerned significantly. • The final BAR includes a “Proof of WULA process” as Appendix L. This document is unreadable and no details can be made out. WCC understands that the public participation process associated with a WULA runs for 60 days rather than the 30 associated with the NEMA process. No notification of the WULA public participation process has as yet been received by this registered I&AP; it should have been a “one environmental system” application, but this appears not to be the case. • The extent of the wetland was defined according to accepted markers for wetland presence on that date and is much the same as the previous delineation. Crucially however, the potential impact of climate change and the continued removal of IAPs from the vicinity on this extent was still not dealt with.	• According to the National Biodiversity Offset Guidelines (2023), a biodiversity offset is only applicable when the residual impact significance of a development is rated as Medium-High or High Negative after all feasible mitigation measures have been implemented. In this case, the botanical specialist has rated the residual impact of the proposed development as Low Medium Negative, which falls below the threshold that would trigger the need for an offset. • As above. • Correspondence relating to the submission of the WULA is attached under Appendix L. • The Stormwater Management Plan (SMP) was prepared to manage both current and future stormwater runoff patterns and to minimise potential hydrological impacts on the delineated wetland. The SMP incorporates conservative design principles aimed at maintaining pre-development flow regimes and accommodating potential increases in runoff associated with climate change. The delineated wetland extent is therefore considered appropriate for the purposes of the assessment, with adaptive management measures proposed should changes in wetland
--	---	--

	- Any development next to a wetland requires a buffer zone in order to protect the wetland from encroachment. It is unacceptable to use the seasonal wetland demarcation as a proxy for a buffer zone. The buffer zone should extend from the outer delimitation of the seasonal wetland and development should only be considered past the buffer zone. This will of course reduce the size of the proposed erven and is likely to render the proposed southern three erven too small for development. - Much is made in the FBAR of the so-called conservation of the wetland through strict limitations on permissible development and the establishment of a Public Open Space “conservancy”, or “conservation servitude”. This is to be managed and controlled by a Home Owners’ Association (HOA) to ensure that the so-called no-go areas will be respected. The HOA is charged with (inter alia) ensuring that pollution and encroachment does not occur and that AIPs are removed on annually under strict conditions.	extent be observed over time. - The wetland delineation and buffer determination were undertaken by a suitably qualified freshwater specialist using accepted field-based delineation methods and relevant guideline documents. The delineated wetland boundary and recommended buffer therefore represent the best available scientific assessment of the wetland system and its functional ecological edge at the time of the study. The seasonal wetland extent identified through the specialist investigation was not used as a substitute for a buffer zone, but rather formed part of the overall delineation process used to inform the development layout and mitigation measures. Through the refinement of the layout alternatives during the impact assessment process, the final preferred layout (Alternative 4) was specifically designed to respond to the wetland delineation and associated sensitivity. This redesign resulted in a reduction in the number and size of erven and increased protection of wetland areas through the allocation of no-development zones and private open space. Development infrastructure and building footprints have been positioned outside the permanent wetland areas and largely outside the seasonal wetland extent, with only limited and unavoidable encroachment associated primarily with the internal access road and small portions of certain erven along the edge of the seasonal wetland. These limited encroachments were assessed by the freshwater specialist and considered acceptable within the context of the site constraints. - There is a long-term management of the site will be the responsibility of the Homeowners Association, and this is included as a Condition of Environmental Authorisation. - The wetland boundaries on Erf 1486 have
--	--	---

	- There have been various attempts over the years to define the boundaries, both permanent and seasonal, of the wetland on the erf but these remain open to debate. Given changing circumstances, a definitive boundary is likely to remain elusive. In such circumstances, the precautionary principle should apply. In August 2018 the aquatic biodiversity screening assessment confirmed and delineated the onsite wetland, and an updated delineation was done in May 2023. The delineated wetland covers approximately 0,9Ha of the 1,5Ha site, i.e. almost two-thirds of it, and the site was classed as being of “very high” aquatic sensitivity. - Following the redesign of the development proposal to the format now proposed, a “Wetland offset, rehabilitation and management plan” was prepared in October 2024. A basic flaw of this however, is that the study area for this aquatic assessment and plan is only the extent of erf 1486. No consideration is given to its situation within the Bot River to Vermont Pan wetland system, nor to the unavoidable impact on the extent of the onsite wetland of factors beyond its boundaries. In this regard, the assessment makes the risible assertion that liability for increased water flow from the removal of AIPs beyond the erf’s boundaries should rest with the remover. It is of course the responsibility of the developer to conduct an environmental due diligence before deciding to purchase.	been assessed and delineated by two independent, suitably qualified freshwater specialists during different stages of the assessment process. Both specialist investigations applied accepted delineation methodologies, including the identification of hydromorphic soils, hydrophytic vegetation, and terrain indicators, to determine the current wetland extent. The findings of these assessments confirmed that the wetland delineation used to inform the impact assessment and layout planning is considered accurate and representative of the present ecological conditions on site. While it is acknowledged that wetland systems are dynamic and may change over time due to natural processes and external influences, the delineation relied upon in this application reflects the best available scientific information at the time of assessment. The mitigation hierarchy and layout design were informed directly by these specialist findings, with the preferred layout (Alternative 4) avoiding the permanent wetland areas and largely avoiding the seasonal wetland extent. The Wetland Offset, Rehabilitation and Management Plan was prepared specifically to address impacts associated with activities undertaken on Erf 1486 and therefore focuses on the portion of the wetland system that falls within the legal boundary of the property. This approach is consistent with standard environmental assessment practice, where the impact assessment evaluates the receiving environment at both the site scale and the broader ecological context, while management actions and offset measures are defined for areas under the control of the applicant. The aquatic assessment did, however, recognize that the wetland on Erf 1486 forms part of the larger Bot River–Vermont Pan wetland system and acknowledged the hydrological connectivity between these systems in the baseline description of the receiving environment. Wetland systems are influenced by catchment-level processes, including upstream land use, stormwater
--	---	--

	In an attempt to ameliorate the situation, the assessment details activities aimed at restoration and management of the remaining portion, stating that these will suffice as an offset for the losses. This assertion is arrived at after the application of formulae that result in a positive outcome. However, an offset can only be explored in an EIA process after a long process of examining a cascade of options arising from the use of the mitigation hierarchy and would involve the identification of a suitable “like for like” piece of ground to substitute for unavoidable loss. It is clear that there are no mitigation options open to this proposal. Proposing to use the remaining existing	inputs, groundwater dynamics, and alien invasive plant (AIP) infestation or clearing. These processes are not limited to property boundaries and are typically managed through broader catchment management initiatives rather than site-specific development mitigation alone. The Wetland Offset, Rehabilitation and Management Plan therefore focuses on interventions that are feasible and legally implementable within the development footprint, including rehabilitation of disturbed wetland areas, alien vegetation clearing within the property, stormwater management, and long-term ecological management through the Homeowners Association and Environmental Management Programme. These measures contribute positively to the functioning of the local portion of the wetland system and support ecological processes at a landscape scale. From a feasibility perspective, the redesigned development layout reflects the application of the mitigation hierarchy and specialist input to avoid permanent wetland areas and minimise disturbance to seasonal wetland zones. The remaining impacts were assessed by the freshwater specialist as limited and manageable with the implementation of the Wetland Offset, Rehabilitation and Management Plan, stormwater controls, and long-term ecological management measures. The intention of the Wetland Offset, Rehabilitation and Management Plan is not to justify additional wetland loss, but rather to restore and improve the ecological functioning of the remaining wetland areas that have already been disturbed by historical activities on the property. The specialist assessments recognize that portions of the wetland system on Erf 1486 have been modified through past land uses, including infilling, alien vegetation infestation, and the presence of derelict infrastructure. The proposed rehabilitation interventions are therefore aimed at reinstating wetland structure and function where feasible, including the removal of foreign fill material, alien
--	---	---

	wetland as an onsite offset for the inevitable wetland losses from the development is specious. Improving the condition of the remainder of an endangered ecosystem cannot compensate for the loss of part of that ecosystem, particularly when both result from and are conditional on the actions of the developer. Given the basic flaw of the restriction of the study area to the boundaries of erf 1486 however, these calculations and proposed activities are nothing more than arranging the deckchairs to ensure maximum occupancy on the deck of a sinking ship. A WULA should not be issued. • The current proposal will result in a loss of Critically Endangered vegetation of some 500m² and reduces the impact from the previous iteration from high to medium negative. However, there is no indication as to where this will be lost and how the area/s of loss relate to the wetland delineation. It should be noted that according to the National Biodiversity Offset Guidelines, if the residual impact is medium, a biodiversity offset is required, but this aspect is not dealt with.	invasive vegetation clearing, restoration of natural vegetation, and the protection of hydrological processes through formal conservation mechanisms. The application of the mitigation hierarchy informed the evolution of the preferred layout alternative, which avoids permanent wetland areas and minimises intrusion into seasonal wetland zones to the greatest extent practicable within the constraints of the property. The freshwater specialist confirmed that, given the configuration of the wetland across the site and the property's location within the urban edge, some limited wetland disturbance associated primarily with access infrastructure is unavoidable. The rehabilitation and management measures are therefore intended to reduce the overall ecological risk and improve the condition of the remaining wetland habitat in the long term. Furthermore, retaining the property in its current unmanaged state does not guarantee the protection of the wetland. Without formal management, the site remains vulnerable to continued alien plant invasion, illegal dumping, and incremental disturbance, all of which can further degrade wetland functioning. The proposed development introduces enforceable environmental management obligations and rehabilitation actions that would not otherwise be implemented. In this regard, the proposal represents an opportunity to secure long-term protection, restoration, and monitoring of the wetland system within the property while accommodating compatible land use within the urban edge. • The new preferred layout – Alternative 4 minimizes the clearance of the indigenous vegetation <500m² compared to earlier alternatives proposed. Since the layout has evolved, the impact rating has been reduced to low-medium after mitigation, therefore not triggering the offset.
--	---	--

	• The BAR emphasises throughout, including in the section on need and desirability, that the development will satisfy housing needs and promotes infill development and densification – even referring to this as fulfilling a mandate (page 101). These are laudable goals for urban development in general but are not appropriate for this property. The ecological importance of the erf is such that it must be protected from encroachment – it should in fact be restored to its natural state. • The development needs and aims to capitalise on the misguided purchase of the erf. Thus, the BAR attempts to persuade decision-makers that the development will be of benefit to the erf and that negative impacts will be minimal and transient. This is nonsense. Construction activities on the erf will destroy critically endangered natural vegetation and interfere with the natural functioning of the legally protected wetland. Occupation will jeopardise the erf's function as an important ecological corridor by interfering with faunal existence and movement. The development will also dampen the wetlands' ability as part of a larger system to mitigate the effects of future storm surges • The development will cause damage to the wetland both in the construction phase and afterwards when the development is established. In the construction phase this includes loss of wetland area, habitat disturbance, alteration of the flow regime of the wetland and water quality impairment. During the operational phase the damage includes habitat disturbance, alteration in the flow regime, water quality impairment and potential sewerage leaks. • Table 1 of the BAR notes that the percentage of seasonal wetland on the various residential erven ranges from 0 (one unit of 350m²) to 30 (four units of 300m² and one of 450m²), averaging at 25% coverage (not 15% as stated in Table 1). The inclusion of areas of seasonal wetland in the erven is no doubt to ensure marketable erven sizes and increase the financial viability of the proposal.	• The concerns raised are acknowledged. Following further refinement of the development proposal, a revised preferred layout (Alternative 4) has been prepared. The updated layout makes provision for the retention and protection of the larger wetland area (open space). • The current preferred new layout Alternative 4 will provide sufficient space for faunal movement, hydrological connectivity and will result to low clearance of indigenous vegetation onsite. These provisions have been supported by the specialist team, provided that all the mitigation measures recommended are fully implemented. • The preferred layout (Alternative 4) was developed in consultation with the freshwater specialist to ensure that all permanent wetland areas are avoided and that impacts on seasonal wetland areas are minimised as far as reasonably practicable within the constraints of the site. All the sewer lines have been removed from the wetland boundary. • The revised preferred layout (Alternative 4) has addressed the concern regarding the inclusion of seasonal wetland areas within residential erven. During the refinement of the layout, erven that previously extended into the seasonal wetland area were reduced in size and repositioned to minimise intrusion into these sensitive areas as far as practicably possible. This amendment ensures the preservation of a larger contiguous wetland area and strengthens the
--	--	--

	The individual property boundaries as well as the proposed sewer and enhanced protective swale system should be well outside of the seasonal wetland areas. Placing the swale inside the boundaries of the seasonal wetland is not acceptable as it is likely to result in the draining of these areas. The proposed sewer line should also be placed outside the seasonal wetland boundaries.	protection of the ecological functioning of the wetland system. While a small portion of seasonal wetland remains associated with some erven, it is important to note that full avoidance of the seasonal wetland is not practically feasible due to the size of the property. The proposed sewer line and the swale system have been removed from the seasonal wetland area.
Cape Nature	- The primary outstanding concern with the proposed development after three rounds of public participation is the encroachment of the proposed residential erven into the areas delineated as a wetland in the aquatic biodiversity impact assessment. The proposal is to ensure that the sections of wetland which encroach on to residential erven are not developed through title deed restrictions, however CapeNature does not consider this to be feasible based on numerous precedents of attempts at conserving natural habitat on individual private residential erven. The layout of the residential erven has not changed in the current proposal. - Subsequently the applicant has provided a revised layout plan whereby the residential erven avoid the delineated wetland. There are very small linear encroachments which are unavoidable and for all intents and	- The layout has been revised from the previous alternative, and the current preferred layout (Alternative 4) reflects a meaningful reduction in wetland encroachment compared to earlier proposals. The updated design ensures that all development is located outside of the permanent wetland area, with only limited and unavoidable encroachment occurring along the edge of the seasonal wetland in relation to the internal access road and portions of a small number of erven. This refinement followed specialist input and consideration of comments received during the public participation process and from Organs of State. - It is important to note that the preferred layout represents the best practicable environmental option for the site, given the spatial extent of the wetland across the property and the constraints associated with developing a small erf within the urban edge. The design process applied the mitigation hierarchy to avoid and minimise impacts as far as reasonably possible, while ensuring that the majority of the wetland system and ecological corridor remain protected. - The stormwater management plan has been updated to incorporate permeable paving along the driveway on the southern boundary, as well as the swale along the northern portion of the site. - Noted.

	purposes and considering the motivation provided in the wetland delineation review regarding the wetland delineation, the current layout avoids the residential erven encroaching on the wetland. CapeNature is therefore satisfied that our concern has been addressed. • For record purposes, the current layout which we do not object to is indicated as Revision 24 and dated 25 September 2025 as indicated in Figure 1 below, whereas the layout presented in the most recent round of public participation (Final Basic Assessment Report) where there was encroachment into the wetland is indicated as Revision 20D and also dated 25 September 2025 and indicated as Figure 2 below. • Concerns were also raised that there was insufficient investigation regarding mechanisms whereby the wetland offset can be secured. We recommend that supplementary information is provided in this regard with the final submission to DEA&DP and that a copy is provided to CapeNature for record keeping purposes. With regards to the current layout (Revision 24) and the wetland offset requirements, the wetland offset was calculated based on the minor encroachments of the access roads into the wetland and the encroachments of the access roads in the revised layout are the same as previously. It is accepted that the minor encroachments are unavoidable.	• Noted. • Noted.
Cape Nature	• The primary outstanding concern regarding the application after four rounds of public participation is the encroachment of the residential erven into the delineated wetland as indicated in our most recent comments dated 28 October 2025. A motivation was provided that there are restrictions regarding the minimum size of erven within the suburb of Vermont. • Subsequently the applicant has provided a revised layout plan whereby the residential erven avoid the delineated wetland. There are very small linear encroachments which are unavoidable and for all intents and purposes and considering the motivation provided in the wetland delineation review regarding the wetland delineation, the	Noted. Comment is noted and acknowledged.

	current layout avoids the residential erven encroaching on the wetland. CapeNature is therefore satisfied that our concern has been addressed. - For record purposes, the current layout which we do not object to is indicated as Revision 24 and dated 25 September 2025 as indicated in Figure 1 below, whereas the layout presented in the most recent round of public participation (Final Basic Assessment Report) where there was encroachment into the wetland is indicated as Revision 20D and also dated 25 September 2025 and indicated as Figure 2 below. - Concerns were also raised that there was insufficient investigation regarding mechanisms whereby the wetland offset can be secured. We recommend that supplementary information is provided in this regard with the final submission to DEA&DP and that a copy is provided to CapeNature for record-keeping purposes. - CapeNature is satisfied that the concerns regarding the encroachment of the residential erven into the wetland have been addressed and we do not object to the current layout (Revision 24) subject to all other comments made in the four rounds of public participation	Comment is noted and acknowledged. Noted. Comment is noted and acknowledged.
--	--	---

Public Participation Process 5		
Overberg District Municipality (06 July 2026)	- The municipality takes note of the amendments incorporated in the report based on the development layout in response to specialist recommendations, stakeholder input and environmental constraints. The municipality supports Alternative 4, as the preferred development alternative, as it minimizes impacts on the seasonal wetland by relocating development outside the wetland area, limiting residual impacts to the proposed access crossing, and providing for the rehabilitation and long-term protection of the retained wetland. - Furthermore, the municipality notes the proposed wetland biodiversity offset, with associated rehabilitation and management plans to address the residual impacts associated with the proposed development. ODM supports the principle of rehabilitating and securing the retained wetland area through conservation servitude and long-term management measures. - The Overberg District Municipality has no objection to the application, provided that all relevant mitigation, rehabilitation, biodiversity offset and environmental management measures are implemented and adhered to.	Noted. No further actions required. Noted. However, it must be noted that a wetland offset is applicable and no biodiversity offset was required. Noted, no further actions are required.
Denis Brandjes and Samantha Hogg-Brandjes (18 July 2026)	- The FBAR's claim that residential erven sit outside the wetland is disputed. The Freshwater Consulting delineation (July 2026) finds that most of Erf 1486 is wetland habitat, so the objectors argue direct infilling and permanent habitat loss will occur. - With wetland habitat covering nearly the whole site, they say almost no terrestrial buffer remains. They flag the water and sewer pipelines as running through or near the wetland, with contamination risk to the wetland and Vermont Pan in the event of a leak or failure. - Erf 1486 is described as a bottleneck corridor linking the Hoek van die Berg reserve wetlands to Vermont Pan. Alien clearing in the upper reserve is said to be driving hydrological recovery and rising groundwater, and the objectors argue	Wetland extent and erven placement: all residential erven are positioned outside the delineated permanent wetland. Limited infringements fall within the seasonal wetland under Alternative 4, but these are smaller than the objection suggests. CapeNature has reviewed and supports this layout. Buffer and infrastructure: the revised layout keeps residential erven clear of the delineated wetland, with only small, unavoidable linear encroachments (confirmed by the wetland delineation review). A no-go open space area is retained through construction and operation to protect the wetland and associated habitat. Water and sewer lines are routed outside the permanent and seasonal wetland, and spill management measures for the sewer pipelines are built into the EMPr.

	development at this point would fragment habitat connectivity for SoCC, including the Near Threatened Cape Dwarf Chameleon. • Climate projections for the Overstrand region point to more intense rainfall. Hardening the site is said to reduce natural attenuation capacity, raising the risk of concentrated runoff, erosion, and downstream flooding. • The offset calculation is challenged on the basis that it understates wetland extent (0.90 ha, with only 0.027 ha of loss). A larger actual wetland footprint would mean greater loss and less residual area for offset gains, making a net ecological gain unlikely in their view. • The objectors' recommendation, echoing the Freshwater Consulting report, is complete avoidance: no further development on Erf 1486, with the site preserved as part of the ecological corridor.	Ecological corridor and connectivity: the retained open space area has been assessed by the registered faunal specialist as sufficient to protect wetland-associated habitat and maintain connectivity across the site. The specialist has confirmed the current layout as acceptable from a faunal perspective. Climate change and flooding: Overstrand climate projections have been factored into the design and assessment. Stormwater infrastructure is included in the layout to attenuate and manage runoff, aimed at reducing concentrated discharge, erosion, and downstream flood risk. Offset calculation: based on the delineation carried out by the project's registered aquatic specialist, and considered accurate on that basis. Overall position: Alternative 4 is presented as the aquatic specialist's and CapeNature's preferred layout, arrived at through the mitigation hierarchy with input from the aquatic and faunal specialists. The applicant's position is that permanent wetland is avoided, seasonal wetland infringement is minimised, and open space is retained to preserve connectivity.
PHS on behalf of UVA Property (20 July 2026)	PHS references earlier comments (13 June 2024, 22 July 2024, 13 October 2015) as still standing, now supported by the Freshwater Consulting Group's updated delineation and review (July 2026), commissioned in response to alien clearing in the upper catchment and inconsistencies across delineations completed for Erf 1486 between 2006 and 2025. Erf 1486 is described as a constrained bottleneck corridor linking the reserve's upper wetlands to Vermont Pan. Alien clearing is said to have restored hydrological function and raised groundwater levels, and six residential units plus road infrastructure are argued to fragment this recovering corridor and threaten connectivity for the Near Threatened Cape Dwarf Chameleon. The July 2026 field verification is said to show that most of Erf 1486 is permanent, seasonal, or temporary wetland, contradicting the application's assumption that even sit outside the wetland. On this basis, PHS argues the layout would result in direct infilling and permanent loss of an active wetland system.	Specialist assessment history: the development is supported by the full specialist team, including the freshwater specialist. The wetland delineation record comprises Joshua Gericke's initial 2018 delineation, Delta Ecology's updated aquatic assessment and delineation (Kimberley van Zyl, 2023, updated 2025/2026), and EnviroSwift's independent peer review (Nick Steytler, 2025), which confirmed no material discrepancy with earlier findings. These were conducted under the gazetted specialist protocols and submitted to the competent authority and BOCMA. Corridor and connectivity: the layout has been revised to minimise impact on delineated wetland features. A co-management agreement between the developer and Overstrand Municipality is underway to secure long-term protection of approximately 9,000 m² of permanent and seasonal wetland on site, aligned with the broader Vermont Pan to Botrivier wetland link vision. This securing arrangement, and the financial management capacity behind it, is presented as a positive outcome. Infrastructure and buffer: potable water and

	With wetland habitat said to cover almost the whole site, PHS argues no functional terrestrial buffer remains, and raises concern over potable water and sewer pipelines placed through or adjacent to these areas, with pollution risk to the wetland and Vermont Pan from leakage or edge effects. Overstrand climate projections point to more intense, shorter rainfall events. PHS argues hardening the site removes natural attenuation capacity, increasing stormwater velocity and flood risk to the reserve's lower boundary and downstream properties. The offset calculation (0.90 ha extent, 0.027 ha loss) is described as based on an underestimated wetland size, so the actual loss would be larger and the space available for offset gains smaller, making net ecological gain unachievable in PHS's view. PHS's position, following the specialist review, is that the layout is not supported from a freshwater perspective, that the mitigation hierarchy requires avoidance ahead of development, and that no further development should be permitted on Erf 1486, with the site preserved in full to maintain hydrological and ecological continuity.	sewer pipelines are designed to avoid the delineated wetland, with alignments located outside the wetland area. The response also notes that Erf 1486 sits within Vermont's built up urban edge, and that the system was already affected and cut off by the construction of Lynx Avenue. Climate change and flooding: Overstrand climate projections have been incorporated into the design and assessment. Stormwater infrastructure is included in the layout to attenuate and manage runoff, reducing the risk of concentrated discharge, erosion, or downstream flooding. Offset calculation: the offset assessment was prepared by Delta Ecology (2025/2026) based on the delineation informing the Basic Assessment (Delta Ecology, 2023, updated 2026), independently peer reviewed by EnviroSwift (2025). The 0.90 ha extent and 0.027 ha loss figures are presented as derived from this specialist record, not an arbitrary or underestimated baseline. Mitigation hierarchy: application of the hierarchy is said to be demonstrated through the evolution of the layout alternatives across the NEMA process. A note directs readers to Appendix E for the EAP and application specialist team's comments on the independent delineation commissioned by UVA Properties, prepared outside the NEMA application process.
DEA&DP: Management	- Confirmation is required regarding the zoning of the site prior to 5 March 2012. It is noted that this confirmation is required to ascertain whether the site is regarded as being located inside an urban area. This will have implications for the applicability of Activity 12 of Listing Notice 1 and Activity 14 of Listing Notice 3. In addition, it is noted that the road will be wider than 4 meters. The applicability of Activity 4 of Listing Notice 3 should be confirmed. If applicable, it should also be included and addressed as part of the application. - The proposed development also includes a stormwater swale and stormwater outlet structures with associated gabions which will be located on the northern and southeastern edge of the seasonal wetland. Please be advised that all components of the proposed development must be included in the site development plan.	The property was zoned for Single Residential prior to 05 March 2012. Noted.

	• Comment must be obtained from BOCMA regarding the onsite wetland offset and whether this is appropriate. • It is noted that the proof of the newspaper advertisement submitted relates to the advertisement published in 2023. However, the previous pre-application and application processes have since been concluded. As a new EIA process is currently underway, proof of the newspaper advertisement published as part of the current process must be provided. • It is noted that no confirmation regarding the provision of electricity has been included in the BAR. Please ensure that confirmation is obtained from the local authority that sufficient, spare, unallocated electricity is available to supply the proposed development. • The estimate duration of the construction phase should be provided.	Refer to BOCMA comment attached. The updated Proof of Newspaper advertisement is attached in the Proof of PP under Appendix E1. A letter of confirmation has been requested from Eskom. However, no correspondence has been received. The construction phase will be concluded within 10 years.
Cape Nature	• Cape Nature provided comment on four previous versions of the Basic Assessment Report (BAR) in which concerns raised primarily regarding the encroachment of the proposed development into the wetland which links between the Vermont Pan and the Whale Coast Nature Reserve. An additional comment on a revised layout dated 6 November 2025 was provided to the environmental assessment practitioner outside of the public participation process. The revised layout (Revision 24 dated 25 September 2025) ensured that none of the proposed residential erven encroached into the wetland as delineated in the aquatic biodiversity assessment, with only minor encroachments by the proposed permeable paving access roads. CapeNature indicated that the revised layout addressed concerns regarding encroachment into the wetland as delineated. • A wetland delineation peer review appointed by the applicant was undertaken for inclusion in the previous round of public	• Noted. • Noted.

	participation. The delineation in the peer review study did not exactly match the delineation of the aquatic biodiversity assessment with a slightly larger extent delineated, however the conclusion and recommendation of the peer review study was that the delineation in the aquatic biodiversity assessment was supported and that no amendment to the proposed development layout was required. • CapeNature's comment (18 June 2024) raised concern that the wetland extent is likely to expand due to future release of water into the catchment from AIP clearing on the adjacent reserve; the response noted that assessing future catchment transformation falls outside the specialist reports' scope • A new, privately commissioned independent wetland delineation indicates that the entire erf (excluding existing buildings) is wetland, varying significantly from the aquatic biodiversity assessment; CapeNature considers this substantive new information — undertaken by SACNASP-registered scientists and having considered future catchment context — that requires resolution, although not yet part of the formal process. • CapeNature will not comment in detail on the private delineation unless it is formally included in the process; notes the delineation followed DWS methodology and does not dispute the aquatic habitat findings of the assessment, only the extent of the wetland and its hydrological/landscape context. • WULA: public participation for the BAR and WULA is being undertaken concurrently (supported); however, the WULA layout plan is the previous (wetland-encroaching) layout and must be updated to the current preferred layout and address the concerns raised in the independent delineation; only selected PPP comments are included in the WULA rather than the full history across all rounds. • Wetland offset: once the delineation is	• Noted. A Stormwater Management Plan has been compiled for the project and the proposed development has been designed with reference to it, incorporating measures intended to accommodate a degree of hydrological uncertainty in the site's wetland-related catchment. A motivation has been provided by the appointed freshwater specialist. Noted. Noted. The WULA has been updated to reflect the current preferred layout (Alternative 4).
--	--	--

	verified and the mitigation hierarchy reapplied, the need for and calculation of the offset must be revisited; the outstanding issue is the mechanism for securing the offset, given that the CapeNature stewardship programme (NEM:PAA) was found unsuitable at the 3 February 2026 regional screening review; recommend further engagement between the applicant, CapeNature, Overstrand Municipality and BOCMA; notes possible EMOZ Category D / OECM relevance. • The privately commissioned wetland delineation must be taken into account before the application can be considered further; if not supported, a well-motivated and detailed response is required from the compiler of the aquatic biodiversity assessment; once the delineation is confirmed, the mitigation hierarchy must be reapplied and, if an offset is still required, the relevant parties must meet on the securing mechanism	A council-approved co-management agreement between the Overstrand Municipality and the Homeowners' Association (HOA) has been identified as a workable alternative mechanism. As a council-approved instrument, this agreement would carry the standing of a formal policy document, providing the necessary long-term security for the offset site. Further engagement will be undertaken with Cape Nature, the Overstrand Municipality and the Breede Olifants Catchment Management Agency (BOCMA) to formalise this co-management agreement, including securing the requisite Council approval and confirming the respective roles and responsibilities of the Municipality and the HOA in the long-term management of the offset site. The mitigation hierarchy has already been applied in developing the current site layout. Through five rounds of public participation since 2023, the number of proposed development sites has been reduced from an original 13 to 6, and approximately 9,361 m² of on-site wetland is proposed for long-term protection as a no-go/offset area. The site lies within the Overstrand urban edge and is zoned Single Residential Zone 1. Multiple wetland delineations have been undertaken since 2018 (Gericke 2018; Delta Ecology 2023 and 2026), the majority broadly consistent with one another; Delta Ecology confirms consistency with these earlier studies and does not support commissioning a further delineation. This is corroborated by EnviroSwift's independent peer review (2025), which found no material discrepancy. The discrepancy arises from the separate, privately commissioned Freshwater Consulting delineation indicating substantially greater wetland coverage. The appointed specialists maintain that their information is technically sound, consistent with the majority of prior delineations since 2018, and reflects an appropriate application of the DWAF/DWS methodology to the site's specific conditions; Delta Ecology and EnviroSwift are satisfied that the delineation underpinning the current layout remains valid and do not support a further delineation.
--	---	---

Whale Coast Conservation	WCC confirms that its earlier submission (25 October 2025) remains valid and should be read alongside this comment. Its concerns on the current BAR (Alternative 4, DEA&DP Ref 16/3/3/6/7/1/E2/40/1525/22) are as follows. WULA discrepancy The WULA (May 2026) is based on Alternative 3, the layout CapeNature did not approve, and explicitly names Alternative 3 as the preferred design on page 7. The BAR, however, proceeds on Alternative 4. WCC says this must be clarified, and the WULA rewritten and resubmitted to BOCMA. Wetland extent and the "snapshot" approach WCC maintains that the wetland, both core and seasonal, is larger than delineated and will keep expanding westward, driven by AIP clearing on the neighbouring reserve and by climate change. It argues the entire erf should be treated as wetland, with no development permitted anywhere on it. WCC challenges the EAP's position that legislation only requires a delineation "snapshot" confined to the erf boundary, taken in 2018 and reviewed in 2025 with similar results, noting the EAP's own review states that wetland delineation "is not a precise science." WCC also disputes the EAP's earlier response that upstream areas outside the erf fall outside the assessment scope, arguing this ignores that Erf 1486 is the area actually affected by upstream hydrological change. Independent delineation (Freshwater Consulting, July 2026) WCC cites this study as showing wetland habitat across the entire erf, extending into the neighbouring reserve and along the southern boundary. It references a WCC site inspection on 15 July that found standing pools, active springs, and established <i>Typha capensis</i> beyond the southern boundary, plus standing water and drainage infrastructure (a boardwalk, a concrete wall apparently built to redirect water) on Erf 1486 itself. WCC argues demolition of the existing building would release this water onto the site. Wetland increase WCC contests the freshwater specialist's explanation that a 2023 increase in delineated extent stems from stormwater discharge from the southern 2007 to 2012 housing development. WCC argues the more likely explanation is that the wetland itself is expanding southward, citing reports from southern neighbours of rising water	• Noted. The WULA has been updated accordingly to reflect Alternative 4. • WULA discrepancy (Alternative 3 vs Alternative 4): noted, the WULA has been updated accordingly. • Wetland extent / entire erf as wetland: the application team stands by the specialist findings, built on a detailed multi-year site history and ecological baseline. Reference is made to Appendix E for the responding statement on the Freshwater Consulting (UVA-commissioned) delineation. • Current extent / "snapshot" methodology and downslope linkage comment: the wetland delineation scope is confirmed as Erf 1486 itself. The Vermont Salt Pan downslope reference was included only to situate the on-site wetland in its broader catchment context, not as a substitute for considering upstream influences. On IAP removal in the WCNr specifically, the EAP confirms this falls outside the delineation scope, since methodology (DWAF/DWA/DWS guidelines) requires delineation based on on-site indicators present at the time of assessment, not anticipated future hydrological change, regardless of whether that change originates upstream or downstream. The EAP adds that a demonstrable, measurable future change in on-site hydrology or wetland extent from IAP clearing would need to be assessed at that time through the appropriate regulatory process. • Larger wetland system (Bot River to Vermont Pan) comment: noted and acknowledged, with reference to Appendix E. • Independent delineation study (Freshwater Consulting): noted, with reference to Appendix E. Multiple delineations since 2018 (Gericke 2018; Delta Ecology 2023 and 2026) are described as consistent with one another. Delta Ecology confirms consistency with earlier studies and does not support a further delineation, corroborated by EnviroSwift's independent peer review (Steytler, 2025), which found no material discrepancy. The Freshwater Consulting
--	--	--

	tables and a caution from the Erf 2319 owners (June 2024, reiterated July 2025) that the southern erven will both affect and be affected by the enlarging wetland. Future risk WCC argues the wetland boundary will keep shifting due to ongoing AIP removal and climate driven storms, and that the EAP's position, that only a point in time snapshot is required and future change need not be assessed, is inadequate. It notes the freshwater specialist's own report flags this as a monitoring risk, and argues monitoring after approval achieves nothing. WCC also quotes the EAP's statement that excluding the full no go area from erven would create impractically small, unviable properties, and argues this shows the development is not viable at all given the site's wetland status. Layout and access WCC flags that the current layout (version 4) does not show how the two southern erven will be accessed from Lynx Road, or whether they connect to the northern erven. It also raises a large culvert at the southeastern corner, which appears to discharge water from southern properties back into the wetland via Erf 2317, and notes this culvert would sit directly in the path of any proposed southern access road. Ecological corridor function WCC argues Erf 1486 has become a hydrological bottleneck due to past development, and that further development will worsen flood risk, erosion, and downstream disturbance. It notes the erf is recognised as part of an Environmental Management Overlay Zone (EMOZ) corridor by Overstrand Municipality, and that functional corridors need enough open space for wetlands to store and dissipate water. Offset WCC argues an offset should not be used to justify development that should not occur in a wetland in the first place, and that the mitigation hierarchy, properly applied, shows the environmental cost outweighs the development's need and desirability. It challenges the HOA based offset mechanism as unlikely to succeed long term, and argues the offset area calculation is invalid because it assumes developable land exists outside the wetland delineation, which WCC	delineation is acknowledged as indicating substantially greater coverage, but the appointed specialists maintain their findings are technically sound, consistent with the majority of prior delineations, and reflect appropriate application of DWAF/DWS methodology to site-specific conditions. Delta Ecology and EnviroSwift are stated to be satisfied the delineation underlying the current layout remains valid. • Site observations (standing pools, springs, boardwalk, concrete wall) and southern boundary expansion: the EAP states these have not been ignored, but recorded and responded to by the specialist team, informed by their expertise. It notes Erf 1486 is not a pristine wetland site but is highly degraded and located within a built-up urban area (Vermont). • Increase of wetland / stormwater outlet explanation: the outlet has been factored into the Stormwater Management Plan. • Future risk / EAP's "snapshot only" position being unacceptable: the specialist's caution about future change in extent, ecological state and function is acknowledged and accepted, but the EAP maintains this doesn't conflict with its position, arguing that because future change cannot be reliably predicted or delineated now, ongoing monitoring rather than speculative boundary expansion is the methodologically correct response. Monitoring is framed as operating alongside the adopted layout, which avoids the delineated permanent and seasonal wetland zones and protects approximately 9,314 m² as a no-go/offset area under the council-approved co-management agreement (Overstrand Municipality, CapeNature, BOCMA, HOA). • Financial motive / development viability argument: the EAP does not engage this point directly beyond confirming the site sits within the built-up urban edge of Vermont. • Layout and southern access: confirmed as via a servitude erf driveway with mitigation measures per the specialist reports (later detailed as a driveway branching off Lynx Avenue, traversing
--	---	---

	disputes. It also questions the underlying assumptions used to estimate the offset's ecological success and long term hydrological connectivity. Conclusion WCC's position is that version 4, despite reducing the footprint, does not resolve the underlying issue that the entire erf is wetland. WCC's recommendation is that the BAR not be approved.	between the southern erven, as shown in the BAR). • Southern culvert: confirmed present, returning water to the wetland, but will be left undisturbed by the development. New stormwater runoff will be attenuated via permeable paving and swales, so the culvert's function in sustaining the wetland is not compromised. • Ecological corridor / bottleneck effect: the cumulative effect of surrounding development on flow dynamics, and Erf 1486's position within the system, is acknowledged. Alternative 4 is presented as avoiding permanent and seasonal wetland for residential erven, limiting encroachment to access infrastructure, and formally conserving over 62% of the site in perpetuity. A Stormwater Management Plan by DECA Consulting, informed by the aquatic biodiversity assessment, addresses stormwater management. • EMOZ corridor recognition: noted and acknowledged; the co-management agreement (Overstrand Municipality, HOA, developer) is presented as directly addressing the EMOZ, with the Municipality's role as co-manager intended to offset the risk of a purely private mechanism failing long term. • Offset mechanism and calculation: notably, the EAP's position here differs from earlier responses to Brandjes/Hogg-Brandjes and PHS: it states a biodiversity offset is not applicable to this project, since the residual impact under Alternative 4 is rated low to medium negative after mitigation, below the Western Cape Biodiversity Offset Guidelines (2023) threshold (Medium-High or High Negative) that would trigger an offset requirement. This is attributed to the botanical specialist's impact rating. • WULA public participation: confirmed as released for 60 days during round 5 (20 May to 20 July 2026). • Delineation methodology and DWS guidelines compliance: reiterated, delineation reflects on-site indicators (vegetation, soils, hydrology) at the time of assessment and represents the current verified extent.
--	---	--

		• EnviroSwift independent review: confirmed as informed by a site visit on 3 August 2025, finding the wetland extent consistent with the previous delineation. On the point that this review didn't address climate change or continued IAP removal, the EAP states this was not an oversight, since assessing future catchment-level change falls outside the legislated scope of a wetland delineation, and this exclusion is transparently recorded in the Limitations sections of the specialist reports (not overlooked). • HOA/co-management mechanism concerns: noted and acknowledged, with the clarification that the mechanism is a council-approved agreement between the Municipality and the HOA, not the HOA acting alone, giving it the standing of a formal policy document and addressing the risk of a purely private mechanism failing long term (this point is repeated for both the offset area and the open space management question). • Biodiversity loss impact: noted and acknowledged, rated low to medium negative after mitigation. • Closing conclusion (WCC's recommendation that the BAR not be approved): no direct response is recorded to this specific closing statement; the preceding point-by-point responses stand as the EAP's position.
Breede Olifants Catchment Management Agency	• A full Water Use Licence is required for the project due to encroachment into the onsite wetland. • Notes the ecologically transformed unchannelled valley-bottom wetland still holds ecological and hydrological value. • Encourages reinstatement of the ecological corridor link (Hoek van der Berg to Vermont Salt Pan) via implementation of the onsite Wetland Offset, Rehabilitation and Management Plan (WORMP). • The WORMP should be implemented with clear method statements for construction and further maintenance. • The WORMP must be fully implemented with clear timelines and accountability measures, including ongoing monitoring and adaptive management if targets are not	• Noted. A WULA is in process. • Comment is noted. • Noted. A Wetland Offset, Rehabilitation and Management Plan will be implemented. • Method statements for construction-phase wetland protection and post-construction maintenance will be incorporated into the EMP and the Wetland Offset, Rehabilitation and Management Plan. • Noted

	met. • The Stormwater Management Plan must address the site-specific hydrological dynamics influenced by the wetland and its surrounding catchment. • Notes strong opposition received from Whale Coast Conservation, including reliance on a 2006 delineation (Nancy Job and Geordie Ratcliff) and the contention that the existing estate was itself built in the wetland during a dry period caused by alien vegetation on the reserve; requests feedback on this historical detail.	• The Stormwater Management Plan has addressed this. • The comment is noted and acknowledged. Wetland delineation on the site has been the subject of more than one delineation over time, including the EnviroSwift freshwater screening (2018), Delta Ecology (2023), and a review delineation undertaken by EnviroSwift (2025). The EnviroSwift (2025) review delineation confirmed no material discrepancy between its findings and the Delta Ecology delineation, with both assessments reflecting consistent wetland boundaries on site.
--	---	--

Note: Five rounds of public participation have been conducted, this is the sixth and final round.

- PPP 1 – 22/03/2023 to 24/04/2023
- PPP 2 – 17/05/2024 to 18/06/2024
- PPP 3 – 20/06/2025 to 23/07/2025
- PPP 4 – 29/09/2025 – 29/10/2025
- PPP 5 – 20/05/2026 – 20/07/2026

After the fourth round of public participation, Lornay Environmental Consulting approached Cape Nature regarding their remaining concerns and comments which Cape Nature had provided on the previous preferred layout during public participation 4. Following this consultation, the final preferred layout (Alternative 4) was generated. Cape Nature provided a preliminary comment on this Alternative 4 layout and confirmed support thereof:

CapeNature Comments – Erf 1486 Vermont, Hermanus (6 November 2025)

- **CapeNature does not object to Revision 24 (Alternative 4)** (dated 25 September 2025) — the revised layout adequately avoids residential erven encroaching on the delineated wetland
- The previous layout (Revision 20D – Alternative 3) was **not supported** due to wetland encroachment; this has now been resolved after four rounds of public participation
- Minor linear encroachments by **access roads** into the wetland are acknowledged as unavoidable and are accepted
- The wetland offset calculation remains unchanged from the previous round, as the access road encroachments are the same
- CapeNature requests that **supplementary information on the wetland offset mechanism** be submitted with the final application to DEA&DP, with a copy to CapeNature for record-keeping
- **CapeNature's support is subject to** all other conditions raised across the four rounds of public participation remaining in effect
- CapeNature reserves the right to revise comments if additional information is received

Note:

A register of all the I&AP's notified, including the Organs of State, and all the registered I&APs must be included in Appendix F. The register must be maintained and made available to any person requesting access to the register in writing.

The EAP must notify I&AP's that all information submitted by I&AP's becomes public information.

Your attention is drawn to Regulation 40 (3) of the NEMA EIA Regulations which states that "Potential or registered interested and affected parties, including the competent authority, may be provided with an opportunity to comment on reports and plans contemplated in subregulation (1) prior to submission of an application but **must** be provided with an opportunity to comment on such reports once an application has been submitted to the competent authority."

All the comments received from I&APs on the pre -application BAR (if applicable and the draft BAR must be recorded, responded to and included in the Comments and Responses Report and must be included in Appendix F.

All information obtained during the PPP (the minutes of any meetings held by the EAP with I&APs and other role players wherein the views of the participants are recorded) and must be included in Appendix F.

Please note that proof of the PPP conducted must be included in Appendix F. In terms of the required "proof" the following is required:

- a site map showing where the site notice was displayed, dated photographs showing the notice displayed on site and a copy of the text displayed on the notice;
- in terms of the written notices given, a copy of the written notice sent, as well as:
 - if registered mail was sent, a list of the registered mail sent (showing the registered mail number, the name of the person the mail was sent to, the address of the person and the date the registered mail was sent);
 - if normal mail was sent, a list of the mail sent (showing the name of the person the mail was sent to, the address of the person, the date the mail was sent, and the signature of the post office worker or the post office stamp indicating that the letter was sent);
 - if a facsimile was sent, a copy of the facsimile Report;
 - if an electronic mail was sent, a copy of the electronic mail sent; and
 - if a "mail drop" was done, a signed register of "mail drops" received (showing the name of the person the notice was handed to, the address of the person, the date, and the signature of the person); and
- a copy of the newspaper advertisement ("newspaper clipping") that was placed, indicating the name of the newspaper and date of publication (of such quality that the wording in the advertisement is legible).

SECTION G: DESCRIPTION OF THE RECEIVING ENVIRONMENT

All specialist studies must be attached as Appendix G.

1. Groundwater

1.1.	Was a specialist study conducted?	YES	NO x
1.2.	Provide the name and or company who conducted the specialist study.		
N/A			
1.3.	Indicate above which aquifer your proposed development will be located and explain how this has influenced your proposed development.		
N/A			
1.4.	Indicate the depth of groundwater and explain how the depth of groundwater and type of aquifer (if present) has influenced your proposed development.		
N/A			

2. Surface water

2.1.	Was a specialist study conducted?	YES X	NO
------	-----------------------------------	-------	----

2.2.	Provide the name and/or company who conducted the specialist study.
Enviroswift and Delta Ecology	
2.3.	Explain how the presence of watercourse(s) and/or wetlands on the property(ies) has influenced your proposed development.
The presence of an Unchanneled Valley-Bottom (UVB) wetland, centrally located within Erf 1486, Vermont, has played a critical role in shaping the design and layout of the proposed residential development as well as the application of the Mitigation Hierarchy. The wetland on site, forms part of a larger 1.4 km-long hydrological system that ultimately connects to the Vermont Salt Pan. It is important to note that during this impact assessment process, the boundaries of the Wetland have been delineated several times by 3 independent Freshwater Specialists. In August 2018, Joshua Gericke (Enviroswift) conducted a Wetland Screening and Delineation (Appendix F1), this was conducted to inform the application process going forward. Kim van Zyl of Delta Ecology was then appointed to conduct the Freshwater Impact Assessment for the proposed development and May 2023 conducted another wetland delineation. In August 2025, in response to comments received during Public Participation 3, the EAP appointed a third independent specialist to undertake a third, independent wetland delineation. The 2025 delineation confirmed that the extent of the wetland is consistent with both the 2018 delineation conducted by Enviroswift and the 2023 delineation conducted by Delta Ecology, and therefore the wetland delineation is regarded as accurate for planning purposes within this impact assessment.  Wetland delineation 1 – Conducted in May 2018 by Enviroswift (Joshua Gericke)	



Wetland delineation 2 – Conducted in August 2023 by Delta Ecology (Kim van Zyl)



Wetland delineation 3 – Conducted in response to PPP3 comments by Nick Steytler

Aquatic Biodiversity Impact Assessment (van Zyl, 2025)

The presence of a delineated Unchanneled Valley-Bottom (UVB) wetland on Erf 1486, Vermont has played a critical role in shaping the proposed development layout. This wetland, which is part of a broader 1.4 km-long natural system hydrologically connected to the Vermont Salt Pan, was delineated through assessments conducted by EnviroSwift (2018) and updated by Delta Ecology in 2023. It exhibits moderate Ecological Importance and Sensitivity (EIS) despite being in a largely modified Present Ecological State (Category D), due to historical disturbances such as excavation, vegetation clearing, and infilling.

The delineated wetland was assessed as having moderate value in terms of ecosystem services particularly sediment trapping, phosphate and toxicant assimilation, and carbon storage and was confirmed to still exhibit functioning hydromorphic soils. Vegetation within the property was identified to be extensively disturbed, with a mixture of indigenous species such as *Senecio halimifolius* and the wetland obligate *Juncus kraussi* alongside alien invasive species such as Kikuyu grass (*Cenchrus clandestinum*) and pampas grass (*Cortaderia selloana*). While the latter species is not wetland obligate, it is commonly found in wetlands where it grows particularly densely (van Outshoorn, 2014). An additional wetland obligate species, *Typha capensis*, was also found in isolated patches during the site assessment.

The hydrology was observed on the site with runoff from the neighbouring housing estate's stormwater system into the depression clearly visible. Terrestrial soils within the study area are dark grey, sandy and appear to be well drained. Soils that were sampled in wetter areas near the depression did not differ markedly from terrestrial soils, aside from appearing darker and with a higher organic content than the terrestrial baseline. Mottling and gleying are not expected in this wetland. Mottling was however found in isolated patches on the southern periphery of the depression in brown soils that are likely the result of limited historical infilling. The wetland was delineated at the outer boundary of the temporary zone. The presence of saturated, high carbon soils and isolated instances of mottling within the upper 500 mm of the soil was used in conjunction with the presence of hydrophytic vegetation to delineate the wetland. The excavated depression represented the permanent zone.




Figure 8: Overview of the hydrological connectivity from the subject property (red) to the Vermont Salt Pan (blue).



Photo 1: View of the existing building structures on the subject property.



Photo 2: Wetland obligate *Juncus kraussi* indicated by the arrow. This species, along with *Senecio halimifolius*, were used as primary indicators of the outer boundary of the wetland within the study area.



Photo 3: Dense clumps of alien invasive *Pennisetum clandestinum* along the edges of the depression within the study area, particularly where sediment dredged from the depression was dumped.



Photo 4: Additional wetland species *Typha capensis*, located in front of the derelict buildings onsite.




Photo 5: A) Near-surface soil sample, showing typical terrestrial soil conditions within the study area. Terrestrial soils within the study area are sandy, characterised by a uniform grey - brown colour, with no mottling, gleying or organic matter visible. B) Near-surface soil sample, taken within a wet area; darker chroma observed.




Photo 6: A) Soil taken from within a wet area. Rusty orange-coloured mottles are observed; alongside fill material and B) rusty orange mottle (red circle) observed in high carbon, dark soils from a wet area.

Pipeline upgrade

The existing pipeline to be upgraded is located along Kogans Close and Malmok Road (**Figure 9**). The wetland area along the stretch of this road where the pipeline is to be upgraded, is critically degraded, i.e. relic or historical, due to infill from the road. Other notable impacts to the general UVBW in this vicinity include artificial channels, roads, residential dwellings, excavation, and culverts, which have altered natural flow regime, vegetation, water quality and geomorphology.

The vegetation within the functional UVB wetland downslope / adjacent to the road, consists of wetland obligate species *Juncus kraussii*, *Cyperus textilis*, with wetland facultative *Senecio halimifolius* and *Zantedeschia Aethiopica* along the outer boundary of the functional wetland area.

Soils that were sampled in the UVB wetland did not differ markedly from terrestrial soils, aside from appearing darker and with a higher organic content than the terrestrial baseline.

Given that the Erf, and the proposed pipeline to be upgraded, are located more than 387 m away from the Vermont Salt Pan, no impacts to this wetland as a result of the project is expected. Therefore, the only watercourse deemed to be “At Risk” is the UVBW on Erf 1486.



Photo 7: *Zantedeschia Aethiopica* in the UVB wetland along the existing road.



Photo 8: Channel along the road, within the UVB wetland.



Photo 9: Channel within the UVB wetland.




Figure 9: View of the area where pipeline upgrades will be required. Minor excavation is anticipated within the area indicated by the yellow circle.

Present Ecological State

The Macfarlane *et al.* (2020) WET-Health Version 2.0 assessment produced an overall Present Ecological State (PES) score within category D. This indicates that the wetland was in a largely modified condition at the time of the assessment. The key factors that influenced the scoring are summarised below.

Hydrology

- The natural flow regime of the UVB Wetland (UVBW) has been altered as a result of disturbances such as the excavation to create the centre depressional area on the erf itself, historical vegetation clearing and infilling, and catchment hardening associated with the roads, dirt tracks, residential areas.
- Although there is an overflow pipe that crosses beneath Lynx Road and flows into the wetland on the far side, the construction of Lynx Road, and excavation within the centre of the site, has created a dam within the centre of the UVBW.
- The presence of nutrient rich laterite, in soils that are naturally nutrient poor, such as those on the proposed development area, are associated with the dominance of invasive species such as the dense clumps of Kikuyu grass (*Pennisetum clandestinum*) seen onsite, which leads to altered surface roughness and therefore altered flow regimes in the wetland.
- The hydrology of the UVBW has been impacted by the presence of urban residential land use within the wetland itself, and in the wetland's immediate catchment area. Urban land use such as residential areas and tarred roads has resulted in flow diversion and catchment hardening which is associated with increased runoff and storm peak flows.
- The wetland has been canalized, leading to concentration of flow, and likely the drying out of the wetland in various locations.

- Additionally, a stormwater outlet is in the southeast corner of the erf, which discharges runoff from the neighbouring housing development into the wetland. Additional stormwater outlets into the wetland are observed downstream of the erf.

Vegetation

- While several communities of indigenous hydrophytic species were noted, there was moderate vegetation disturbance within the wetland area as a result of:
 - The excavation of the dam on the erf;
 - Large areas of the UVBW on the erf were brush cut during 2004, and downstream of the erf large areas were cleared during 2022;
 - Construction activities associated with the derelict houses on the erf, and downstream residential areas;
 - Dumping of rubble within the wetland area.
- The vegetation present within the wetland is characterised by a mixture of alien and indigenous vegetation. Alien invasive species noted onsite include dense clumps of Kikuyu grass (*Cenchrus clandestinum*) and pampas grass (*Cortaderia selloana*).
- No species of conservation concern were noted. According to the Botanist appointed for the proposed project, at least one plant SoCC (*Disa hallackii*) may be present in low numbers (Nick Helme Botanical Surveys, 2023).

Geomorphology

- The geomorphology of the UVBW wetland was largely modified by the excavation of the depressional / dam area in the centre of the erf.
- Additionally, historical vegetation clearing, infilling, and hardening across large areas of the wetland has resulted in extensive disturbance to its natural geomorphic state.
- The wetland system extends from the study area in a south-easterly direction and ultimately augments the Vermont Salt Pan. The construction of Lynx Road, Kolgans Close Road, and numerous other roads, has seriously altered this portion of the UVBW's geomorphology.

Water Quality

The water quality within the UVB wetland has been disturbed because of the adjacent infilling and compaction of the southern portion of the Erf; along with large portions which have been infilled which has resulted in:

- Leaching of toxicants and nutrients from the infilling materials such as hydroxyl ions from cement particles and nitrates from laterite.
- The water quality within the wetland is likely to be impacted by the residential nature of the catchment.
- It is likely that runoff entering the wetland through the stormwater outlets is likely polluted by the surrounding catchment area for example, runoff from roads is likely to contain contaminants such as laterite, oil, fuel, rubber from car tires and other pollutants.

At the outset of the planning process, several site-specific sensitivities were identified that warranted avoidance. These included the ecological corridor linking the Walker Bay Nature Reserve to the Vermont Salt Pan. An initial preferred layout during the first round of public participation attempted to avoid the permanent wetland, however, further site analysis revealed that some erven were still encroaching into the wetland zone. This would have compromised wetland functioning and faunal movement. In response, a revised site development plan, Alternative 4, has been formulated in direct response to specialist findings and concerns raised during the public participation process. These concerns primarily related to the functionality of the wetland and its hydrological connectivity with the adjacent Vermont Salt

Pan. Under the revised layout, all proposed residential erven are located outside the delineated permanent and seasonal wetland area.

The layout of the access roads under Alternative 4 will result in a minor loss of approximately 0,024 ha (3 %) of the 0,90-ha wetland, this is significantly reduced compared to the previous alternatives and is considered acceptable by the freshwater specialist, provided that mitigation measures and a comprehensive Wetland Offset and Rehabilitation Management Plan are implemented. The maintenance of an ecological link along the entire system, remains an important consideration. In the final preferred layout, all of the permanent wetland as well as the seasonal wetland areas are excluded from development.



Figure 10: Location of infrastructure and landmarks within and adjacent to the study area.




Figure 11a: Amended layout Alternative 4 – new and final preferred

The potential impacts to the UVBW as a result of the proposed development are listed below:

Construction Phase

- Areas of the onsite UVBW will be lost (i.e. complete loss in flow regime, water quality, vegetation, and geomorphic structure) as a result of the private road construction (Minor loss of approximately 0,024 ha (3 %) of the 0,90-ha wetland).
- Habitat disturbance within the UVBW may occur due to the construction of residential housing and the upgrade of the sewer pipeline.
- Alteration of the flow regime of the UVBW during construction of the residential housing.
- Water quality impairment due to increased sediment input, potential spillage, or release of potentially contaminated runoff into the UVBW during construction of the residential housing and the upgrade of the sewer pipeline.

Operational Phase

- Habitat disturbance due to the use of the wetland as a public open space (likely); and any maintenance associated with the sewer pipeline.
- Alteration of the flow regime of the UVBW once the housing development is complete, due to potential flow diversion / increase in storm flows – stormwater management plan includes freshwater recommended mitigation measures.
- Water quality impairment due to the release of potentially contaminated stormwater (hydrocarbons) into the UVBW; and potential leakage associated with the sewer pipeline and maintenance thereof.

2025 Wetland Delineation (Nick Steytler)

A follow-up wetland delineation was undertaken on 03 August 2025 by EnviroSwift, following concerns raised during the public participation process where I&APs requested an additional independent assessment. This was the third delineation on the property, with previous studies conducted in 2018 and 2023.

The delineation was carried out in line with the (DWAF, 2008) and supplemented by the Job (2009) method tailored for Western Cape soils. Due to the region's atypical wetland soil indicators (low iron content and gley soils), the assessment relied strongly on wetland vegetation indicators such as *Orphium frutescens*, *Stenotaphrum secundatum*, *Elegia nuda*, and *Zantedeschia aethiopica*. *Plecostachys serpyllifolia* was commonly observed in areas of the site located outside the permanent wetland zone. The permanent wetland zone itself was characterised by the presence of indicator species such as *Juncus kraussii*, *Typha capensis*, and *Phragmites australis*. While *P. serpyllifolia* is often associated with seasonally wet areas, it is also a strong indicator of disturbance. Its presence alone is therefore not considered sufficient evidence of wetland conditions. In this case, the occurrence of *P. serpyllifolia* within the more terrestrial portions of the site is interpreted as being linked to past disturbance rather than true wetland habitat conditions. Furthermore, areas outside the permanent wetland zone were generally dominated by terrestrial vegetation, with wetland-associated species restricted to the delineated seasonal and permanent zones.

The study confirmed the presence of a wetland temporary/seasonal zone, with the outer boundary delineated using a GPS survey. When compared with the most recent 2024 delineation (Delta Ecologists), no material differences were found between the two delineations. EnviroSwift has therefore endorsed the Delta delineation, noting that any minor discrepancies are attributed to differences in mapping tools rather than ecological interpretation.



Figure 11b: Wetland Delineation (EnviroSwift, 2025).



Figure 11c: Comparison between wetland delineation conducted in 2023 (Van Zyl) vs delineation by Steytler in 2025.
No material difference is evident between the two delineations



Figure 11d: *Orphium frutescens* occurring in the wetland seasonal zone. (Steytler, 2025)



Figure 11e: *Zantedeschia aethiopica* growing alongside a partially demolished wall near the existing building on the site. Source: (EnviroSwift, 2025).



Figure 11f: *Plecostachys serpyllifolia* growing in the terrestrial part of the site, likely as a result of disturbance rather than wetland conditions. Source: (Enviroswift, 2025).

Stormwater Management Plan

The Stormwater Management Plan was developed to address the site-specific hydrological dynamics influenced by the wetland and its surrounding catchment. The site, characterized by a flat gradient draining eastward toward the Vermont Salt Pan, is part of a larger catchment with steep mountainous terrain to the north (Catchment Area 1, CA1) and the development site to the south of the R43 (Catchment Area 2, CA2). Hydrological assessments, utilizing the Alternative Rational Method for peak flow runoff calculations and PCSWMM for a 24-hour SA Type 1 SCS storm, revealed minimal differences between pre- and post-development runoff for both CA1 and CA2, as shown in **Tables 3-4** below. However, runoff from CA1 discharges through culverts under the R43 into CA2 and the wetland's natural attenuation area (approximately 10,000 m²), slightly increasing peak flows at the Lynx Avenue culvert post-development (**Table 4**). Water level increases in the wetland remain minimal, with a maximum post-development rise of 0.69 m for a 100-year storm event (**Table 5**). These findings underscore the need for robust stormwater management to mitigate potential impacts on the wetland's hydrological and ecological functions.

Control Quantity and Rate of Runoff

To address these challenges, the preferred layout, Alternative 4, was designed to avoid development within the permanent and seasonal wetland zone, restricting unavoidable encroachment to 0.024 ha of the wetland area (3% of this zone), primarily affected by the proposed access roads. The majority of the wetland is designated as Private Open Space, with strict construction management and no development areas included in the design. The Stormwater Management Plan incorporates Low Impact Development (LID) measures, including a permeable paving system south of the wetland and an enhanced swale system to the north, to manage both the quantity and rate of runoff. These measures, detailed in **Tables 9** and **10** of the Stormwater Management Plan, are designed to maintain post-development runoff at levels comparable to pre-development conditions, ensuring that wetland water levels are sustained in a controlled manner in order to protect the development while minimizing potential downstream impacts.

Improving Water Quality from the Development

The proposed development includes measures to ensure that rainwater runoff from the site does not harm the surrounding wetland or other natural areas. Rainwater flowing off roads, roofs, and paved surfaces can carry pollutants such as dirt, nutrients, and metals. To reduce these impacts, the development will use a combination of permeable paving and a vegetated swale system.

Permeable Paving:

- This is a special type of paving that allows rainwater to soak through the surface rather than running off immediately.
- The water passes through layers of gravel and soil, which naturally filter out pollutants before the water enters the wetland.
- The system is designed to handle the volume of water from typical storm events and to retain water for slow release, helping maintain the wetland's water levels.

Enhanced Swale System:

- A swale is a shallow, vegetated channel designed to guide stormwater safely across the site.
- As water flows through the swale, plants and soil help remove pollutants and slow down the water, reducing the risk of flooding and erosion.

- Important to note that the swale system was shifted as part of the refinement of the preferred layout and no longer falls within the seasonal or permanent wetland area.

Together, these measures will significantly improve the quality of water entering and leaving the site, reducing nutrients, sediments, and other pollutants. This helps protect the wetland, supports wildlife, and ensures the development blends responsibly with the natural environment.

Further mitigating flood risks, the plan proposes controlling stormwater runoff from a 2 x 600 mm diameter culvert under the R43 road (**Figure 13a**) through a 2 x 900 mm diameter pipes within Erf 1486 (**Figure 13b**), ensuring measured discharge without flooding the development. Properties will be elevated at least 1.0 m above the wetland level to protect against inundation. Regular inspection and maintenance schedules for the permeable paving and swale systems are indicated in Tables 13 and 14 of the Stormwater management plan to ensure long-term functionality, preventing sediment buildup and maintaining infiltration capacity. Additionally, the Wetland Offset, Rehabilitation, and Management Plan also compliments these measures, aligning with the Department of Water and Sanitation’s “no net loss” policy to rehabilitate and enhance the remaining wetland areas.




Figure 12: Catchment area of site for development.

Table 3: Pre- and Post development Runoff -CA1

Return period	Pre-development (m ³ /s)	Post-development (m ³ /s)
Q2	1.72	1.72
Q5	2.55	2.55
Q10	3.19	3.19
Q20	3.89	3.89
Q50	4.93	4.93
Q100	5.82	5.82

Table 4: Pre- and Post development Runoff -CA2.

Return Period	Pre-development (m ³ /s)	Post-development (m ³ /s)
Q2	0.29	0.29
Q5	0.41	0.41
Q10	0.51	0.50
Q20	0.61	0.60
Q50	0.76	0.75
Q100	0.89	0.88

The catchment area North of the R43 (CA1) discharge through the R43 via various culverts along the road, which discharge to the catchment area South of the R43 (CA2). Both catchment areas discharge into a natural attenuation facility, which forms part of the wetland area. It was accepted that the attenuation area provides approximately 10 000m² in area. Should this natural attenuation area be taken into consideration, the peak flow runoff for the various recurrence interval storm events that discharge through the existing 2 x 750mm x 0.5mm box culvert in Lynx Avenue are as follows:

Table 5. Pre- and Post development Runoff – Culvert at Lynx Avenue.

Return Period	Pre-development (m ³ /s)	Post-development (m ³ /s)
Q2	0.669	0.727
Q5	1.071	1.106
Q10	1.420	1.467
Q20	1.831	1.892
Q50	2.491	2.575
Q100	3.107	3.211

The maximum depth that the water rises in the wetland area during the various recurrence interval storm events are as follows:

Table 6: Pre - and Post development water level in attenuation area.

Return Period	Pre-development (m)	Post-development (m)
Q2	0.29	0.29
Q5	0.38	0.38
Q10	0.44	0.45
Q20	0.51	0.52
Q50	0.60	0.61
Q100	0.67	0.69



Figure 13a: Drawing 2 – Culverts along R43 and discharge through Lynx Avenue.



Figure 13b: Position of proposed stormwater control through development via a 2 x 900mm pipes.



Figure 14: Proposed location of Permeable Paving and Enhanced Swale.

Permeable paving for section south of wetland:

The permeable paving system is proposed on the southern section of the site to reduce water flow and improve post development infiltration as indicated in **Table 7** and **Figure 15** below:

Table 7: Criteria of Permeable Paving System.

ITEM	VALUE	COMMENT
SURFACE		
Storage Depth	50mm	Kerb height
Vegetation Fraction	0	No Vegetation growth
Manning n	0.03	
Surface Slope	0.5%	
PAVEMENT		
Thickness	80mm	
Void Ratio	0.12	10% voids in paving
Impervious Surface	0	Total surface as permeable paving
Permeability	360mm/hour	For clogged paving system
Clogging Factor	0	Taken into consideration above
STORAGE		
Height	400mm	Base course depth
Void Ratio	0.43	30% voids in base course
Conductivity	120mm/h	Conductivity of in-situ material
Clogging Factor	0	Taken into consideration above
UNDERDRAIN		
Drain Coefficient	1.667mm/hour	
Drain Exponent	0.5	Conduit
Drain Offset	0	Invert of Base course

The road structure is proposed to be as follows:




Figure 15: Proposed Permeable Paving System.

Table 8: Enhanced Swale for section North of the wetland.

ITEM	VALUE	COMMENT
SURFACE		
Storage Depth	400mm	
Vegetation Fraction	0.75	No Vegetation growth
Manning n	0.24	
Surface Slope	0.5%	
STORAGE		
Height	750mm	Base course depth
Void Ratio	0.43	30% voids in base course
Conductivity	120mm/h	Conductivity of in-situ material
Clogging Factor	0	Taken into consideration above
UNDERDRAIN		
Drain Coefficient	1.667mm/hour	
Drain Exponent	0.5	Conduit
Drain Offset	0	




Figure 16a: Proposed Enhanced Swale System.

Control of Erosion and Litter

To protect the wetland and surrounding areas from erosion and litter, all points where stormwater leaves the development and enters the wetland will be carefully managed. These points (1,2,3 indicated below) include:

- 1: Outlet for stormwater from the mountains above the R43 with swale outlet
- 2: Outlet for the permeable paving and stormwater in road
- 3: Outlet for stormwater along road.

At each of these outlets, gabion control measures will be installed (refer to Stormwater Management Plan). Gabions are wire cages filled with stones that:

- Slow down the flow of water to prevent soil erosion.
- Trap litter and debris, stopping it from entering the wetland.
- Allow water to continue flowing in a controlled manner while protecting the soil and vegetation.

These measures are designed to ensure that water entering the wetland is clean and flows in a controlled way, which helps maintain the ecological health of the area.




Figure 16b: Showing the position of the outlet's structures.

Conclusions provided by the Engineer:

- The proposed permeable paving and vegetated swale system will reduce the post development runoff to equal or less than the pre-development recurrence interval storm.
- The proposed permeable paving and swale system will ensure that the water level in the attenuation area will remain to that of the pre-development level.
- The proposed permeable paving and swale system will treat the stormwater runoff quality to the acceptable requirements.
- The stormwater runoff from above the R43 be controlled to discharge through the site for development as proposed.
- The development will be protected from flooding by ensuring that the properties are above at least 1.0 m in high above the wetland.

→ That all outlet structures be provided with erosion and litter control structures.

Wetland Offset, Rehabilitation and Management Plan

Wetland Loss

The preferred layout (Alternative 4) results in a loss of approximately 0.024–0.027 ha (3%) of the wetland, confined to the eastern and southern access roads. For conservatism, the upper figure of 0.027 ha was used in all calculations. The remaining 0.846 ha is designated as private open space and forms the offset area.

Table 9: Offset Calculation (Macfarlane et al. 2016)

	Function (HE)	Habitat (HE)
Loss	0.0157	0.1985
Gain (rehabilitation)	0.1173	1.0025
Net surplus	0.1016	0.8041

The offset is considered satisfied with a meaningful net ecological gain

Rehabilitation Programme

Fill removal: all foreign fill material and rubble to be removed at the start of summer (not winter) to avoid sedimentation; site to be reshaped to restore the gentle slopes characteristic of a UVB wetland (central basin 0–1%, transitional edge 1–3%).

Alien invasive species removal: priority species are Pampas grass (*Cortaderia selloana*, NEMBA Category 1b), Kikuyu grass (*Cenchrus clandestinus*), Port Jackson (*Acacia saligna*), and Rooikrans (*Acacia cyclops*). Earthworks must avoid the Western Leopard Toad breeding season (late July to September). Herbicide application restricted to dry summer months.

Revegetation: a minimum of six locally indigenous wetland species to be planted at approximately 4 plants/m², targeting 80% vegetation cover within 8–12 months. Recommended species include *Cyperus textilis*, *Bolboschoenus maritimus*, *Elegia capensis*, and *Senecio halimifolius*. *Typha capensis*, although present naturally, is excluded from planting due to its invasive tendency. Best planting window is autumn (March–May). Plants to be sourced from Kraaibosch Nursery, Fynbos Life Nursery, or Kirstenbosch, with 12 months' notice recommended.

Stormwater management: all measures in the Stormwater Management Plan must be strictly implemented. Vegetated swales, permeable paving, rainwater harvesting tanks, sediment traps, and energy dissipaters are all required. Herbicides and pesticides within private gardens are strictly prohibited.

Improved flow regime along Lynx Avenue: additional or enlarged culverts recommended to restore more natural flow and reduce back-flooding in the central depression. Design to be done by a suitably qualified engineer in consultation with an aquatic ecologist.

Target Ecological State

The rehabilitation aim is to elevate the wetland's Present Ecological State (PES) from Category D (largely modified) to upper Category C (moderately modified), with a minimum WET-Health PES score of 79%.

Monitoring

During rehabilitation: a minimum of two specialist site visits (after fill removal, and 12 months after planting), with annual visits if the PES target has not been met. Fixed-point photography from at least four GPS-marked points, conducted annually.

Post-rehabilitation: an independent environmental audit every five years using WET-Health Version 2.0, assessing PES, vegetation cover, erosion, and alien species presence.

Formal Protection

A conservation servitude over the 0.9361 ha offset area must be registered as a title deed restriction, preventing any future development within the wetland in perpetuity. The WUL holder (owner of Erf 1486) bears full responsibility for implementing the plan and appointing qualified implementing agents.

Specialist Conclusion

The plan is considered practically implementable. The specialist concludes that implementation would result in substantial biodiversity gains and that approval of the development, subject to this plan as a condition, is acceptable from a wetland and biodiversity perspective.



Figure 17: Wetland area to be lost and developed.

Below mitigation measures have been recommended by the Freshwater specialist:

- Discharge stormwater from rooftops into rain harvesting tanks. This will limit the volumes of stormwater runoff that will reach the wetland. Where possible, water collected in rain harvesting tanks can be utilised for flushing of toilets, washing etc.
- Vegetated swales must be utilised rather than concrete drains or underground stormwater pipes in order to encourage infiltration, particularly next to roadways.
- Energy dissipaters / erosion protection measures (such as lining with stones, grass, reno-mattresses, or gabions) must be constructed where stormwater is released in order to reduce the runoff velocity and therefore erosion.
- Sheet runoff from hardened surfaces must be intercepted and the treatment and infiltration of runoff must be promoted.
- Sediment traps should be incorporated into stormwater drains / swales upstream of all discharge points into the wetland.
- All stormwater draining into the wetland must receive basic filtering and treatment prior to its release.
- Incorporate measures into the stormwater design to trap solid waste, debris and sediment carried by stormwater. Measures may include the use of curb inlet drain grates and debris baskets/bags.
- Stormwater generated from areas with a higher risk of contamination such as parking areas and roads must receive basic filtering and treatment prior to its release into surrounding areas. Treatment methods may include sand filter traps and oil-water separators which will require maintenance.
- The extent of hardened surfaces must be minimised. E.g. where required permeable paving must be used.

- Homeowners must be encouraged to landscape their gardens with the use of indigenous species to decrease the area of hardened surface and increase infiltration.
- Homeowners should store any potential pollutants in such a way that pollution will not occur to the wetland (such as any fuel, etc.). Potential pollutants should be stored in an adequately bunded area.
- The use of herbicides, pesticides and any other poisons within private gardens must be strictly prohibited. The home owner's association must be responsible for ensuring that residents are compliant with this.
- Backwashing of swimming pools directly into the wetland must be strictly prohibited. Backwash water can be collected in settling tanks where dirt and debris settle to the bottom. The cleaner water can then be reused for non-potable purposes or even filtered back into the pool system. Backwash water can be diverted to greywater tanks.
- Monitor the proposed development and adjacent wetland for erosion and sedimentation after heavy rainfall events. Any erosion noted must be immediately addressed. Rehabilitation measures may include the removal of accumulated sediment by hand, filling of erosion gullies and rills, the stabilisation of gullies with silt fences, riprap, and the revegetation of stabilised areas.
- Stormwater systems will require ongoing maintenance. Any build-up of silt or debris within stormwater drains or swales will need to be cleared to ensure the continued functioning of the systems.
- Any damage to stormwater infrastructure, and any flaws identified in the functionality of stormwater infrastructure, must be rectified immediately.
- Stormwater systems must be monitored and maintained into perpetuity and collections of debris and solid waste removed from grates and baskets. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles.
- The stormwater system must be designed by a suitably qualified engineer with input from an aquatic specialist.

3. Coastal Environment

3.1.	Was a specialist study conducted? NOT APPLICABLE	YES	NO x
3.2.	Provide the name and/or company who conducted the specialist study.		
N/A			
3.3.	Explain how the relevant considerations of Section 63 of the ICMA were taken into account and explain how this influenced your proposed development.		
N/A			
3.4.	Explain how estuary management plans (if applicable) has influenced the proposed development.		
N/A			
3.5.	Explain how the modelled coastal risk zones, the coastal protection zone, littoral active zone and estuarine functional zones, have influenced the proposed development.		
N/A			

4. Biodiversity

4.1.	Were specialist studies conducted?	YES x	NO
4.2.	Provide the name and/or company who conducted the specialist studies.		

Nick Helme of Nick Helme Botanical Surveys – Terrestrial Biodiversity Impact Assessment

Jan Venter – Terrestrial Animal Site Sensitivity Verification Report and Compliance Statement

- 4.3. Explain which systematic conservation planning and other biodiversity informants such as vegetation maps, NFEPA, NSBA etc. have been used and how has this influenced your proposed development.

1. Terrestrial Biodiversity Impact Assessment Report (Botanical and Plant Species Assessment)

The systematic conservation planning, supported by Cape Nature BSP, SA vegetation maps, NFEPA, NSBA, and other biodiversity informants analysed via a desktop study, played a collaborative role in positively shaping the proposed development. Following the guidelines outlined in the Western Cape Biodiversity Spatial Plan (2023), the chosen development site is strategically positioned within the Ecological Support Area (ESA2). While it incorporates this section of the ESA2, it falls outside the Priority Area. The botanical report highlights the significance of the study area within the Southwest Fynbos bioregion, emphasizing its high biodiversity value and the presence of numerous threatened plant species.

SA Vegetation Map (2024) shows the regional extent of the original natural vegetation in the study as Hangklip Sand Fynbos. This vegetation is now gazetted as Critically endangered according to NEM:BA, 2004 (ACT NO. 10 of 2004). Less than 68% of the vegetation extent still remains intact, while less than 18% of its portion is conserved, and the 30% of it is the national conservation target.

A site survey, supported by Google Earth imagery, indicates that the vegetation on the property has not been affected by fire for at least the past 20 years, implying that the vegetation on site is senescent (some species dying of old age; diversity dropping), as this type of Fynbos should burn once every 10-14 years for optimal ecological functioning.



Photo 10: View south from near the northeastern corner, with non-wetland vegetation in the foreground, grading into wetland vegetation after about 6m. *Source:* Helme, (2023).



Photo 11: View south along the western boundary. Indigenous buffalo grass (*Stenotaphrum secundatum*) is dominant in the foreground. Source: Helme, (2023)



Photo 12: View of the central wetland channel, looking east, with indigenous *Juncus kraussii* (steekbiesie) dominant. The tall, showy grass at left is the declared alien invasive pampas grass (*Cortaderia selloana*) and should be removed.



Photo 13: View of the southwest corner of the erf, looking west, showing how someone (presumably neighbours) have taken it upon themselves to garden this area. Most of the planted species are aliens or horticultural varieties not present in Fynbos systems. *Source:* (Helme, 2023)



Photo 14: View of the southeast corner of the erf, looking east, showing extensive invasion of alien kikuyu grass (*Cenchrus clandestinus*) in the previously disturbed area. The dark trees at left are milkwoods (*Sideroxylon inerme*), possibly planted here.

Photographs taken during the site visit reveal the presence of existing vegetation, which is extensively invaded by alien Kikuyu grass (*Cenchrus clandestinus*). Additionally, five fairly large milkwood trees (*Sideroxylon inerme*), likely planted, were observed on site (**Photo 14**). From a botanical perspective, there is evidence of brush cutting on the southern side of the wetland. Historical imagery also shows that the first houses were constructed along the southern boundary of the site in the period 2007-2009, suggesting early disturbance in that area.

The previously disturbed areas are in three main patches: the current, occupied building area; the northeastern edge of the main wetland; and the southern boundary. Many of the disturbed areas are dominated by alien invasive kikuyu grass (*Cenchrus clandestinus*), which tends to smother any indigenous seedlings. The southwestern edge of the erf has been gardened (**Photo 13**) with all manner of non-locally indigenous species planted, including *Pelargonium* hybrids, *Ficus* species, *Searsia pendulina* and *Arctotis stoechadifolia*. At least two bird Species of Conservation Concern (SoCC) may use the site for foraging, and at least one plant SoCC (*Disa hallackii*) may be present in low numbers, but no plant or animal SoCC were recorded on site during the survey.

Large alien invasives are present on site but occur at a low density (<2% cover), and include *Leptospermum laevigatum* (Australian myrtle), *Cortaderia selloana* (pampas grass), *Hakea drupacea* (sweet needlebush), *Acacia saligna* (Port Jackson) and *Acacia cyclops* (rooikrans), evidently thanks mostly to some active alien vegetation removal that takes place regularly.

The permanent wetland area has clearly become significantly more vegetated in the last five years (compared to photos in the EnviroSwift wetland report of 2018) and is now in good condition. Indigenous plant species include *Senecio halimifolius*, *Juncus kraussii*, *Orphium frutescens*, *Typha capensis*, *Plecostachys serpyllifolia*, *Schoenoplectus scirpoides*, *Juncus lomatophyllus*, *Isolepis striata*, *Nidorella ivifolia*, *Nidorella pinnatifida*, *Fuirena coerulescens*, *Laurembergia repens* and *Elegia nuda*.

About 50% of the site is made up by what could be considered permanent wetland, but that is not seasonally inundated or flooded (mostly indicated as seasonal wetland in the Freshwater Screening (EnviroSwift 2018). Indigenous species in this area include *Senecio halimifolius*, *Juncus kraussii*, *Orphium frutescens*, *Plecostachys serpyllifolia*, *Nidorella ivifolia*, *Nidorella pinnatifida*, *Fuirena coerulescens*, *Laurembergia repens*, *Zantedeschia aethiopica*, *Stenotaphrum secundatum*, *Cynodon dactylon*, *Senecio rigidus*, *Cyperus sphaerospermus*, *Pycreus* sp., *Juncus cephalotes* and *Elegia nuda*.

The non-wetland portions of the site that have not been totally disturbed and they support the following indigenous plant species: *Passerina corymbosa*, *Thamnochortus insignis*, *Stenotaphrum secundatum*, *Seriphium plumosum*, *Pelargonium capitatum*, *Searsia lucida*, *Colpoon compressum*, *Mesembryanthemum canaliculatum*, *Struthiola ciliata*, *Metalasia muricata*, *Osteospermum moniliferum*, *Cliffortia stricta*, *Oxalis dentata*, *O. pes-caprae*, *Carpobrotus edulis* and *Athanasia trifurcata*.

The non-wetland portions of the site that have not been totally disturbed support the following indigenous plant species: *Passerina corymbosa*, *Thamnochortus insignis*, *Stenotaphrum secundatum*, *Seriphium plumosum*, *Pelargonium capitatum*, *Searsia lucida*, *Colpoon compressum*, *Mesembryanthemum canaliculatum*, *Struthiola ciliata*, *Metalasia muricata*, *Osteospermum moniliferum*, *Cliffortia stricta*, *Oxalis dentata*, *O. pes-caprae*, *Carpobrotus edulis* and *Athanasia trifurcata*.

Plants species of Conservation Concern

No plants Species of conservation concern have been identified during the site survey, the specialist also highlights that there is likely occurrence of at least one species, *Disa Hallackii*, which is endangered and has been recorded in the nearby erf, and that there are various records of this species type from Onrus and Vermont area. According to the specialist this species type is most evident in the first few years after a fire, since the vegetation on the property is in senescent state and has not been burnt for more than twenty years, this mitigates against finding it onsite.

Fauna

Two species of frogs were heard calling on site, and populations on site are probably viable and significant. *Hyperolius marmoratus* (painted reed frogs) were calling from the standing water, whilst *Strongylopus grayii* (clicking stream frogs)

were calling across most of the site. *Cacosternum australis* may also occur here, but was not heard. An animal species of conservation concern *Bradypodion pumilum* (Cape Dwarf Chameleon) is likely to be present on site, since it has been recorded from similar nearby habitat. Additionally, no other Reptile Redlist species are considered to be present on site. The Southern Adder (*Bitis armata*; Vulnerable) has been flagged by the Screening Tool for the region but is unlikely in this habitat.

The botanical specialist highlights that at least two bird's species may occasionally visit this site, this includes African Marsh Harrier (*Circus ranivorus*; Endangered) and the Black Harrier (*Circus maurus*; Endangered), which are known from the general area and travel widely.

While Blue Cranes (*Anthropoides paradiseus*), Lesser Flamingos (*Phoenicopterus minor*), and Greater Flamingos (*Phoenicopterus roseus*) all listed as Near Threatened have been recorded in the greater Vermont Pan area, the specialist indicates that these species are unlikely to frequent the study site itself due to the limited size of the water body present. This suggests that the site does not provide suitable habitat for feeding or roosting for these avifaunal species, though its proximity to the Vermont Pan may contribute to broader ecological functioning.

Mammalian presence was confirmed by the detection of tracks and scat, with species such as Porcupine (*Hystrix africaeaustralis*), Vlei Rat (*Otomys unisulcatus*), Cape Grey Mongoose (*Herpestes pulverulentus*), and Water Mongoose (*Atilax paludinosus*) recorded. Additional species likely to traverse the site include Large Grey Mongoose (*Herpestes ichneumon*), Striped Fieldmouse (*Rhabdomys pumilio*), and Cape Genet (*Genetta tigrina*). Some of these species likely use the site transiently as a corridor between the site and Hoek van der Berg and the Salt Pan.


Although no threatened butterfly species have been recorded, the possibility of their occurrence cannot be definitively ruled out without a focused survey, as referenced by Mecenero et al. (2013). The dune snails (*Trigonephrus* spp., possibly *T. ambiguosus*) were also observed on site.

Impact Assessment

The specialist notes that the primary construction phase ecological impacts include the permanent loss of existing and natural and partly natural vegetation and faunal habitat within the development footprint. However, no plants species of conservation concern have been identified on site, and there is a moderate chance of at least one present (*Disa hallackii*; endangered). Though the specialist highlights that at least two Endangered bird species may occasionally utilise the site to forage (*Circus ranivorus* and *Circus maurus*).

The botanical specialist confirms that Alternative 4 (preferred) is a good compromise and has substantially lower ecological impact than the alternative assessed in the previous report (Alternative 3) (refer to the attached Botanical Impact Assessment Addendum, 2025). The proposed residential erven now exclude most of the High sensitivity areas (as required in my first bullet point of mitigation), and it is estimated that less than 500m² of high sensitivity habitat will now be lost. The private access road now does not need to cross the wetland, as there will now be two access roads instead of one (also a requirement in bullet point one of my mitigation sections). Some 58% of the total erf will now be conservation area (Private Open Space), up from an original 36%.

The ecological significance of the proposed development phase of the project has now been reduced from an unacceptable High negative (Alternative 2) to an acceptable Low Medium negative (Alternative 4).



2. Terrestrial Animal Site Sensitivity Verification Report and Compliance Statement (Faunal Assessment)

A significant portion of the disturbed areas are covered by alien invasive kikuyu grass (*Cenchrus clandestinus*). The southwestern edge of the property has been landscaped, and although alien invasive plants are present on site, they are found in low density (Helme 2023).



Photo 15: Fence line between study site and Hoek van der Berg Nature Reserve



Photo 16. Large portion of disturbed areas dominated by invasive kikuyu grass (*Cenchrus clandestinus*) (Venter, 2024).

During the site visit, the following animal species were observed through visual sightings, acoustic signals, tracks, and other signs.

Table 10: Animal species observed at Erf. 1486, Vermont during the site visit (Venter, 2024)

Group	Species	Notes	Status
Birds	Cape spurfowl, <i>Pternistis capenis</i>	In short grass next to fence, nature research	Least concern
	Yellow billed duck, <i>Anas undulata</i>	In wetland	Least concern
	Egyptian goose, <i>Alopchen aegyptiaca</i>	Flying	Least concern
	Hadedda ibis, <i>Bostrychia hagedash</i>	Flying	Least concern

		Cape turtle dove, <i>Streptopelia capicola</i>	Onsite	Least concern
		Cape weaver, <i>Ploceus capensis</i>	On site (birds & nests observed)	Least concern
Amphibians		Southern caco, <i>Cacosternum australis</i>	Calling on site	Least concern
		Clicking stream frog, <i>Strongylopus grayii</i>	Calling on site	Least concern
		Cape river frog, <i>Amietia fuscigula</i>	Observed	Least concern
Mammals		Four striped field mouse <i>Rhabdomys pumilio</i>	Observed	Least concern
		Bush vlei rat, <i>Otomys, unisulcatus</i>	Nests and latrine observed	Least concern
		Cape porcupine, <i>Hystrix africaeastralis</i>	Scat observed	Least concern
		Cape genet, <i>Genetta tigrina</i>	Scat observed	Least concern
		Cape dune mole-rat, <i>Bathergus suillus</i>	Fossorial activity	Least concern

The desktop study identified several other notable species that have might have occurred either on site or in the nearby area, as listed in **Table 11** below.

Table 11: Other notable animal species likely to occur at or near Erf. 1486, Vermont based on the desktop survey (Venter, 2024)

Group	Species	Notes	Status
Birds	Black Harrier, <i>Circus maurus</i>	iNaturalist, GBIF	Endangered

	African marsh harrier, <i>circus ranivorus</i>	iNaturalist, GBIF	Endangered
	Martial eagle, <i>Polemaetus bellicosus</i>	iNaturalist, GBIF	Endangered
	Cape dwarf chameleon, <i>Bradypodion pumilum</i>	iNaturalist, GBIF	Near threatened
Reptiles	Cape dwarf chameleon, Bradypodion pumilum	iNaturalist, GBIF immediate area	Near threatened

Animal Species of concern

The screening tool identified a total of eight animal species of concern. Additionally, one more species of conservation concern (SCC) was identified during the desktop study. The following section addresses the site's potential significance for these species and assesses the likelihood of their presence in the habitats within the development area.

Connectivity for animal species

The conservation planning map of the Western Cape Biodiversity Plan (Pool-Stanvliet et al. 2017) indicates the presence of a ESA2 (Ecological Support Area), linking the Hoek van die Berg Private Nature Reserve to the west with the Vermont Salt Pan to the east, and is part of the primary water source for that pan, see (Helme, 2023)




Figure 18: The conservation planning map of the Western Cape Biodiversity Plan (Pool-Stanvliet et al. 2017) indicates the presence of a ESA2 (Ecological Support Area)(yellow dotted arrows), linking the Hoek van die Berg Private Nature Reserve to the west with the Vermont Salt Pan to the east (Venter, 2024).

In accordance with the faunal specialist report by Venter (2024), the preservation of the ecological corridor is identified as critical for facilitating species movement between the nature reserve and the on-site wetland. The preferred development layout, Alternative 4, has been specifically designed to incorporate a more substantial undeveloped space between the permanent and seasonal / temporal zones of the wetland. This approach aligns with the input provided by botanical and aquatic specialists, aiming to support ecological movement and maintain hydrological connectivity within the wetland. However, Venter (2024) also noted that the development footprint encroaches upon the Ecological Support Area 2 (ESA2) corridor, with minor infringement by the residential erven and a more significant encroachment by the access road. This was also highlighted in the Freshwater specialist report. Despite these encroachments, which have been significantly reduced from the original design, the faunal connectivity assessment classifies the proposed development risk as 'medium' before mitigation and **Low - Medium** after mitigation.

It is important to note, as indicated in the Aquatic Biodiversity Assessment and Wetland Offset, Rehabilitation and Management Plan that the recommended mitigation measures will be fully implemented on site to ensure the continued functionality of the wetland area as well as their habitat will be restored into more functional state. A nighttime Search and Rescue is mandatory prior to vegetation clearance and commencement of construction. Sheraine van Wyk from Whale Coast Conservation Chameleon project must be contacted to facilitate the Search and Rescue for animal species, (sheraine.wcc@gmail.com 083 484 0202).

Based on input from the botanical, faunal and wetland specialist the development footprint has evolved to make provision for a 'private open space' facilitating a more functional corridor connection which runs from the Vermont Salt Pan across to Hoek van der Berg. The evaluation of its improved functionality (compared to earlier versions of the development plan) in terms of connectivity for animal species is summarized below (Venter, 2024).

Table 12. Impact Assessment comparison

Potential impacts and risk	Alternative 2	Preferred Alternative 4
Nature of impact	Cape dwarf chameleon, <i>Bradypodion pumilum</i> habitat loss and movement impediment	
Extent and duration of impact:	Local and long term	Local and long term
Consequence of impact or risk:	High	Low
Probability of occurrence:	High	High
Degree to which the impact may cause irreplaceable loss of resources:	High	Medium-Low
Degree to which the impact can be reversed:	Irreversible	Irreversible
Indirect impacts:	N/A	N/A
Cumulative impact prior to mitigation:	High	Low
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High	Low
Degree to which the impact can be avoided:	Low	Medium

Degree to which the impact can be managed:	Low	High	
Degree to which the impact can be mitigated:	Low	High	
Residual impacts:	High	Medium	
Cumulative impact post mitigation:	High	Medium	
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High	Low	Medium

Black harrier (*Circus maurus*)

The faunal specialist indicates that the Black Harrier (*Circus maurus*), a rare and endangered species endemic to southern Africa, may have lost more than 50% of its breeding habitat due to extensive land transformation caused by agriculture, invasive alien vegetation, and urbanization within the Fynbos biome (Curtis et al. 2004; Taylor 2015a). This species typically breeds in Fynbos, particularly in Strandveld and Mountain Fynbos, and in fragmented Renosterveld habitat, it is only found in high-quality, larger patches (Curtis et al. 2004). The Black Harrier's foraging habitat includes montane areas, lower-altitude Karoo scrub, semi-desert regions, floodplains, and croplands (Curtis et al. 2004), with small mammals and birds, especially quail, being its primary diet (Curtis et al. 2004).

Data from both GBIF and iNaturalist indicate sufficient records of this species in the general region of the property, suggesting a reasonable likelihood that the Black Harrier may be frequent in the area for foraging. Although the species was not observed during the field visit, the small footprint of the proposed development and the provision of 'private open space' provide adequate foraging habitat for the Black Harrier. Given that the species ranges widely, the minor loss of foraging habitat is unlikely to significantly affect it. Additionally, the development site does not significantly impact potential breeding sites or prey species. Therefore, the faunal specialist concludes that the proposed development is not likely to significantly impact the Black Harrier, and the potential impact is classified as '**low**'.

African marsh harrier (*Circus ranivorus*)

According to the faunal specialist findings, the African marsh harrier (*Circus ranivorus*) typically inhabits large water bodies and adjacent open vegetation (Simmons 2005). Classified as Endangered in South Africa (Taylor 2015b), this species faces significant threats from habitat loss and degradation. Records from both GBIF and iNaturalist indicate the presence of this species near and within the general region of the property, suggesting a reasonable likelihood of the species foraging on the property. Although the species was not observed during the field visit, the small footprint of the proposed development and the provision of 'private open space' offer sufficient foraging habitat for marsh harriers. Given the species' wide range and the minor extent of habitat loss, the development is unlikely to have a significant impact on the African marsh harrier. Additionally, the development does not significantly affect potential breeding sites or prey species. Consequently, the potential impact on the African marsh harrier is considered '**low**'.

Martial Eagle (*Polemaetus bellicosus*)

The Martial Eagle is native to sub-Saharan Africa and is considered an African endemic species that is currently declining, having recently been classified as globally Vulnerable due to a lack of detailed population trend data (Amar and Cloete 2018). In South Africa, the species is listed as 'Endangered' (Taylor 2015d). Martial Eagles typically occupy various habitats as long as there are tall trees or pylons available for nesting and perching (Machange et al. 2005). Although there are a few iNaturalist and GBIF records of the species in the general area, it was not observed during the field visit. The site does not provide suitable habitat for the Martial Eagle's preferred prey species, and the minor loss of marginal forage habitat is unlikely to significantly affect the species. Additionally, the development site does not impact potential

breeding sites or prey species. Therefore, the proposed development is expected to have a '**low**' impact on the Martial Eagle.

Denham's Bustard (*Neotis denhami*)

Denham's Bustard inhabits natural vegetation such as fynbos and grasslands, as well as pastures and agricultural fields (Allan 2005). Classified as 'Vulnerable' (Taylor 2015c), the species faces threats from powerline collisions, habitat conversion to monoculture fields, and overgrazing (Shaw et al. 2010). iNaturalist and GBIF records show several occurrences east of the property, predominantly in the more open agricultural fields of the Overberg. The species was not observed during the field visit, and the habitat on the development site is unsuitable for it. Consequently, the impact of the proposed development on Denham's Bustard is considered '**low**'.

Hottentot Buttonquail (*Turnix hottentottus*)

The Hottentot Buttonquail is an endangered species endemic to the Fynbos biome (Lee et al. 2018). Major threats to this species include inappropriate burning frequencies and rapid urban and agricultural expansion in lowland areas (Peacock 2015). It prefers sparse, drier vegetation and avoids older or dense vegetation (Lee et al. 2018). Although there are iNaturalist and GBIF records in the vicinity, they do not match the habitat types of the development site. The species was not observed during the field visit, and the dense wetland vegetation at the site is unsuitable for its needs. Therefore, the likelihood of the Hottentot Buttonquail occurring at the site is low, and the impact of the proposed development on the species is expected to be '**low**'.

Striped Flufftail (*Sarothrura affinis*)

The South African population of Striped Flufftail is suspected to be declining due to habitat loss (Peacock et al. 2015). Over 10% of the regional population may have been lost because suitable grassland habitats are threatened by inappropriate burning practices, heavy grazing, agriculture, and afforestation (Peacock et al. 2015). In the Western Cape, this species is typically found in dense Psoralea-Osmopsis Fynbos near streams or moist depressions (Graham and Ryan 1984, Kakebeeke 1993). Records on iNaturalist and GBIF show sightings mostly around Kleinmond and Grabouw, about 20 km away, with one GBIF record closer to the property, within 15 km, on the mountain slopes near the Klein River to the east. Despite attempts to attract the species with playbacks, none were detected at the development site, possibly due to high winds affecting the call-ups. While the habitat at the site is not considered highly suitable for this species, its presence cannot be ruled out entirely. If present, some habitat loss is likely, and disturbance during construction may temporarily drive them away, though the adjacent nature reserve and wetland system could offer refuge. The potential impact on the Striped Flufftail is deemed '**low**'.

Southern Adder (*Bitis armata*)

The Southern Adder is classified as 'Vulnerable' due to its fragmented distribution and reduced habitat quality (Maritz and Turner 2023). It has a small range along the southwest coastal margin of the Western Cape with three disjunct populations: one from West Coast National Park to just north of Cape Town, another near Hermanus, and the third near De Hoop Nature Reserve (Maritz and Turner 2023). This species inhabits coastal lowland Fynbos on sandy and rocky substrates (Phelps 2010) and is known to shelter under rocks between dense shrubs (Phelps 2010). Records on iNaturalist and GBIF are concentrated between Stanford and Struisbaai, 20 km to the east of the property. The species was not observed during our visit, and the dense wetland vegetation at the development site is unsuitable for it. Thus, the likelihood of its presence is considered low, and the impact of the development is likely to be '**low**'.

Cape Dwarf Chameleon (*Bradypodion pumilum*)

Although not listed as a species of conservation concern in the screening report, the Cape Dwarf Chameleon is included here due to its confirmed presence near the development site. It is classified as 'Near Threatened' due to habitat loss and decline in quality and extent (Tolley 2023). The species is found from southwestern Cape Town to the Agulhas Plain (Tolley and Burger 2004) and inhabits various vegetation types, including Fynbos, forested riparian zones, and some exotic and indigenous trees. It can also adapt to peri-urban gardens and greenbelts (Tolley 2023). Several iNaturalist and GBIF records indicate its presence directly adjacent to, and likely within, the development site. Although not observed during our field visit, the habitat is deemed highly suitable for this species. Habitat loss and construction disturbance are likely to have a negative impact, though the adjacent nature reserve and wetland system provide some refuge. A search and rescue operation before construction could be considered. With regard to Cape dwarf chameleon habitat, the provision of an open space in Alternative 4 (preferred) represents a notable improvement compared to earlier alternatives. This adjustment enhances habitat functionality, resulting in the overall impact being reduced to **low to medium** significance.

Yellow-winged Agile Grasshopper (*Aneuryphymus montanus*)

This endemic grasshopper species is found in the mountains of the Western and Eastern Cape and is listed as 'Vulnerable'. It has been recorded from near Clanwilliam extending eastward to East London, typically in various fynbos types on south-facing, cool slopes (Brown 1960). Brown (1960) notes that the species was collected "amongst partly burnt stands of evergreen sclerophyll in rocky foothills." Documented sites include Graafwater, near Lambert's Bay, De Rust, Suurbraak, Bot River, Kogelberg, and Joubertinia. The species appears to prefer rocky, mountainous areas, with an estimated extent of occurrence of about 170,000 square kilometers. No specimens were observed during the field visit. The proposed development is considered to have a 'low' impact on *A. montanus* due to the lack of species data from this area, absence of suitable habitat, no direct evidence of occurrence, the small scale of the development relative to the surrounding vegetation, and the species' broad regional distribution.

4.4.	Explain how the objectives and management guidelines of the Biodiversity Spatial Plan have been used and how has this influenced your proposed development.
------	---

The objectives and management guidelines of the WCBSP are intended to guide planning and decision-making in terrestrial and Freshwater CBAs and ESAs on land outside the protected area:

These guidelines direct the EAPs or specialist to promote the effective management of the biodiversity. The Western Cape Biodiversity Spatial Plan Identifies the development site within Ecological Support Area, which serves as a critical corridor linking the Hoek van der Berg Private Nature Reserve to the Vermont Salt Pan. This corridor supports hydrological connectivity and faunal movement. The preferred development layout (Alternative 4) was designed to minimize infringement on the ESA2 corridor, incorporating a substantial "private open space" to maintain ecological connectivity and support wetland functionality, this is considered desirable by the faunal specialist. It is important to highlight that this portion of the site constituting of the wetland area will be protected through a conservation servitude. The adjustment of the preferred layout (Alternative 4) from the previously preferred alternative (Alternative 3) significantly reduces the ecological footprint compared to earlier alternatives, lowering the overall impact from high to low to medium negative, as assessed by faunal and botanical specialists. The development in its current scenarios offers an opportunity for long term conservation and rehabilitation of this link and reduces risk of future development which may have long term negative impacts on the system.

4.5.	Explain what impact the proposed development will have on the site-specific features and/or function of the Biodiversity Spatial Plan category and how has this influenced the proposed development.
------	--

The proposed development is anticipated to have several site-specific ecological features which are indicated to be lower than the previous alternatives. The areas anticipated to be impacted includes, Critically Endangered Hangklip Sand Fynbos vegetation (500m²), a portion of the seasonal wetland area through road construction, and forage habitat for some animal species (Cape dwarf Chameleon, *Bradypodion pumilum*). These impacts have been carefully evaluated in accordance with the Biodiversity Spatial Plan, particularly concerning the Ecological Support Area (ESA2) corridor, as outlined by Venter (2024). The development footprint, whilst reduced in the preferred layout (Alternative 4), still results in a slight infringement on the ESA2 corridor, however, through layout refinements and the avoidance of most of the delineated wetland area, the project has sought to balance ecological preservation with development needs, reducing impacts to an acceptable level as far as practical and fulfilling the mandate of infill development within built up urban areas.

Vegetation Loss and Ecological Function

The site is characterized by Hangklip Sand Fynbos, a vegetation type gazetted as Critically Endangered. According to the Terrestrial Assessment (Helme, 2023), the on-site vegetation has not been subjected to fire for over 20 years, resulting in its senescence and the decline of certain species. Optimal ecological functioning of Fynbos requires burning every 10-15 years, a condition not met on this site due to its location within the built-up urban landscape. Approximately 50% of the site comprises permanent wetland areas supporting a higher prevalence of indigenous vegetation, while non-wetland areas retain only some native species. No plant species of conservation concern were recorded on-site, though *Disa hallackii* (Redlisted as Endangered) is known from a nearby erf and is most detectable post-fire (Helme, 2023). The absence of recent burns likely reduces the probability of its presence.

The development will result in the permanent loss of all natural and semi-natural vegetation and faunal habitat within the development footprint, including approximately 500 m² of high-sensitivity habitat. Through design revisions, the impact has been reduced from a high negative (Alternative 2) to a low to medium negative (Alternative 4), rendering it acceptable within the context of the project's constraints.

Ecological Connectivity for Faunal Species

The site supports an ecological corridor important for the movement of ground-dwelling species between adjacent nature reserves and wetlands (Venter, 2024). The inclusion of designated "private open space" in the current layout (Alternative 4) enhances connectivity and is considered essential for maintaining faunal movement. While the development footprint still encroaches slightly on the ESA2 corridor primarily through the residential erven and access roads, these infringements are significantly reduced compared to the initial layout (Alternative 2). Consequently, the risk to faunal connectivity is assessed as medium.

The Site Development Plan has evolved in response to comments received from specialists, organs of state and I&AP's to allow for a more functional corridor within the area zoned for open space (Seasonal and Temporary wetland). The Alternative 4 layout incorporates an improved functionality compared to earlier alternatives (Alternative 1 and Alternative 2) in terms of Cape Dwarf chameleon habitat. Therefore, the significance rating of the impact of development on Cape Dwarf Chameleon habitat loss and movement impediment is low to medium after the mitigation measures have been applied.

Hydrological Connectivity and Wetland Impacts

The proposed eastern and southern boundary access roads overlap with a small portion of the Unchanneled Valley Bottom (UVB) wetland, leading to the loss of approximately 0.024 ha (3%) of the 0.90-ha wetland. Given the site's spatial constraints and the central location of the wetland, complete avoidance of wetland encroachment is not feasible, as noted in the Aquatic Biodiversity Impact Assessment (van Zyl et al., 2025). Efforts to further reduce the development

footprint were deemed inviable, and no additional mitigation measures could eliminate wetland loss entirely. However, the application of the mitigation hierarchy has minimized impacts to the greatest extent practicable, ensuring that wetland loss is kept to an unavoidable minimum through implementation of Wetland Offset Rehabilitation and Management Plan.

Moreover, an existing pipeline to be upgraded is located along Kolgans Close and Malmok Road. The wetland area along the stretch of this road where the pipeline is to be upgraded, is critically degraded, i.e. relic or historical, due to infill from the road. Other notable impacts to the general UVBW in this vicinity include artificial channels, roads, residential dwellings, excavation, and culverts, which have altered natural flow regime, vegetation, water quality and geomorphology.

The vegetation within the functional UVB wetland downslope / adjacent to the road, consists of wetland obligate species *Juncus krausii*, *Cyperus textilis*, with wetland facultative *Senecio halimifolius* and *Zantedeschia Aethiopica* along the outer boundary of the functional wetland area.

Soils that were sampled in the UVB wetland did not differ markedly from terrestrial soils, aside from appearing darker and with a higher organic content than the terrestrial baseline.

Given that the Erf, and the proposed pipeline to be upgraded, are located more than 387 m away from the Vermont Salt Pan, no impacts to this wetland as a result of the project is expected. Therefore, the only watercourse deemed to be "At Risk" is the UVBW on Erf 1486.

4.6.	If your proposed development is located in a protected area, explain how the proposed development is in line with the protected area management plan.
------	---

Not applicable. The development is not within a protected area.

4.7.	Explain how the presence of fauna on and adjacent to the proposed development has influenced your proposed development.
------	---

A Faunal Specialist was appointed to assess the site and development proposal.

The species observed on-site, such as the Cape spurfowl, Southern caco, and Cape porcupine, among others, are predominantly classified as "Least Concern." However, their presence, particularly in and around the wetland area, emphasized the need to preserve critical habitats on site and maintain ecological connectivity along the entire wetland length from the Vermont Salt Pan and across to the Hoek van der Berg Nature Reserve. The wetland area, which supports several of these species, has been incorporated into the design as a private open space, ensuring that their habitat remain largely undisturbed.

Connectivity and Ecological Corridors

The conservation planning map from the Western Cape Biodiversity Spatial Plan (2017) identifies an Ecological Support Area 2 (ESA2) corridor on the site. This corridor is crucial for facilitating species movement between the Hoek van de Berg Private Nature Reserve, the site and the Vermont Salt Pan. The development layout, particularly Alternative 4, was adjusted to include a larger open space between the permanent and seasonal/temporal zones of the wetland, thereby supporting both faunal movement and hydrological connectivity. While there is very little encroachment into the seasonal/temporal wetland area by the access road and few residential erven, this has been minimized compared to other alternative designs. Of importance to note, the private open space, including the permanent and seasonal wetland area will be preserved via a conservation servitude so that it maintains and improve its functional status, these efforts will also be done through an implementation of a Wetland Offset, Rehabilitation and Management Plan compiled by Delta Ecology to ensure its recovery during post-construction phase. This will ensure that, aside from the access road

encroachment already accounted for in the wetland offset, portions of the erven that are still encroaching on the seasonal wetland area will be designated as no-go areas where no development will be permitted.

Species of Conservation Concern

The desktop study identified several species of conservation concern, including the Black Harrier, African Marsh Harrier, and Martial Eagle. None of these species observed during the site visit, their potential presence has been considered and were classified as low. The development plan has been adjusted to minimize the loss of foraging habitats and avoid impacts on potential breeding sites. For example, the provision of private open space within the development is intended to offer adequate foraging habitat for species like the Black Harrier (*Circus maurus*; Endangered) and African Marsh Harrier (*Circus ranivorus*; Endangered), reducing the overall impact on these species. Nighttime Search and Rescue is mandatory a few days ahead of construction commencement. Sheraine van Wyk from Whale Coast Conservation must be contacted to facilitate the Search and Rescue (sheraine.wcc@gmail.com 0834840202).

Mitigation Measures and Impact Assessment

The potential impacts of the development have been assessed through a systematic evaluation of the development footprint. Alternative 4, which represents the preferred layout, demonstrates a lower impact on faunal connectivity and ecological corridors compared to earlier alternatives.

To further reduce the impact on fauna, the following mitigation measures are recommended by faunal specialist:

- a) During the construction phase the construction area should be clearly demarcated and blocked off from the 'private open space' area to avoid damage and pollution.
- b) Pre and post construction site preparation should include rehabilitation of the 'private open space' by removing current building rubble and litter from this area.
- c) Long term maintenance of ecological integrity of the 'private open space' is critical. Therefore, measures should be put in place for constant removal of alien vegetation, cleanup of litter and prevention of illegal dumping. Clear legal responsibility for the maintenance of the space should be entrenched to be the responsibility of the homeowners association.
- d) The fence traversing the ecological corridor should always be permeable to allow for movement of small sized animals e.g. small antelope, genets, mongoose between the nature reserve and wetland system.
- e) Search and Rescue of chameleons and other slow-moving animals is feasible due to the presence of the adjacent nature reserve where they can be released. A search and rescue effort must be implemented before and during construction where animals that are found are released in the adjacent nature reserve or other suitable sites. The necessary permission and permits should be obtained before this is done.
- f) Pets (especially domestic cats) must not be allowed to free-roam the 'private open space'.

5. Geographical Aspects

Explain whether any geographical aspects will be affected and how has this influenced the proposed activity or development.
Erf 1486 is geographically significant as one of the last remaining large vacant properties within the built-up suburb of Vermont, making it a key site for potential infill residential development. The property is characterized by natural features such as indigenous vegetation, gentle topography, and proximity to ecological corridors and wetland systems. These geographical features have played a central role in informing the planning and design of the proposed development. The most notable geographical change will be the conversion of a portion of the natural landscape within the defined development footprint into a built environment. This transformation introduces a permanent alteration to the site's current state. However, in recognition of the site's ecological and hydrological sensitivity, the development has been carefully designed to minimize ecological impact and reduce the development footprint as far as practical. Specifically, the selection of the preferred layout alternative (Alternative 4) was influenced by the need to retain ecological connectivity and avoid the mapped wetland areas. This layout strategically limits the development footprint to already disturbed or less environmentally sensitive areas, thereby preserving important open space and maintaining hydrological connectivity. These measures are intended to ensure that the development coexists with the surrounding natural landscape and continues to support ecosystem functioning within the broader area.

6. Heritage Resources

6.1.	Was a specialist study conducted? A Notice of Intent to develop was submitted to Heritage Western Cape. HWC has confirmed that no further Heritage Assessment is required. See Appendix F5 .	YES	NO X
6.2.	Provide the name and/or company who conducted the specialist study.		
N/A			
6.3.	Explain how areas that contain sensitive heritage resources have influenced the proposed development.		
N/A			

7. Historical and Cultural Aspects

Explain whether there are any culturally or historically significant elements as defined in Section 2 of the NHRA that will be affected and how has this influenced the proposed development.
N/A

8. Socio/Economic Aspects

8.1.	Describe the existing social and economic characteristics of the community in the vicinity of the proposed site.
------	--

The project site falls within the jurisdiction of the Overstrand Municipality and the Overberg District Municipality (ODM). The visual metrics of the ODM's socioeconomic profile (2023) are presented below:

Overstrand Municipality is located along the south-western coastline of the Overberg District Municipal area bordering the City of Cape Town in the west and Cape Agulhas Municipality in the east. Its northern neighbour is Theewaterskloof Municipality. Overstrand is a dynamic unity combining great potential and a beautiful setting. The aim is to bring about growth and development to the benefit of all their people, in their different communities, whilst maintaining a balance with nature. The Municipality covers a land area of approximately 1708 km², with a projected population of 110 971 people (Western Cape Provincial Treasury, SEP 2022) and covers the areas of Hangklip Kleinmond, Greater Hermanus, Stanford and Greater Gansbaai.

In addition to the endless, pristine beaches dotting the coastline, the Overstrand boasts 5 Blue Flag beaches. Tourism is a major economic driver in the area and its popularity as a holiday destination results in a fourfold increase of its population over the holiday seasons. This influx places a great strain on the existing municipal services and roads infrastructure.

The Overstrand municipality's population increased by 56 721 people over a period of 20 years from 1996 to 2016. Overstrand's population has increased steadily from 80 432 in 2011 to 93 407 in 2016. Between 2011 and 2016 the population growth in Overstrand was 16.1 per cent. The projected population growth for the period 2022-2026 are cited on the Municipal IDP 2023/24. The population increase for the municipality is expected to increase from 110 971 to 124 826 in 2026, making it the most populated municipal area in the Overberg District.

According to the Overstrand IDP 2023/2024, the Overstrand has a growing population that will increase the demand for housing, employment, service delivery and related infrastructure developments. The increased population growth will therefore place increased pressure on the municipal resources to develop new as well as maintain existing infrastructure. The ability to work from home has enabled households to move away from the economic hubs and settle in smaller towns such as Hermanus. This trend can be a valuable injection for the local economy as well as the municipality in terms of income generation, despite the increased demand for services (Source: Western Cape Provincial Treasury, MERO 2021and SEP 2021).

Overstrand's projected forecast is 0.1 per cent economic growth, which is lower than both the District and Western Cape projection over the same period. In 2020, a total of 33 096 workers were employed in the Overstrand municipal area, contributing 27.4 per cent to Overberg District employment during the year. Between 2016 and 2020, the Overstrand municipal area experienced an average annual decline of 520 jobs. Estimates for 2021 indicate a further deterioration in Overstrand's employment, with a total of 1 475 jobs lost. Overall, the deterioration of the Overberg's labour market conditions in 2020 was due to the COVID-19 pandemic and the implantation of lockdown restrictions to contain its spread. Furthermore, restrictions in domestic and international travel greatly impacted activity in sectors related to tourism (Western Cape Provincial Treasury, MERO, 2022). Furthermore, load shedding in 2022 and 2023 are expected to further deteriorate employment prospects in the Overstrand municipal area. The estimated decline in employment opportunities is likely to result in a decline in household income, which in turn will continue to restrain municipal revenue and increase the demand for free basic services.

Overall, all development and growth in Overstrand must be sensitive to the area's most important asset, that being the natural environment. Sustainable development in Overstrand will be guided by the Municipal Spatial Development Framework (SDF) and related sector plans. The SDF identified Kleinmond, Hawston, Hermanus, Stanford and Gansbaai with its suburbs as areas prioritized for further development. This is due to bulk services being available to support densification and developments.

The proposed site is situated in the Overberg Municipal area, specifically in Vermont, which falls under the urban jurisdiction of Hermanus. The existing social and economic characteristics of the community in the vicinity of the proposed site are influenced by several factors:

- Job creation is identified as a critical need in the area, especially for the unskilled labour living in the township. The proposed development is expected to contribute significantly to economic growth by generating employment opportunities. This, in turn, can lead to increased investments in the area, fostering economic prosperity.
- The area has an active real estate and rental market, which is driven by ongoing in-migration to Hermanus. The development of new residential erven aligns with the increasing demand for housing and is anticipated to stimulate local property markets.
- The proposed development is seen as an opportunity for attracting investments. The creation of residential properties may attract investors interested in the real estate market, further stimulating economic activities in the area.

8.2. Explain the socio-economic value/contribution of the proposed development.

The proposed development holds several socio-economic values and contributions to the community and the broader area:

- One of the significant contributions is the creation of employment opportunities, both directly and indirectly. The proposed development will have both short- and long-term economic impacts on the Overstrand Municipality and the surrounding area. It will create employment opportunities during the construction phase, generate additional rates and taxes, all of which will contribute positively to the local economy. The development has the potential to generate revenue for the local municipality through property taxes and other associated fees. This additional revenue can be reinvested in community services and infrastructure.
- By attracting investments and stimulating economic activities, the development contributes to the overall economic growth of the area. Increased economic activities will lead to the growth of local businesses and services, benefiting the community.
- The creation of residential erven adds value to the real estate market in the area. The sale of properties to new residents contributes to the local property market, potentially increasing property values and attracting further investments.
- Additionally, the combined development is expected to accommodate at least 27 new residents to the Hermanus area, based on a calculation ratio of 3 people per dwelling unit. These new residents will contribute to the local economy by spending money on various items such as food, petrol, restaurants, repairs, and other goods and services, thereby boosting the local economy. The development may lead to improvements in local infrastructure. Increased housing demand could necessitate enhancements to utilities, roads, and other essential services, benefiting both existing and new residents

8.3. Explain what social initiatives will be implemented by applicant to address the needs of the community and to uplift the area.

The development will result in a sizable contribution towards job creation during both the construction and operational phase and allow for potential skills development for local laborers and artisans residing in the area.

8.4. Explain whether the proposed development will impact on people's health and well-being (e.g. in terms of noise, odours, visual character and sense of place etc) and how has this influenced the proposed development.

The proposed residential development on Erf 1486, Vermont, is not expected to result in any significant negative impacts on human health and well-being. However, several considerations have been noted, and appropriate mitigation

measures have been incorporated into the Environmental Management Programme (EMPr) to address potential temporary and long-term effects:

- Construction-related activities and the temporary increase in human presence may result in elevated noise levels, potentially affecting nearby residents. Although this impact is considered minor, the EMPr includes specific measures to mitigate construction noise, including adherence to permissible working hours as per municipal bylaws and the implementation of best-practice noise control measures.
- Temporary impacts on air quality due to dust and emissions from construction materials may occur during the development phase. While these impacts are not expected to pose a health risk, the EMPr outlines specifications for dust suppression, proper storage of materials, and regular site maintenance to mitigate nuisance conditions and uphold neighbourhood quality of life.
- The transformation of a portion of the site from natural vegetation to built residential infrastructure may result in a degree of change to the visual character and sense of place, particularly for residents who value the natural setting. To reduce visual intrusion, the development will incorporate design principles that are sensitive to the surrounding context, ensuring architectural harmony and maintaining the aesthetic quality of the area. Landscaping measures and the use of materials compatible with the local character will be prioritised.
- While the development may lead to an influx of new residents and changes to the existing neighbourhood structure, it is not anticipated to disrupt social cohesion significantly. The proposed layout is consistent with surrounding residential land uses and will integrate open space areas to promote a sense of community. Furthermore, the development supports the strategic growth vision of the municipality by aligning with planned urban expansion within demarcated urban edges.

SECTION H: ALTERNATIVES, METHODOLOGY AND ASSESSMENT OF ALTERNATIVES

1. Details of the alternatives identified and considered

1.1.	Property and site alternatives to avoid negative impacts, mitigate unavoidable negative impacts and maximise positive impacts.
Provide a description of the preferred property and site alternative.	
No site alternatives exist. From a planning perspective, the erf is located within the built-up urban edge of the suburb of Vermont and the proposed development is in line with existing development in the area. Through the assessment process and the application of the mitigation hierarchy, a balance between residential development and environmental conservation is achieved. The proposed development is in line with the surrounding residential offerings and forms the logical infill opportunity within the built-up suburb of Vermont. The design sees the avoidance of key biophysical features on site, minimizes negative impacts, mitigates unavoidable effects, and maximizes positive outcomes, particularly in preserving ecological connectivity and biodiversity. Site context and characteristics Erf 1486, located at the corner of the R43 and Lynx Road, approximately 9 km west of central Hermanus in the Western Cape, spans 15 069 m². As one of the last large erven in Vermont suitable for single residential development, it presents a unique opportunity to meet residential demands within an urban context while addressing environmental constraints. The site is bordered by the Hoek van der Berg Private Nature Reserve to the west and a wetland system to the southeast, which connects to the Vermont Salt Pan, the site occurs within the built-up residential suburb of Vermont, and abuts the	

R43 main road to the north. The site contains Critically Endangered Hangklip Sand Fynbos vegetation and an unchanneled valley-bottom wetland, both of which are ecologically sensitive. Its designation as part of an Ecological Support Area (ESA2) corridor as per the BSP (2017) underscores its importance for faunal movement between the Hoek van der Berg nature reserve and the Vermont Salt Pan. The selection of Erf 1486 as the sole property alternative is driven by its size, location within the urban edge of Vermont, and the potential to integrate residential development with ecological preservation through careful planning.

Preferred Site Alternative: Alternative 4

Alternative 4 has been developed through iterative design processes informed by specialist inputs (e.g. botanical, aquatic, and faunal assessments) as well as comments received during public participation, is the preferred layout design for Erf 1486. This preferred alternative optimizes the balance between residential development and environmental conservation. It avoids development within ecologically sensitive areas, notably the permanent and seasonal wetland areas. The unavoidable remaining encroachment into the wetland area is accounted for in the Wetland Offset Calculation.

The key components of Alternative 4 are outlined below:

Residential Use

- Approximately 4253 m² is designated for residential development.
- 6 x Single residential erven of varying sizes are included. Home Owners Association constitution but also the Conservation Servitude to be allocated as per the onsite Wetland Offset.

Access road

- A footprint of approximately 1456 m² is allocated for private access roads.



Open Space

- The remaining portion of the site (approximately 9,361 m²), which incorporates the entirety of the permanent wetland and the majority of the seasonal wetland, is allocated as private open space.
- The formal protection of the open space (wetland) will be secured through the appointment of a Homeowners' Association (HOA) representative, who will be responsible for overseeing the long-term management and maintenance of the area.
- In addition, all development restrictions and conservation requirements applicable to the open space must be clearly stipulated in the sale agreements and the Homeowners' Association Constitution, ensuring that prospective purchasers are fully informed of the nature of the open space, the associated servitudes, and their obligations regarding its protection and management.

Associated service infrastructure

Electricity Supply

Electrical services will be supplied via a connection to the municipal electricity network. The installation will be done in line with the requirements and specifications of the Overstrand Municipality.

Water Supply

Potable water will be sourced from the Preekstoel Water Treatment Plant, via a 200 mm diameter pipeline located along Lynx Avenue. A new connection point will be established, and internal reticulation infrastructure will be constructed in accordance with municipal engineering standards. The Overstrand Municipality has confirmed sufficient capacity to accommodate the additional demand from the development.

Sewer and Effluent Management

The proposed development will be connected to the existing municipal sewer system with the minor upgrade of the North south section in Kolgans and Malmok roads required (110 mm pipeline to 160 mm pipeline). The revision of the final preferred layout, sees the sewer lines being located outside the delineated wetland area, thereby significantly reduces the risks associated with the proposed development.

Stormwater Management

Given the site's proximity to a delineated wetland, a comprehensive Stormwater Management Plan has been developed to manage surface runoff effectively and mitigate impacts on the downstream wetland system. The site forms part of a larger hydrological catchment where runoff from Catchment Area 1 (CA1), located north of the R43, drains into Catchment Area 2 (CA2), which includes the development site and wetland.

Key Stormwater Control Measures Include:

- Installation of 2 culvert pipes to manage upstream flow.

Runoff from R43 enters through the existing culverts which will be connected into the proposed 2 pipes that will facilitate stormwater runoff into the enhanced vegetated swale positioned north of the wetland (outside the wetland edge). This swale will facilitate the controlled flow of stormwater from the two culverts, channelling it through the enhanced swale system and along the stormwater drainage network integrated with the private roads. The design will slow down flows, promote infiltration, and improve water quality before reaching the wetland.

To further control water entering the wetland post-development, a permeable paving system has been incorporated along the private road south of the wetland (outside the wetland edge). This system will allow stormwater to infiltrate into the subsurface, thereby reducing direct runoff and attenuating flows before they discharge toward the wetland environment.

To manage stormwater in the proposed development Low Impact Development (LID) measures will be implemented:

Permeable Paving System (South of Wetland)

Designed to reduce surface runoff and promote infiltration:

- Surface Storage Depth: 50 mm
- Pavement Thickness: 80 mm
- Base Course Height: 400 mm (43% void ratio)
- Permeability (clogged): 360 mm/hr
- Outlet: 160 mm uPVC pipe
- Storage Volume: 140 m³

Enhanced Swale System (North of Wetland)	
A vegetated swale to filter pollutants and slow runoff:	
→ Surface Storage Depth: 400 mm → Swale Storage Depth: 750 mm → Surface Slope: 0.5% → Void Ratio: 0.43 → Vegetative Cover: 75% → Conductivity: 120 mm/hr → Storage Volume: 81 m³	
Provide a description of any other property and site alternatives investigated.	
N/A	
Provide a motivation for the preferred property and site alternative including the outcome of the site selection matrix.	
No property alternatives exist. The property in question forms one of the last vacant erven within the suburb of Vermont and contributes to infill development within the built-up suburb of Vermont. The Overstrand Municipality Spatial Development Framework (2020) projects a population growth of approximately 155 272 for the greater Hermanus area. This anticipated growth highlights the increasing demand for residential development. The proposal is in line with the prevailing development trend in Vermont, which involves utilizing available vacant properties.	
Provide a full description of the process followed to reach the preferred alternative within the site.	
N/A	
Provide a detailed motivation if no property and site alternatives were considered.	
Refer to the above	
List the positive and negative impacts that the property and site alternatives will have on the environment.	
Positive → The proposed development contributes to addressing housing needs, providing residences for single families. → Job creation and economic growth are anticipated during the construction phase, fostering local economic development. Negative → Loss of ecological connectivity → Construction activities may contribute to soil erosion, especially in areas where vegetation is removed, necessitating erosion control measures. → During the construction phase, noise and dust generation may occur, impacting the immediate environment.	
1.2.	Activity alternatives to avoid negative impacts, mitigate unavoidable negative impacts and maximise positive impacts.
Provide a description of the preferred activity alternative.	

N/A	
Provide a description of any other activity alternatives investigated.	
N/A	
Provide a motivation for the preferred activity alternative.	
N/A	
Provide a detailed motivation if no activity alternatives exist.	
N/A	
List the positive and negative impacts that the activity alternatives will have on the environment.	
N/A	
1.3.	Design or layout alternatives to avoid negative impacts, mitigate unavoidable negative impacts and maximise positive impacts
Provide a description of the preferred design or layout alternative.	
ALTERNATIVE 4 (FINAL PREFERRED) This alternative option involves the establishment of 6 residential erven, internal road, and an open space erf. This selection emerged after a series of iterations which considered ecological constraints, particularly sensitive aquatic and terrestrial biodiversity onsite. Adjustments to the layout were made to avoid large areas of the delineated wetland on site. These changes, informed by input from the aquatic biodiversity specialist, led to the adoption of Alternative 4, which significantly minimizes ecological impact compared to previous preferred alternatives evaluated. The new residential erven will strategically be positioned to avoid all of the permanent wetland with only intrusion into the seasonal wetland (0.024 ha) being for a small section of the internal access road. The Wetland offset was applied for this unavoidable loss. It is important to note that the permanent wetland area on site is currently in a modified state, largely due to the presence of foreign fill material and the presence of alien invasive vegetation. The final preferred alternative layout (Alternative 4) includes two access roads instead of one which was proposed on the initial former layout (Alternative 2), eliminating the need for the private road to traverse the permanent wetland area. Approximately 9361 m² of the total area will be designated as conservation space (Private Open Space), a notable increase from the previous alternatives. This shift in design reduces the ecological significance of the development phase from an initially deemed "unacceptable High negative" in Alternative 2 to an "acceptable Low to Medium negative" in Alternative 4. Furthermore, Alternative 4 directly addresses concerns raised during the Public Participation Process, including the realignment of the sewer pipeline to avoid the wetland area, in line with CapeNature's recommendation. The sewer pipeline has now been realigned to run parallel to the water pipeline route, thereby completely avoiding the wetland area (refer to Appendix F6a and F6b). In addition, the stormwater swale infrastructure has also been shifted to fall outside of the delineated wetland boundary. This revision represents a major improvement compared to the previous alternatives and is in line with CapeNature's recommendation to prevent unnecessary impacts on the wetland system.	




Figure 19: Preferred Layout – Alternative 4

Provide a description of any other design or layout alternatives investigated.

ALTERNATIVE 1

Initially, Alternative 1 involved the development of 12 residential erven and 1 road erf, on the subject property. The layout included erven that directly encroach upon the mapped wetland and other highly ecologically sensitive areas onsite. Unlike other alternatives, there is no provision for open space to facilitate ecological corridors. The erven proposed under this layout are larger but extend into the wetland areas and the proposal results in disturbance and loss of wetland area and natural vegetation. No consideration of the natural environment is included in this layout, which is based on financial feasibility and gains only.




Figure 20: Alternative 1 Layout

ALTERNATIVE 2:

This layout was presented in PPP1, as the initial preferred layout. It was guided by the wetland delineation and reduced number of erven. 17 erven are proposed under this layout alternative and includes open space. However, this layout, although improved from Alternative 1, and avoiding the majority of the permanent wetland, still encroached into the seasonal and temporary wetland area.




Figure 21-1: Alternative 2 Layout

The first round of Public Participation was undertaken on Alternative 1 and 2 above, as well as the no Development option (No Go). In response to comments received during the first round of public participation, further revisions were made on the layout which then evolved in response to comments received during PPP1, as follows:

- The Terrestrial Biodiversity specialist proposed that the following erven should be removed from the layout: 1, 2, 7, 8, 10, 11, 12 and 13.
- The proposed access road (erf 14) should also be largely removed so that it does not cross the wetland and ecological corridor and can instead access erf 9 along the southern boundary.
- It was further recommended by the specialist team that with the reduction of the number of erven, and the realignment of the internal roads, all wetland areas including permanent and temporary, must be marked as no development areas.

ALTERNATIVE 3 (previously preferred)

Alternative 3 proposed 9 residential erven, two road erven, and one open space erf. This layout evolved through multiple revisions of the site development plan in response to specialist input and stakeholder comments, particularly regarding aquatic and terrestrial biodiversity sensitivity.

The design reduced development pressure on the wetland system and significantly minimised ecological impacts compared to Alternatives 1 and 2. However, concerns were still raised by Cape Nature regarding:

- Encroachment of portions of residential erven into the seasonal wetland, and
- The practicality of long-term protection and management of sensitive areas, particularly where reliance was placed on title deed restrictions and HOA enforcement alone.

Cape Nature recommended that wetland encroachment be further reduced or removed and that clear long-term management and funding mechanisms be established to ensure the protection of ecological features. These concerns led to further refinement of the layout, resulting in the development of Alternative 4 (preferred alternative).




Figure 21-2: Alternative 3.

NO GO

This option entails maintaining the status quo with no development. The current state remains unchanged, and no new development initiatives are pursued.

Provide a motivation for the preferred design or layout alternative.

The motivation for selecting Alternative 4 as the preferred layout stems from its ability to effectively acknowledge the site's key environmental sensitivities while still allowing for appropriate residential development. A primary consideration is the presence of a wetland system which, although identified by a freshwater specialist as being in a largely modified state due to historical foreign fill material and alien invasive vegetation, remains an important ecological feature requiring protection and ecological management.

Concerns raised during specialist studies and the public participation process highlighted the importance of maintaining hydrological connectivity between the onsite wetland and the Vermont Salt Pan to the east. Earlier layout alternatives reflected a denser development scenario requiring additional road crossings beyond the existing Lynx Avenue access, which would have resulted in higher residual negative environmental impacts.

The application of the mitigation hierarchy informed the refinement of the development footprint toward a more environmentally responsive layout. Alternative 4 achieves this by reducing erven sizes, consolidating infrastructure, and minimizing encroachment into permanent and seasonal wetland areas. Building footprints are located outside mapped seasonal wetland areas as far as practicably possible, with these areas designated as no-go conservation zones.

The preferred layout prioritizes the preservation of hydrological connectivity through the establishment of conservation servitudes and the provision of a large private open space area incorporating the wetland system. This supports ecological functioning, facilitates faunal movement, and enables wetland rehabilitation and long-term management within the development.

Input received from DEA&DP, CapeNature, BOCMA, Whale Coast Conservation, the Vermont Ratepayers' Association, and other interested and affected parties directly informed the refinement of the layout. These comments resulted in the commissioning of additional specialist studies, including a Freshwater Impact Assessment, Botanical Impact Assessment, Faunal Assessment, Risk Matrix, and Wetland Offset and Rehabilitation Plan. The findings of these studies confirmed that Alternative 4 represents an improvement over the previous layout options by reducing ecological impacts and supporting long-term conservation outcomes.

Further confirmation of the wetland boundary was provided through an independent delineation undertaken by EnviroSwift, which verified the accuracy of the Delta Ecology wetland delineation. Infrastructure planning was also refined to avoid wetland impacts, including the relocation of the sewer pipeline to run parallel to the water pipeline outside of the wetland area.

Overall, Alternative 4 represents the most environmentally responsive and sustainable development option for the site, achieving a balance between ecological protection, technical feasibility, and residential development objectives.

Public Participation Round 1 (Pre-application Process)

The first round of public participation, conducted on 23 March 2023, generated important input from authorities, specialists, and local stakeholders regarding the environmental sensitivity of the site. DEA&DP requested additional information relating to wetland rehabilitation, biodiversity impacts, and the applicability of offsetting. CapeNature highlighted the presence of Critically Endangered Hangklip Sand Fynbos and the importance of the wetland system, recommending that the development footprint be reduced within sensitive areas.

Stakeholders including Whale Coast Conservation and the Vermont Ratepayers' Association emphasized the ecological importance of the wetland and the need for improved stormwater management, ecological buffers, and long-term management mechanisms. These comments resulted in the commissioning of additional specialist studies and the refinement of the site layout to better respond to environmental constraints.

Public Participation Round 2

The second round of public participation was undertaken from 17 May 2024 to 17 June 2024, during which revised layout options were presented to stakeholders. This phase specifically addressed concerns raised during the first consultation process, particularly the protection of the wetland system, stormwater management, and biodiversity impacts.

Additional specialist work was undertaken during this phase, including a comprehensive Aquatic Biodiversity Impact Assessment and Risk Matrix, as well as a Faunal Specialist Assessment. These studies informed further refinement of the development footprint and infrastructure placement, moving the proposal closer to the current preferred layout configuration.

Public Participation Round 3 (In-process)

During the current public participation phase, stakeholders requested that an independent wetland delineation be undertaken to confirm the accuracy of the mapped wetland boundary. EnviroSwift was appointed to conduct this

verification. The findings confirmed that the Delta Ecology wetland delineation was accurate, with only minor mapping differences that did not affect ecological interpretation.

Concerns regarding faunal habitat, including the Cape Dwarf Chameleon (*Bradypodion pumilum*), were also addressed through the faunal specialist study, which confirmed that the provision of the open space area improves habitat connectivity and reduces impacts after mitigation.

CapeNature further recommended that the sewer pipeline alignment avoid the wetland area. In response, the infrastructure layout was revised so that the sewer pipeline runs parallel to the water pipeline outside of the wetland. This refinement represents a significant environmental improvement incorporated into Alternative 3.

Public Participation 4 (In Process)

During this round of the Public Participation Process (PPP), which was intended to be the final round of public participation prior to submission of the Final Basic Assessment Report (BAR) to DEA&DP, additional concerns were raised, particularly by CapeNature, in relation to Alternative 3, which was the previously preferred layout.

CapeNature's comments focused on the long-term management and enforceability of wetland protection measures, noting that portions of the proposed residential erven still overlapped with the seasonal wetland area. Concerns were raised that management through a Homeowners Association (HOA) alone may not be sufficient to ensure long-term protection, and that a conservation body or appropriate financial mechanism would be required to secure the wetland offset area. On this basis, CapeNature indicated that they did not support Alternative 3.

Following these comments, a meeting was held between the project specialists and the applicant to discuss the feasibility of the development and to explore alternative mechanisms and layout refinements that could address CapeNature's concerns.

Based on the above, and due to time constraints associated with the Public Participation process, the application was withdrawn prior to submission of the Final BAR. A new application has subsequently been resubmitted, resulting in the restart of the Public Participation Process.

Revised Layout Alternative (Alternative 4)

Following the withdrawal and resubmission of the application, the development layout was revisited in consultation with the project specialists and the applicant to address the concerns raised by CapeNature regarding wetland protection and long-term management. This process resulted in the development of a revised layout (Alternative 4), which is now identified as the new preferred alternative. The revised layout significantly reduces the interface between the proposed residential erven and the delineated wetland areas and increases the extent of land allocated as private open space, thereby improving the protection of the wetland system.

Under Alternative 4, a larger open space area has been incorporated into the layout, allowing the majority of the proposed erven to be located outside of the seasonal wetland area. While minor encroachment remains associated with a limited number of erven and sections of the internal road infrastructure, this represents a significant improvement compared to the earlier layout alternatives, which had greater overlap with the seasonal wetland.

It is important to note that the layout has undergone several refinements throughout the planning process in order to achieve the best practicable environmental option for the site, taking into account site-specific ecological constraints, including wetland extent and ecological connectivity. The revised layout was reviewed by CapeNature, who indicated

that the changes made under Alternative 4 satisfactorily address the key concerns raised in relation to the previous layout (Alternative).

The revised layout also supports the implementation of structured long-term management mechanisms, including HOA-led long-term management of the open space, potential levy-based funding mechanisms, and continued engagement with relevant authorities and stakeholders regarding appropriate wetland offset securing mechanisms.

As a result, Alternative 4 represents a refined and more environmentally responsive layout, which better addresses the concerns raised during the previous public participation process while maintaining the overall development objectives.

Provide a detailed motivation if no design or layout alternatives exist.

N/A

List the positive and negative impacts that the design alternatives will have on the environment.

ALTERNATIVE ONE

Positive:

- Supply of residential erven to Vermont and Hermanus in response to large demand for residential opportunities.
- Investment in the area
- Upgrade and / or contribution to service infrastructure in the area
- Job creation during construction and post-construction phase.

Negative:

- No consideration of the wetland on site
- No opportunity for rehabilitation of the wetland and long-term management thereof to facilitate ecological linkages with the adjacent freshwater systems.
- Loss of high ecologically sensitive areas

ALTERNATIVE TWO

Positive:

- Supply of residential erven to Vermont and Hermanus in response to large demand for residential opportunities.
- Investment in the area
- Upgrade and / or contribution to service infrastructure in the area
- Job creation
- Design with the wetland system in consideration
- Opportunity to rehabilitate the wetland and provide long term management as well as facilitate connection with the surrounding freshwater ecosystems
- Management of activities on site and not adhoc use as currently experienced

Negative:

- Loss of high botanical sensitive areas still takes place
- Loss of wetland area as well as faunal habitats

ALTERNATIVE 3 (PREVIOUS PREFERRED)

Positive

- Job opportunities during the construction and operational phase
- Investments
- Provision of housing
- Incorporation of large open spaces for ecological connectivity

Negative

- Loss of high ecological areas will occur but reduced impacts due to layout changes
- Few residential erven proposed.

ALTERNATIVE 4 (PREFERRED)

Positive

- Improved avoidance of the seasonal wetland through revised layout design.
- Larger open space area allocated to protect the wetland system and associated ecological processes.
- Enhanced opportunity for wetland rehabilitation and structured long-term management.
- Improved ecological connectivity within the freshwater system.
- Reduced environmental impact compared to Alternatives 1–3.
- Continued provision of residential erven within the urban edge.
- Investment in local infrastructure and services.
- Job creation during construction and operational phases.

Negative

- Minor encroachment associated with limited erven and internal road infrastructure remains within the seasonal wetland edge.
- Loss of some secondary or disturbed vegetation within the development footprint.
- Long-term management responsibilities required for the wetland offset area.

NO-GO

Positive:

- The site will remain undeveloped, and the current state will persist
- No clearance of indigenous vegetation on site
- Positive sense of place for residents
- No encroachment or risk to the onsite wetland habitat

Negative:

- No management and rehabilitation of the wetland
- Continuous degrade of the site at the hand of unregulated and uncontrolled activities on site
- No alien vegetation management
- No investment, job creation or infill development with highly developed suburb of Vermont and Hermanus

1.4.	Technology alternatives (e.g., to reduce resource demand and increase resource use efficiency) to avoid negative impacts, mitigate unavoidable negative impacts and maximise positive impacts.
Provide a description of the preferred technology alternative:	
No specific technology alternatives have been explored; however the most recent technological advances will be applied during both construction, design and operations to ensure that the environmental impacts are reduced.	
Provide a description of any other technology alternatives investigated.	
N/A	
Provide a motivation for the preferred technology alternative.	
N/A	
Provide a detailed motivation if no alternatives exist.	
N/A	
List the positive and negative impacts that the technology alternatives will have on the environment.	
N/A	
1.5.	Operational alternatives to avoid negative impacts, mitigate unavoidable negative impacts and maximise positive impacts.
Provide a description of the preferred operational alternative.	
The proposed development entails the establishment of six residential erven, associated private roads, and formal open space on Erf 1486, Vermont, Hermanus, under the preferred layout, Alternative 4. Four erven are situated on the northern portion of the site, accessed via a road entering from Lynx Road, and two erven on the southern portion, accessed via an internal driveway. The layout has been developed through five rounds of public participation since 2023 and reflects the outcome of an iterative application of the mitigation hierarchy, during which the number of proposed development sites was reduced from an original 13 to 6. Under Alternative 4, the majority of the on-site wetland system approximately 9,361 m² is designated as Private Open Space and No-Go Area, encompassing the permanent wetland and the majority of the seasonal and temporary wetland zones, within which no development will be permitted. A very minor, unavoidable encroachment associated with access infrastructure remains, representing the residual impact of the preferred layout. The long-term protection and management of this designated wetland and open space area will be secured through two reinforcing instruments. First, a council-approved co-management agreement between the Overstrand Municipality and a Homeowners Association (HoA) and / developer, as recommended by Cape Nature, will carry the standing of a formal policy document and provide the necessary long-term institutional security for the offset area. Second, the HoA itself will be legally constituted with a registered constitution and established as a mandatory condition of Environmental Authorisation and of property transfer, undertaking the day-to-day operational responsibilities set out in the co-management agreement, including: • Management and protection of all designated No-Go Areas and Private Open Space; • Implementation of the Wetland Offset, Rehabilitation and Management Plan (WORMP); • Maintenance of stormwater management infrastructure; • Alien vegetation clearing and ecological restoration;	

- Administration of a dedicated environmental levy, funding wetland rehabilitation, ecological corridor maintenance, alien vegetation control, monitoring and reporting, and the appointment of ecological specialists where required.

This levy-based environmental management fund is modelled on approaches such as the Nature Care Fund, which is supported by conservation authorities in the Overstrand region as a practical, financially sustainable mechanism for securing the long-term management of smaller wetland systems.

Protection of the No-Go areas is accordingly secured through a layered set of legal, financial and institutional mechanisms Environmental Authorisation conditions, the council-approved co-management agreement between the Municipality and the HoA, the HoA constitution and management rules, a dedicated No-Go Management Plan, a Maintenance Management Plan, and the Environmental Management Programme (EMPr) rather than reliance on voluntary compliance alone. During the operational phase, the HoA, supported by specialists where necessary and operating under the co-management agreement, will be responsible for ensuring that no development occurs within the wetland No-Go areas, that indigenous landscaping principles are followed, that stormwater infrastructure functions as designed, that wetland rehabilitation targets are met, and that ecological connectivity between the Vermont Salt Pan and surrounding natural systems is maintained.

Please note that Lornay Environmental Consulting, in response to Cape Natures recommendations after PPP4, presented the site to Nature Connect to determine whether they would take on the site and its long-term management. At the end of these discussions, it was concluded that the site was too small for their current management and funding models and that local role players would be better suited for such activities. Lornay Environmental Consulting approached Whale Coast Conservation on the matter, particularly due to their location adjacent to the subject site as well as the ability for this conservation area to link with the future plans for the rehabilitation of the Vermont Salt Pan and Paddavlei Link, however WCC declined to be involved.

Nature Connect (<https://natureconnect.earth/>) is a NPO based in Cape Town and actively involved in the long term management and funding mechanism for open spaces and conservation servitudes linked to developments and authorisations.

Provide a description of any other operational alternatives investigated.

N/A

Provide a motivation for the preferred operational alternative.

N/A

Provide a detailed motivation if no alternatives exist.

N/A

List the positive and negative impacts that the operational alternatives will have on the environment.

N/A

1.6. The option of not implementing the activity (the 'No-Go' Option).

Provide an explanation as to why the 'No-Go' Option is not preferred.

The 'No-Go' Option, which entails maintaining the status quo without implementing the proposed development activity, is not preferred due to several factors. Firstly, it fails to address the need for balanced urban infill development in Vermont. Secondly, it overlooks the opportunity to rehabilitate the site and reinstate the ecological corridor between Hoek van der Berg and the Vermont Salt Pan whilst including a development option which allows for infill development within the built-up urban edge and avoids sensitive areas and mitigates ecological impact through careful planning and design. Ultimately, by choosing not to proceed with the proposed activity, the potential benefits of responsible development, such as accommodating the growing population, job creation, economic growth, and sustainable land use practices, would be missed, undermining the long-term prosperity and well-being of the community.

1.7.	Provide an explanation as to whether any other alternatives to avoid negative impacts, mitigate unavoidable negative impacts and maximise positive impacts, or detailed motivation if no reasonable or feasible alternatives exist.
------	---

Four layouts and the no go have been assessed in the NEMA process. Two rounds of out of process public participation and three rounds of in process PP, have been undertaken to date, as follows:

- PPP1: 22/03/2023 - 24/04/2023 (Pre-Application)
- PPP2: 17/05/2024 - 17/06/2024 (Pre-Application)
- PPP3: 20/06/2025 – 23/07/2025 (In Process)
- PPP4: 29/09/2025 – 23/10/2025 (In Process)
- Consultation with Cape Nature – See Cape Nature comment dated 6 November 2025)
- PPP5: 20 May 2026 – 20 July 2026

Alternative 1 formed the initial layout for the proposal based on the concept, as per the adjacent development typologies, to create a grid type residential development. Alternative two was initially presented as the preferred Alternative in Public participation rounds 1 and 2, however, there were challenges on the layout due to its encroachment on highly sensitive habitats (i.e. seasonal wetland area). The Terrestrial Biodiversity Impact Assessment mitigation measures proposed that the following erven should be removed from the previous preferred layout (Alternative 2): 1, 2, 7, 8, 10, 11, 12 and 13. Additional to this, the proposed access road had to be redesigned so that it does not lie across the wetland and ecological corridor and can instead access Erf 9 along the southern boundary. It was recommended by the aquatic biodiversity specialist that the actual development footprints should then be positioned within the proposed new Erven out of the seasonal wetland boundary, as this will result to the reduced impact on wetland loss.

Cape Nature recommended that development footprints be positioned outside the seasonal wetland boundary, which would reduce wetland loss and associated ecological impacts.

Alternative 3, which was subsequently identified as the previously preferred layout, incorporated many of the specialist recommendations and stakeholder inputs. However, this alternative was not supported by Cape Nature, as portions of the proposed erven still encroached into the seasonal wetland area. Concerns were also raised regarding the feasibility of protecting wetland portions located within residential erven through title deed restrictions, which were considered impractical and difficult to enforce.

Furthermore, Alternative 3 did not fully address concerns relating to the long-term management of the wetland and open space areas, as reliance on HOA-led management alone was considered insufficient without a clearer management and funding mechanism.

For the above reasons, the layout was further refined, resulting in Alternative 4, which is now identified as the preferred alternative. **This layout has been supported by Cape Nature as per their letter dated 6 November 2025.** Alternative 4 incorporates a larger consolidated open space area, improves the avoidance of the seasonal wetland, and allows the

majority of residential erven to be located outside of environmentally sensitive areas. The revised layout also enables the implementation of structured long-term management mechanisms, including HOA-led management supported by levy-based funding and monitoring measures.

Through the iterative design process, specialist input, and stakeholder engagement, reasonable and feasible layout alternatives have been explored and refined to avoid and minimise environmental impacts while maximising development and environmental benefits. Alternative 4 is therefore considered the best practicable environmental option for the site, taking into account site-specific ecological constraints, wetland protection requirements, and development feasibility.

1.8. Provide a concluding statement indicating the preferred alternatives, including the preferred location of the activity.

Based on the specialist assessments, stakeholder engagement, and the outcomes of the public participation process, Alternative 4 is identified as the preferred development alternative. This layout represents the best practicable environmental option, as it avoids the majority of the seasonal wetland area, consolidates ecologically sensitive areas within a larger open space system, and supports the implementation of long-term wetland management and rehabilitation measures. As per the Cape Nature letter dated 6 November 2026, Cape Nature supports the proposal as per Alternative 4.

The preferred alternative allows for the development of residential erven within the less environmentally sensitive portions of the property, while protecting the wetland and associated ecological processes through setbacks, open space allocation, and management interventions. Minor infrastructure interfaces with the seasonal wetland edge remain unavoidable due to site-specific constraints, but these have been minimised through the iterative design process.

The preferred location of the activity remains within Erf 1486, Vermont, situated inside the urban edge of Vermont/Hermanus, where infill residential development is consistent with the surrounding land use and municipal planning context.

The preferred alternative therefore balances environmental protection, development feasibility, and long-term management of the wetland system, and is considered the most appropriate option for implementation.

2. “No-Go” areas

Explain what “no-go” area(s) have been identified during identification of the alternatives and provide the co-ordinates of the “no-go” area(s).

The “No-Go” area has been identified as the 9,361 m² portion of the UVB wetland that remains undeveloped in the preferred layout (Alternative 4). This area includes the majority of the wetland, encompassing the permanent wetland zone as well as the remaining seasonal and temporary zones, following the unavoidable loss of approximately 0.024 ha (3%) due to access roads.

To ensure the ecological integrity of the no-go area, no residential erven, roads, or other development activities will be permitted beyond the demarcated wetland boundaries as indicated in the Site Development Plan. The only permissible land use within this area will be indigenous or natural gardens, in line with the recommendations of the Wetland Offset, Rehabilitation and Management Plan. Table 8-1 of the plan provides the list of indigenous plant species suitable for introduction within the wetland offset area.




Figure 22: provides a visual representation of the UVB wetland on site, highlighting both the permanent and seasonal/temporal zones to illustrate the extent of the no-go area.

3. Methodology to determine the significance ratings of the potential environmental impacts and risks associated with the alternatives.

Describe the methodology to be used in determining and ranking the nature, significance, consequences, extent, duration of the potential environmental impacts and risks associated with the proposed activity or development and alternatives, the degree to which the impact or risk can be reversed and the degree to which the impact and risk may cause irreplaceable loss of resources.

An impact is any change to a resource or receptor brought about by a project component or through the execution of a project related activity. The evaluation of baseline data provides information for the process of evaluating and describing how the project could affect the biophysical and socio-economic environment.

Impact is described according to their nature or type, as follows:

Nature/ Type

Nature/ Type of impact	Definition
Positive	An impact that is considered to represent an improvement on the baseline or introduces a positive change.
Negative	An impact that is considered to represent an adverse change from the baseline, or introduces a new undesirable factor.
Direct	Impacts that result from a direct interaction between a planned project activity and the receiving environment/receptors (e.g. between occupation of a site and

	the pre-existing habitats or between an effluent discharge and receiving water quality).
Indirect	Impacts that result from other activities that are encouraged to happen as a consequence of the Project (e.g. in-migration for employment placing a demand on resources).
Cumulative	Impacts that act together with other impacts (including those from concurrent or planned future third-party activities) to affect the same resources and/or receptors as the Project.

Significance

Impacts are described in terms of significance. Significance is a function of the magnitude of the impact and the likelihood of the impact occurring:

Impact Magnitude	
Extent	On site – impacts that are limited to the boundaries of the development site.
	Local – impacts that affect an area in a radius of 20 km around the Development site.
	Regional – impacts that affect regionally important environmental resources or are experienced at a regional scale as determined by administrative boundaries, habitat type/ecosystem.
	National – impacts that affect nationally important environmental resources or affect an area that is nationally important/ or have macro-economic consequences
Duration	Temporary – impacts are predicted to be of short duration and intermittent/occasional.
	Short-term – impacts that are predicted to last only for the duration of the construction period.
	Long-term – impacts that will continue for the life of the Project but ceases when the project stops operating
	Permanent – impacts that cause a permanent change in the affected receptor or resource (e.g. removal or destruction of ecological habitat) that endures substantially beyond the project lifetime
	BIOPHYSICAL ENVIRONMENT
	Negligible – the impact on the environment is not detectable.
	Low – the impact affects the environment in such a way that natural functions and processes are not affected.
	Medium – where the affected environment is altered but natural functions and processes continue, albeit in a modified way.
Intensity	High – where natural functions or processes are altered to the extent that they will temporarily or permanently cease
	SOCIO-ECONOMIC
	Negligible – there is no perceptible change to people's livelihood
	Low - people/communities are able to adapt with relative ease and maintain pre-impact livelihoods
	Medium – people/communities are able to adapt with some difficulty and maintain pre-impact livelihoods but only with a degree of support

High - affected people/communities will not be able to adapt to changes or continue to maintain pre-impact livelihoods.

Likelihood- the likelihood that an impact will occur

Likelihood	
Unlikely	The impact is unlikely to occur
Likely	The impact is likely to occur under the most conditions.
Definite	The impact will occur

Once an assessment is made of the magnitude and the likelihood, the impact significance is rated through a matrix process:

Significance				
Magnitude		Unlikely	Likely	Definite
	Negligible	Negligible	Negligible	Minor
	Low	Negligible	Minor	Minor
	Medium	Minor	Moderate	Moderate
	High	Moderate	Major	Major

Definition of significance:

Negligible	An impact of negligible significance (or an insignificant impact) is where a resource or receptor (including people) will not be affected in any way by a particular activity, or the predicted effect is deemed to be 'negligible'.
Minor	An impact of minor significance is one where an effect will be experienced, but the impact magnitude is small (with and without mitigation) and within accepted standards, and/or the receptor is of low sensitivity/value.
Moderate	An impact of moderate significance is one within accepted limits and standards. The emphasis for moderate impacts is on demonstrating that the impact has been reduced to a level that is as low as reasonably practicable. This does not necessarily mean that 'moderate' impacts have to be reduced to 'minor' impacts, but that moderate impacts are managed effectively and efficiently.
Major	An impact of major significance is one where an accepted limit or standard may be exceeded, or large magnitude impacts occur to highly valued / sensitive resource / receptors. A goal of the EIA process is to get to a position where the Project does not have any major residual impacts.

Significance of an impact is then qualified through a statement of the degree of confidence. Degree of confidence is expressed as low, medium or high.

Significance colour scale (if applicable):

Negative	Positive
Negligible	Negligible
Minor	Minor
Moderate	Moderate
Major	Major

Impact rating colour scale:

Negative	Positive
Negligible	Negligible
Low	Low
Medium	Medium
High	High

4. Assessment of each impact and risk identified for each alternative

Note: The following table serves as a guide for summarising each alternative. The table should be repeated for each alternative to ensure a comparative assessment. The EAP may decide to include this section as Appendix J to this BAR.

SUMMARY OF ALTERNATIVES


ALTERNATIVE ONE

Positive:

- Supply of residential erven to Vermont and Hermanus in response to large demand for residential opportunities.
- Investment in the area
- Upgrade and / or contribution to service infrastructure in the area
- Job creation

Negative:

- No consideration of the wetland on site
- No opportunity for rehabilitation of the wetland and long-term management thereof to facilitate linkages with the adjacent freshwater systems




ALTERNATIVE TWO

Positive:

- Supply of residential erven to Vermont and Hermanus in response to large demand for residential opportunities.
- Investment in the area
- Upgrade and / or contribution to service infrastructure in the area
- Job creation
- Design with the wetland system in consideration
- Opportunity to rehabilitate the wetland and provide long term management as well as facilitate connection with the surrounding freshwater ecosystems
- Management of activities on site and not adhoc use as currently experienced

Negative:

- All proposed residential erven on the Northern part of the property encroach within the delineated seasonal/temporal wetland area.
- loss of high ecological sensitive areas.
- One access road crossing the wetland to the residential erven.




ALTERNATIVE 3

Positive:

- Presented as previously preferred in PPP4
- Supply of residential erven to Vermont and Hermanus in response to large demand for residential opportunities.
- Investment in the area
- Upgrade and / or contribution to service infrastructure in the area
- Job creation
- Design with the wetland system in consideration
- Opportunity to rehabilitate the wetland and provide long term management as well as facilitate connection with the surrounding freshwater ecosystems
- Management of activities on site and not adhoc use as currently experienced
- Lower ecological impact than the previous alternative assessed.
- Proposed residential erven now exclude most of the High sensitivity areas
- Development includes two private access roads away from the delineated wetland area.

Negative:

- About 500m² of high sensitivity habitat will now be lost.
- Loss of sensitive vegetation will occur.



ALTERNATIVE 4

Positive

- Layout supported by Cape Nature as per their letter dated 6 November 2026
- Improved avoidance of the seasonal wetland through revised layout design.
- Larger open space area allocated to protect the wetland system and associated ecological processes.
- Enhanced opportunity for wetland rehabilitation and structured long-term management.
- Improved ecological connectivity within the freshwater system.
- Reduced environmental impact compared to Alternatives 1–3.
- Continued provision of residential erven within the urban edge.
- Investment in local infrastructure and services.
- Job creation during construction and operational phases.

Negative

- Minor encroachment associated with limited erven and internal road infrastructure remains within the seasonal wetland edge.
- Loss of some secondary or disturbed vegetation within the development footprint.
- Long-term management responsibilities required for the wetland offset area.

NO GO

Positive:

- No removal of vegetation and status quo remains

Negative:

- No management and rehabilitation of the wetland
- Continuous degrade of the site at the hand of unregulated and uncontrolled activities on site
- No alien vegetation management
- No investment, job creation or infill development with highly developed suburb of Vermont and Hermanus

ALTERNATIVE 1

PLANNING, DESIGN AND DEVELOPMENT PHASE

Potential impact and risk:	1. Socio-economic
Potential impact	Job creation during the development /construction phase of the Erven
Nature of impact:	Positive
Extent and duration of impact:	local; short-term
Consequence of impact or risk:	Improved livelihoods of the community
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	Job creation for local community
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High Positive
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	1. Ensure labour force is sourced locally as far as possible. 2. A gender balance to be considered during employment.
Residual impacts:	1. Improved livelihoods 2. Improvement of local economy, skills transfer, investment in the area
Cumulative impact post mitigation:	Job creation and skills transfer to local community
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High Positive

PLANNING, DESIGN AND DEVELOPMENT PHASE

Potential impact and risk:	2. Dust
Potential impact	Dust generated from site clearing and site preparation
Nature of impact:	Negative
Extent and duration of impact:	Local, short term
Consequence of impact or risk:	Visual impacts Nuisance for residents adjacent to the site
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	Low
Degree to which the impact can be reversed:	High

Indirect impacts:	Potential for reduced visibility, temporary visual impacts to the general area
Cumulative impact prior to mitigation:	Dust may be generated as a result of earthmoving activities required for construction and development
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium High, High, or Very-High)	High negative
Degree to which the impact can be avoided:	High
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	1. Maintain ground cover for as long as possible to reduce the total surface area exposed to wind. Do not clear entire plots and rather clear building sites only 2. Ensure vehicle speed limits on site are kept to a minimum. 3. Delivery vehicles to keep loads covered. 4. Cover fine material stockpiles. 5. Wet dry and dusty surfaces using non-potable water. 6. Staff to wear correct PPE if dust is generated for long periods. 7. Road surfaces to be swept and kept clean of sand and fine materials
Residual impacts:	None
Cumulative impact post mitigation:	Dust generated during construction, mitigation successful
Significance rating of impact after mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Very-Low Negative

PLANNING, DESIGN AND DEVELOPMENT PHASE

Potential impact and risk:	3. Noise
Potential impact	Noise generated from vehicles and machinery during the construction phase.
Nature of impact:	Negative
Extent and duration of impact:	Local, short term
Consequence of impact or risk	Noise disturbance to transient receptors, i.e. motorists, pedestrians, residents.
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	No resources will be impacted.
Degree to which the impact can be reversed:	High
Indirect impacts:	None
Cumulative impact prior to mitigation:	Noise generated from construction works
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	High negative
Degree to which the impact can be avoided:	Medium – High
Degree to which the impact can be managed:	Medium – High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	1. Limit noise levels (e.g. install and maintain silencers on machinery).

	2. Provide protective wear for workers i.e. ear plugs. 3. Ensure that construction vehicles and machinery are maintained regularly to reduce noise generation. 4. Restrict construction to normal working hours
Residual impacts:	None
Cumulative impact post mitigation:	Typical noise impacts associated with a construction site
Significance rating of impact after mitigation (e.g. Low, Medium, Medium High, High, or Very-High)	Low Negative

PLANNING, DESIGN AND DEVELOPMENT PHASE

Potential impact and risk:	4. Visual
Potential impact:	Visual impacts of construction site and construction activities.
Nature of impact:	Negative
Extent and duration of impact:	Local, short term
Consequence of impact:	Reduce aesthetic value of the site and surrounds
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	High
Indirect impacts:	None
Cumulative impact prior to mitigation:	Short term visual impacts associated with construction
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	High negative
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	1. Good housekeeping of construction site and working areas. 2. Screen the visual elements of the site camp with netting. 3. Locate the site camp in a transformed area. 4. Site officer to walk the site on a daily basis to check for visual impacts and general site aesthetics, particularly prior to weekends and holidays 5. Officer to ensure that waste and batching areas are correctly screened and secured to prevent spread by wind, rain or animals
Residual impacts	None
Cumulative impact post mitigation:	Typical visual impacts associated with a construction site
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	Low Negative

PLANNING, DESIGN AND DEVELOPMENT PHASE

Potential impact and risk:	5. Ecological Impact
Potential impact:	It can safely be assumed that the primary construction phase ecological impact of the proposed subdivision and development would be permanent loss of all of the existing natural and partly

	natural vegetation and faunal habitat in the development footprints (gazetted as a Critically Endangered vegetation type)
Nature of impact:	Negative
Extent and duration of impact:	Local; Permanent
Consequence of impact:	Vegetation loss, species loss, diversity loss, connectivity loss Exposure of soil and degradation thereof
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	High
Degree to which the impact can be reversed:	Low
Indirect impacts:	Continued loss of all critically endangered natural vegetation on site
Cumulative impact prior to mitigation:	Loss of natural vegetation and faunal habitat and threatened plant species to ongoing agriculture, urban development and alien plant invasion
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	High
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Low
Degree to which the impact can be mitigated:	Low
Proposed mitigation:	→ No erven should intrude significantly into the seasonal wetland portions of the site that support mostly habitat of High ecological sensitivity (as per Figure 4). This means that the following erven should be removed from any authorised layout: 1, 2, 7, 8, 10, 11, 12 and 13. The proposed access road (erf 14) should also be largely removed so that it does not cross the wetland and ecological corridor, and can instead access erf 9 along the southern boundary. → No pipelines, cabling or infrastructure should be installed across the High sensitivity areas or wetlands. → Any boundary fencing used must be permeable to small animals at ground level. → The authorised erf and road boundaries should be surveyed and pegged out and fenced on site prior to any site development. → No areas of natural or partly natural vegetation should be disturbed outside the pegged/fenced out and authorised erven. No vehicular activity or dumping of material may take place outside the authorised erven or roads. → All alien invasive vegetation should be removed from within the natural portions of the project area, prior to any authorised development. Removal of the alien vegetation must be undertaken by a trained and licensed alien vegetation removal team and must be undertaken using methodology outlined in the Best Practise Guidelines (see Martens et al 2021). → The Homeowners Association (HoA, or similar) for the proposed development must ensure that all alien invasive vegetation (as per NEMBA legislation) is removed from the Public Open Space area on an annual basis by qualified contractors, using methodology as prescribed in Martens et al

	(2021; see below for reference).The HoA must ensure that there is adequate funding for this every year. - In order to try and safeguard the ecological integrity of the No Go wetland areas on Erven 1-8 (also shown in Figure 1) these areas that should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way. Landowners and the HoA must be made aware of these constraints both prior to and after purchase. Alien invasive plant species should be removed from these areas on an annual basis, as part of the management actions required for the adjacent Private Open Space.
Residual impacts	Loss of high sensitivity vegetation
Cumulative impact post mitigation:	Loss of high sensitivity vegetation
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	High negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	6. Wetland Loss in the delineated UVBW
Potential impact:	During the construction phase there would be loss of all the high ecological sensitive species on site and the wetland. Loss of ecological connectivity as well as hydrological connection from the wetland on site to the Vermont Salt Pan downstream which is an NFEPA designated wetland area.
Nature of impact:	High; Negative
Extent and duration of impact:	Local; Permanent
Consequence of impact:	Loss of wetland habitat, critically endangered fauna and wetland plants.
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	High
Degree to which the impact can be reversed:	Very low
Indirect impacts:	Loss of the entire wetland on site.
Cumulative impact prior to mitigation:	Loss of wetland and habitat for SoCC that could potentially be found on site
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Very High
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	N/A
Degree to which the impact can be mitigated:	N/A
Proposed mitigation:	→ The only mitigation applicable to wetland loss is reduction of the area of loss. → It is recommended that the proposed residential areas are positioned within the proposed new Erven so as to avoid the delineated wetland area.

	→ Should the proposed residential developments avoid the wetland area entirely, the impact of Wetland Loss, as assessed in this report, will not be applicable.
Residual impacts:	Wetland loss, impact on adjacent freshwater systems, impact on infrastructure located within permanent wetland area
Cumulative impact post mitigation:	Wetland loss, impact on adjacent freshwater systems, impact on infrastructure located within permanent wetland area
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	7. Faunal impacts
Potential impact:	Infringement of development footprint on ESA2 corridor
Nature of impact:	Negative
Extent and duration of impact:	Local and long term
Consequence of impact:	High
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	High
Degree to which the impact can be reversed:	Irreversible
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	High
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Low
Degree to which the impact can be mitigated:	Low
Proposed mitigation:	Amend the site layout
Residual impacts:	Loss of all faunal species on the development footprint
Cumulative impact post mitigation:	High Loss of faunal connectivity on site as a result of development footprint
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative

POST-CONSTRUCTION PHASE	
Potential impact and risk:	1. Socio economic impacts
Potential impact	Access to employment for the community during the operational phase, Job creation, Provision of residential erven in response to provincial demand, investment in the area
Nature of impact:	Positive
Extent and duration of impact:	Local, long-term
Consequence of impact or risk:	Improved livelihoods beneficiaries, influx of people to the area, investment in the area, spending in the area
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	Access to employment for the community during the operational phase, Job creation, Provision of residential erven in response to provincial demand, investment in the area
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High positive
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	N/A
Proposed mitigation:	-
Residual impacts:	Investment in the area, attraction to the area, spending in the area
Cumulative impact post mitigation:	Investment in the area, attraction to the area, spending in the area Access to employment for the community during the operational phase, Job creation, Provision of residential erven in response to provincial demand, investment in the area
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High positive
POST-CONSTRUCTION PHASE	
Potential impact and risk:	2. Visual
Potential impact:	Typical Visual impacts associated with the operational phase of a residential dwelling or group of residential dwellings that may lead to changes in sense of place of the individual from what was there and to what has now changed.
Nature of impact:	Negative – changes in the visual aesthetics of the area during the operational phase. Positive- infill development within an urban area as opposed to the alienation of new land, contributing to more sustainable land use.
Extent and duration of impact:	Long term, local to regional
Consequence of impact:	Risk – visual impact of operation within landscape and suburb
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	High

Indirect impacts:	Loss of sense of place due to the removal of the natural vegetation that is appealing to nature lovers
Cumulative impact prior to mitigation:	Short term impacts associated with changes of the built infrastructure.
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	High negative
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Low
Degree to which the impact can be mitigated:	High
Proposed mitigation:	• Implement landscaping strategies to minimize the visual impact of construction and operational activities. • Incorporate green design principles into the development to enhance aesthetics and mitigate negative visual effects. • Communicate with the community to ensure understanding and acceptance of the changes in the visual character. • Consider the use of native vegetation in landscaping to maintain a natural feel and reduce visual disruptions.
Residual impacts	None
Cumulative impact post mitigation:	Typical visual impacts associated with operational phase
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low negative
POST-CONSTRUCTION PHASE	
Potential impact and risk:	3. Ecological
Potential impact:	Loss of current moderate levels of ecological connectivity across the site (essentially only W-E connectivity is now available), and associated habitat fragmentation. Loss of ability for natural fires Loss of sensitive botanical areas and vegetation Reduction in natural habitat
Nature of impact:	Negative – ecological impacts Positive – infill development within urban area as opposed to alienation of new land
Extent and duration of impact:	Permanent, local to regional
Consequence of impact:	Loss of all available natural or partly natural faunal habitat on site. Loss of natural spaces, corridors and high ecological species.
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	High
Degree to which the impact can be reversed:	N/A
Indirect impacts:	Loss of moderate current ecological connectivity across the site and associated habitat fragmentation.
Cumulative impact prior to mitigation:	Loss of all natural spaces, corridors and vegetation on site.

Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Very High
Degree to which the impact can be avoided:	Possible
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium
Proposed mitigation:	→ No erven should intrude significantly into the seasonal wetland portions of the site that support mostly habitat of High ecological sensitivity (as per Figure 4). This means that the following erven should be removed from any authorised layout: 1, 2, 7, 8, 10, 11, 12 and 13. The proposed access road (erf 14) should also be largely removed so that it does not cross the wetland and ecological corridor, and can instead access erf 9 along the southern boundary. → No pipelines, cabling or infrastructure should be installed across the High sensitivity areas or wetlands. → Any boundary fencing used must be permeable to small animals at ground level. → The authorised erf and road boundaries should be surveyed and pegged out and fenced on site prior to any site development. → No areas of natural or partly natural vegetation should be disturbed outside the pegged/fenced out and authorised erven. No vehicular activity or dumping of material may take place outside the authorised erven or roads. → All alien invasive vegetation should be removed from within the natural portions of the project area, prior to any authorised development. Removal of the alien vegetation must be undertaken by a trained and licensed alien vegetation removal team and must be undertaken using methodology outlined in the Best Practise Guidelines (see Martens et al 2021). → The Homeowners Association (HoA, or similar) for the proposed development must ensure that all alien invasive vegetation (as per NEMBA legislation) is removed from the Public Open Space area on an annual basis by qualified contractors, using methodology as prescribed in Martens et al (2021; see below for reference). The HoA must ensure that there is adequate funding for this every year. • In order to try and safeguard the ecological integrity of the No Go wetland areas on Erven 1-8 (also shown in Figure 1) these areas that should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way. Landowners and the HoA must be made aware of these constraints both prior to and after purchase. Alien invasive plant species should be removed from these areas on an annual basis, as part of the management actions required for the adjacent Private Open Space.
Residual impacts	Loss of sensitive vegetation, open spaces, corridors
Cumulative impact post mitigation:	Loss of natural spaces, loss of ecological connectivity, corridors and vegetation
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	High negative

POST-CONSTRUCTION PHASE	
Potential impact and risk:	4. Wetland loss within the UVBW
Potential impact:	Site clearance, infilling and compaction will result in alteration of the flow regime for the onsite wetland and even loss of the entire wetland. Pollutants may enter the onsite wetland via stormwater or sewage leaks (although highly unlikely).
Nature of impact:	Negative
Extent and duration of impact:	Local; permanent
Consequence of impact:	High loss of ecological infrastructure as well as aquatic species
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	Loss of High ecological sensitivity and hydrological connectivity
Cumulative impact prior to mitigation:	High
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	High
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	N/A
Degree to which the impact can be mitigated:	N/A
Proposed mitigation:	→ The significance of this impact can be largely mitigated by demarcating the UVBW as No-Go area during construction. → Bunded, impervious areas that are more than 15 m away from the UVBW must be designated by an Environmental Control Officer for temporary toilets, vehicle parking/servicing areas, and for pouring and mixing of concrete/cement, paint, and chemicals. → The significance of this impact can be largely mitigated by ensuring that SW generated onsite flows into the wetland through an appropriately designed broad, vegetated earth swale (to avoid erosion). → If possible, conduct any rehabilitation activities during summer months (November to March). It is recommended that a suitably qualified aquatic specialist compiles detailed method statements once the final layout of the proposed project has been formalized. → Additionally, a suitable Rehabilitation and Management Plan should be drafted for the wetland area onsite.
Residual impacts	Loss of wetland and ecological connectivity as well as the hydrological connectivity.

Cumulative impact post mitigation:	Loss of wetland and ecological connectivity as well as the hydrological connectivity.
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	High Negative
POST-CONSTRUCTION PHASE	
Potential impact and risk:	5. Faunal impacts
Potential impact:	Continued loss of fauna through introduced domestic animals.
Nature of impact:	Negative
Extent and duration of impact:	Local and long term
Consequence of impact:	High
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	High
Degree to which the impact can be reversed:	Irreversible
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	High
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	High
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Low
Degree to which the impact can be mitigated:	Low
Proposed mitigation:	→ During the construction phase the construction area should be clearly demarcated and blocked off from the 'private open space' area to avoid damage and pollution. → Pre and post construction site preparation should include rehabilitation of the 'private open space' by removing current building rubble and litter from this area. → Long term maintenance of ecological integrity of the 'private open space' is critical. Therefore, measures should be put in place for constant removal of alien vegetation, cleanup of litter and prevention of illegal dumping. Clear legal responsibility for the maintenance of the space should be entrenched to be the responsibility of the homeowners association. → d) The fence traversing the ecological corridor should always be permeable to allow for movement of small sized animals e.g. small antelope, genets, mongoose between the nature reserve and wetland system. → e) Search and Rescue of chameleons and other slow-moving animals is feasible due to the presence of the adjacent nature reserve where they can be released. A search and rescue effort should be implemented before and during construction where animals that are found are released in the adjacent

	nature reserve. The necessary permission and permits should be attained before this is done. → f) Pets (especially domestic cats) should not be allowed to free-roam the 'private open space'.
Residual impacts:	Loss of all faunal species on the development footprint
Cumulative impact post mitigation:	High Loss of faunal connectivity on site due to post-commencement activities on site.
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
DECOMMISSIONING AND CLOSURE PHASE	
Potential impact and risk:	N/A
Nature of impact:	-
Extent and duration of impact:	-
Consequence of impact or risk:	-
Probability of occurrence:	-
Degree to which the impact may cause irreplaceable loss of resources:	-
Degree to which the impact can be reversed:	-
Indirect impacts:	-
Cumulative impact prior to mitigation:	-
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	-
Degree to which the impact can be avoided:	-
Degree to which the impact can be managed:	-
Degree to which the impact can be mitigated:	-
Proposed mitigation:	-
Residual impacts:	-
Cumulative impact post mitigation:	-
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	-

ALTERNATIVE 2

PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	1. Socio-economic impacts
Potential impact	Job creation during the development /construction phase of the Erven
Nature of impact:	Positive
Extent and duration of impact:	Local; short term
Consequence of impact or risk:	Improved livelihoods of the community
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	Job creation for local community
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High Positive
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	→ Ensure labour force is sourced locally as far as possible. → A gender balance to be considered during employment.
Residual impacts:	Improved livelihoods Improvement of local economy, skills transfer, investment in the area
Cumulative impact post mitigation:	Job creation and skills transfer to local community
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High Positive
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	2. Dust
Potential impact	Dust generated from site clearing and site preparation
Nature of impact:	Negative
Extent and duration of impact:	Local, short term
Consequence of impact or risk:	Visual impacts

	Nuisance for residents adjacent to the site
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	Low
Degree to which the impact can be reversed:	High
Indirect impacts:	Potential for reduced visibility, temporary visual impacts to the general area
Cumulative impact prior to mitigation:	Dust may be generated as a result of earthmoving activities required for construction and development
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
Degree to which the impact can be avoided:	High
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	→ Maintain ground cover for as long as possible to reduce the total surface area exposed to wind. Do not clear entire plots and rather clear building sites only → Ensure vehicle speed limits on site are kept to a minimum. → Delivery vehicles to keep loads covered. → Cover fine material stockpiles. → Wet dry and dusty surfaces using non-potable water. → Staff to wear correct PPE if dust is generated for long periods. → Road surfaces to be swept and kept clean of sand and fine materials
Residual impacts:	None
Cumulative impact post mitigation:	Dust generated during construction; mitigation successful
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Very-Low Negative

PLANNING, DESIGN AND DEVELOPMENT PHASE

Potential impact and risk:	3. Noise
Potential impact	Noise generated from vehicles and machinery during the construction phase.
Nature of impact:	Negative
Extent and duration of impact:	Local, short term
Consequence of impact or risk:	Noise disturbance to transient receptors, i.e. motorists, pedestrians, residents.
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	No resources will be impacted.
Degree to which the impact can be reversed:	High
Indirect impacts:	None
Cumulative impact prior to mitigation:	Noise generated from construction works
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative

Degree to which the impact can be avoided:	Medium – High
Degree to which the impact can be managed:	Medium – High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	1. Limit noise levels (e.g. install and maintain silencers on machinery). 2. Provide protective wear for workers i.e. ear plugs. 3. Ensure that construction vehicles and machinery are maintained regularly to reduce noise generation. 4. Restrict construction to normal working hours
Residual impacts:	None
Cumulative impact post mitigation:	Typical noise impacts associated with a construction site
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Low Negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	4. Visual
Potential Impact	Visual impacts of construction site and construction activities.
Nature of impact:	Negative
Extent and duration of impact:	Local, short term
Consequence of impact or risk:	Reduce aesthetic value of the site and surrounds
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	High
Indirect impacts:	None
Cumulative impact prior to mitigation:	Short term visual impacts associated with construction
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	→ Good housekeeping of construction site and working areas. → Screen the visual elements of the site camp with netting. → Locate the site camp in a transformed area. → Site officer to walk the site on a daily basis to check for visual impacts and general site aesthetics, particularly prior to weekends and holidays → Officer to ensure that waste and batching areas are correctly screened and secured to prevent spread by wind, rain or animals
Residual impacts:	None
Cumulative impact post mitigation:	Typical visual impacts associated with a construction site
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Low Negative

PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	5. Ecological Impact
Potential impact:	During the removal of vegetation for the proposed subdivision and development would be permanent loss of all or most of the existing natural and partly natural vegetation and faunal habitat in the development footprints (most of it gazetted as Endangered vegetation type).
Nature of impact:	Negative
Extent and duration of impact:	Local, Regional; Permanent
Consequence of impact:	Vegetation loss, species loss, diversity loss, connectivity loss Exposure of soil and degradation thereof
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	Medium
Degree to which the impact can be reversed:	Low
Indirect impacts:	Continued loss of Hangklip Sand Fynbos (CR)
Cumulative impact prior to mitigation:	Loss of natural vegetation and faunal habitat and threatened plant species to ongoing agriculture, urban development and alien plant invasion
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	High
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Low
Degree to which the impact can be mitigated:	Medium
Proposed mitigation:	→ No erven should intrude significantly into the seasonal wetland portions of the site that support mostly habitat of High ecological sensitivity (as per Figure 4). This means that the following erven should be removed from any authorised layout: 1, 2, 7, 8, 10, 11, 12 and 13. The proposed access road (erf 14) should also be largely removed so that it does not cross the wetland and ecological corridor, and can instead access erf 9 along the southern boundary. → No pipelines, cabling or infrastructure should be installed across the High sensitivity areas or wetlands. → Any boundary fencing used must be permeable to small animals at ground level. → The authorised erf and road boundaries should be surveyed and pegged out and fenced on site prior to any site development. → No areas of natural or partly natural vegetation should be disturbed outside the pegged/fenced out and authorised erven. No vehicular activity or dumping of material may take place outside the authorised erven or roads. → All alien invasive vegetation should be removed from within the natural portions of the project area, prior to any

	authorised development. Removal of the alien vegetation must be undertaken by a trained and licensed alien vegetation removal team and must be undertaken using methodology outlined in the Best Practise Guidelines (see Martens et al 2021). → The Homeowners Association (HoA, or similar) for the proposed development must ensure that all alien invasive vegetation (as per NEMBA legislation) is removed from the Public Open Space area on an annual basis by qualified contractors, using methodology as prescribed in Martens et al (2021; see below for reference). The HoA must ensure that there is adequate funding for this every year. → In order to try and safeguard the ecological integrity of the No Go wetland areas on Erven 1-8 (also shown in Figure 1) these areas that should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way. Landowners and the HoA must be made aware of these constraints both prior to and after purchase. Alien invasive plant species should be removed from these areas on an annual basis, as part of the management actions required for the adjacent Private Open Space.
Residual impacts	Loss of high sensitivity vegetation
Cumulative impact post mitigation:	Loss of high sensitivity vegetation
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	High negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	6. Wetland loss within the delineated UVBW
Potential impact:	At present, areas of the onsite UVBW will be lost (i.e. complete loss in flow regime, water quality, vegetation, and geomorphic structure) as a result of the private road construction associated with the residential development (minor loss of approximately 0,024 ha (3 %) of the 0,90-ha wetland). The remaining delineated wetland area will be set aside for Private Open Space. The UVBW has a PES score in the D category (Largely Modified), however still offers ecosystem services of moderate importance and exhibits Moderate EIS. The wetland vegetation type is CR and although the fynbos onsite is considered senescent, there could potentially be SoCC. There is also hydrological connection to the Vermont Salt Pan downstream which is an NFEPA designated wetland area.
Nature of impact:	Negative
Extent and duration of impact:	Local; permanent
Consequence of impact:	High loss of ecological infrastructure as well as aquatic species
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	Loss of High ecological sensitivity and hydrological connectivity

Cumulative impact prior to mitigation:	High
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	High
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	N/A
Degree to which the impact can be mitigated:	N/A
Proposed mitigation:	→ An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist.
Residual impacts	Loss of wetland and ecological connectivity as well as the hydrological connectivity.
Cumulative impact post mitigation:	Loss of wetland and ecological connectivity as well as the hydrological connectivity.
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium Negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	7. Habitat Disturbance
Potential impact:	Disturbance of wetland habitat within the UVBW may occur due to the proximity of the proposed residential development, including but not limited to vegetation clearing, infilling, and construction of the housing; as well as the upgrade of the existing sewer pipeline.
Nature of impact:	Negative
Extent and duration of impact:	Local; permanent
Consequence of impact:	Loss of aquatic habitat
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	Medium
Degree to which the impact can be reversed:	Low – Medium
Indirect impacts:	Reduced habitat areas for animal species as well as foraging
Cumulative impact prior to mitigation:	Medium
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium – High
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Low-Medium
Degree to which the impact can be mitigated:	Low- Medium
Proposed mitigation:	– Designate the UVB wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline). Clearly demarcate the construction footprint (including construction camp, access roads, stockpile areas and working servitudes) with orange hazard tape, fencing or similar prior to the commencement of any activity, and strictly prohibit the movement of construction vehicles and personnel outside of the demarcated areas.

	– Locate site camps, laydown areas, stockpile areas, construction material, equipment storage areas, vehicle parking areas, bundled vehicle servicing areas and re-fuelling areas in designated areas of already hardened surface or disturbed areas located outside of the No Go area. These areas should preferably be located on level ground in a previously disturbed area of vegetation approved by the Environmental Control Officer (ECO). Cut and fill must be avoided where possible during the set-up of the construction site camp. – Demarcation of the construction footprint/working servitude must be signed off by an ECO (or similar). Demarcation should not be removed until construction is complete, and rehabilitation (if applicable) has taken place. – Limit access into the construction footprint to existing access roads. – Prohibit the dumping of excavated material, building materials or removed vegetation within the No Go area. Building material must be stored at the designated storage area located outside of the no-go area. Spoil material must be appropriately disposed of at a registered waste disposal facility. – Undisturbed topsoil and subsoils removed from the construction footprint must be stored separately at the designated stockpile area for future rehabilitation. – Vegetation clearance should be restricted to the relevant development components and indigenous vegetation cover should be maintained as far as practically possible. – Vegetation which is considered suitable for rehabilitation activities after construction (such as indigenous grasses and other herbaceous species) should be carefully removed from the construction footprint and stored at an appropriate facility for use in later rehabilitation activities. – Clear and remove any rubble or litter that may have been accidentally deposited into the no-go area because of construction activities and dispose of at an appropriate registered facility. – An ECO must inspect the construction footprint on a weekly basis and must take immediate measures to address unforeseen disturbances to the wetland. Any disturbed / compacted areas falling outside of the demarcated construction footprint must be immediately rehabilitated. Depending on the extent of damage the method of rehabilitation may require input from an aquatic specialist / suitably qualified contractor. – Once construction has been completed, orange hazard fences as well as all construction waste, rubble, and
--	--

	equipment must be removed from the construction footprint. – In line with the NEMBA, all AIPS listed under the amended AIPS Lists (DEFF: GN1003, 2020) must either be removed or controlled on land under the management of the proponent. – An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist. Rehabilitation must take place as soon as possible after construction is completed, and monitoring of rehabilitated areas must be undertaken. A suitably qualified professional must supervise the rehabilitation and monitoring activities.
Residual impacts	Loss of wetland habitat and ecological connectivity as well as the hydrological connectivity.
Cumulative impact post mitigation:	Loss of wetland and ecological connectivity as well as the hydrological connectivity.
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	Low Negative Medium negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact:	8. Altered Flow Regime
Nature of impact:	Site clearance, infilling, and compaction will result in alteration of the flow regime of wetland area on the site. Hardened catchment area would result in increased stormwater runoff, velocity and increased flood peaks within the wetland and would also likely result in sedimentation and erosion.
Nature of impact:	Negative
Extent and duration of impact:	Local; short-term
Consequence of impact:	The accumulation of sediments and soil compaction could lead to reduced infiltration capacity, a shift in hydrological functioning, and a loss of habitat suitability for wetland-dependent species.
Probability of occurrence:	High
Degree to which the impact may cause irreplaceable loss of resources:	Medium
Degree to which the impact can be reversed:	Partially reversible
Indirect impacts:	– Decreased water quality downstream due to increased sedimentation – Disruption of aquatic biodiversity – Impaired ecological services such as flood attenuation and nutrient cycling
Cumulative impact prior to mitigation:	Medium- High
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium - High

Proposed mitigation:	– Designate the wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline). – The status quo in terms of hydrological connection from Erf 1486 to the downstream system must be maintained / should not be impacted because of the proposed development. – If possible, conduct construction activities of dwellings, associated stormwater infrastructure and any rehabilitation activities during summer months (November to March). – Ensure that effective stormwater management measures are implemented during construction. Stormwater management must ensure that no runoff, which will impair the water quality and lead to increased sedimentation, may enter the downstream wetland area. Additionally, clean SW which does enter the downstream wetland system should do so in a manner that ensures no erosion occurs, specifically during storm events, such as through vegetated swales. – Appropriately designed raft foundations for residential dwellings may significantly reduce the impact on subsurface flow and therefore reduce this impact / risk. – Rainwater harvesting schemes may reduce runoff intensity and thereby mitigate the impact of catchment hardening. – The alien invasive vegetation present within the wetland area must be removed and replanted with indigenous wetland vegetation. – An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist.
Residual impacts	Minor changes in the timing and magnitude of surface runoff and potential localized compaction near access roads.
Cumulative impact post mitigation:	Low
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	Low negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact:	9. Water Quality Impairment
Nature of impact:	Accidentally spilled cement, construction chemicals, sewage during the upgrade of the pipeline, or petrochemicals from construction vehicles may find their way into the wetland area. Additionally, litter and dumping may occur due to the proximity of the proposed development to the wetland area.
Nature of impact:	Negative
Extent and duration of impact:	Local; short-term
Consequence of impact:	Pollutants such as cement, oils, and sewage can degrade water quality, impact aquatic biodiversity, and reduce the wetland's ecological functioning (e.g., water purification, habitat provision). Toxic substances like cement leachate can be particularly harmful to aquatic flora and fauna, leading to long-term biological stress.

Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	Medium
Degree to which the impact can be reversed:	Moderate
Indirect impacts:	– Decline in aquatic biodiversity – Reduced wetland ecosystem services – Pollution downstream of the wetland area – Long-term contamination of soil and groundwater if unmanaged.
Cumulative impact prior to mitigation:	Medium to High
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium – High
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium – High
Degree to which the impact can be mitigated:	Medium- High
Proposed mitigation:	– Designate the wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline). – The site manager / ECO must check the No Go area for pollution/spills, erosion damage and sedimentation weekly and after every heavy rainfall event. Should pollution, erosion or sedimentation be noted, immediate corrective measures must be undertaken. – Fuel, chemicals, and other hazardous substances should preferably be stored offsite, or as far away as possible from the no-go area. These substances must be stored in suitable secure weather-proof containers with impermeable and bunded floors to limit pilferage, spillage into the environment, flooding, or storm damage. – Inspect all storage facilities, vehicles, and machinery daily for the early detection of deterioration or leaks and strictly prohibit the use of any vehicles or machinery from which leakage has been detected. – Mixing and transferring of chemicals or hazardous substances must take place outside of the No Go area, and must take place on drip trays, shutter boards or other impermeable surfaces. – Drip trays must be utilised at all fuel dispensing areas; and during the maintenance of existing sewer flow as possible. – Vehicles and machinery should preferably be cleaned off site. Should cleaning be required on site it must only take place within designated areas outside of the No Go area and should only occur on bunded areas with a water/oil/grease separator. – Dispose of used oils, wash water from cement and other pollutants at an appropriate licensed landfill site.

	– Avoid the use of infill material or construction material with pollution / leaching potential. Where possible, in situ earthen materials must be used during construction to reduce the risk of leachate from imported materials contaminating the wetland area. – Concrete should preferably be imported as “ready-mix” concrete from a local supplier. Should onsite concrete mixing be required it must not be done on exposed soils. Concrete must be mixed on an impermeable surface in an area of low environmental sensitivity identified by the ECO outside of the no-go area. Surplus or waste concrete must be sent back to the supplier who will dispose of it. – Construct temporary bunds around areas where cement is to be cast in situ. – Dispose of concrete and cement-related mortars in an environmental sensitive manner (can be toxic to aquatic life). Disposal of any of these waste materials into the No Go area is strictly prohibited. – Washout must not be discharged into the no-go area. A washout area should be designated, and wash water should be treated on-site. – Clean up any spillages immediately with the use of a chemical spill kit and dispose of contaminated material at an appropriately registered facility. – Provide portable toilets where work is being undertaken (1 toilet per 10 workers). These toilets must be located within an area designated by the ECO outside of the no-go area and should preferably be located on level ground. Portable toilets must be regularly serviced and maintained. – Provide an adequate number of bins on site and encourage construction personnel to dispose of their waste responsibly. – Waste generated by construction personnel must be removed from the site and disposed of at a registered waste disposal facility on a weekly basis
Residual impacts	Residual impacts may include minor localized contamination from accidental small spills, which can be quickly addressed with spill kits and clean-up procedures.
Cumulative impact post mitigation:	Medium
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	10. Faunal impacts
Potential impact:	Infringement of development footprint on ESA2 corridor and Cape dwarf chameleon, <i>Bradypodion pumilum</i> habitat loss and movement impediment.

Nature of impact:	Negative
Extent and duration of impact:	Local and long term
Consequence of impact:	High
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	High
Degree to which the impact can be reversed:	Irreversible
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	High
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Low
Degree to which the impact can be mitigated:	Low
Proposed mitigation:	→ During the construction phase the construction area should be clearly demarcated and blocked off from the 'private open space' area to avoid damage and pollution. → Pre and post construction site preparation should include rehabilitation of the 'private open space' by removing current building rubble and litter from this area. → Long term maintenance of ecological integrity of the 'private open space' is critical. Therefore, measures should be put in place for constant removal of alien vegetation, cleanup of litter and prevention of illegal dumping. Clear legal responsibility for the maintenance of the space should be entrenched to be the responsibility of the homeowners association. → The fence traversing the ecological corridor should always be permeable to allow for movement of small sized animals e.g. small antelope, genets, mongoose between the nature reserve and wetland system. → Search and Rescue of chameleons and other slow-moving animals is feasible due to the presence of the adjacent nature reserve where they can be released. A search and rescue effort should be implemented before and during construction where animals that are found are released in the adjacent nature reserve. The necessary permission and permits should be attained before this is done. → Pets (especially domestic cats) should not be allowed to free-roam the 'private open space'.
Residual impacts:	Loss of all faunal species on the development footprint
Cumulative impact post mitigation:	High Loss of faunal connectivity on site as a result of development footprint
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative

POST-CONSTRUCTION PHASE	
Potential impact and risk:	1. Socioeconomic
Potential Impact	Access to employment for the community during the operational phase, Job creation, Provision of residential erven in response to provincial demand, investment in the area
Nature of impact:	Positive
Extent and duration of impact:	Local; long term
Consequence of impact or risk:	Improved livelihoods beneficiaries, influx of people to the area, investment in the area, spending in the area
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	Access to employment for the community during the operational phase, Job creation, Provision of residential erven in response to provincial demand, investment in the area
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High positive
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	N/A
Proposed mitigation:	-
Residual impacts:	Investment in the area, attraction to the area, spending in the area
Cumulative impact post mitigation:	Investment in the area, attraction to the area, spending in the area Access to employment for the community during the operational phase, Job creation, Provision of residential erven in response to provincial demand, investment in the area
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High positive
POST-CONSTRUCTION PHASE	
Potential impact and risk:	2. Visual Impact
Potential Impact	Typical Visual impacts associated with the operational phase of a residential dwelling or group of residential dwellings that may lead to changes in sense of place of the individual from what was there and to what has now changed.
Nature of impact:	Negative – changes in the visual aesthetics of the area during the operational phase. Positive- infill development within an urban area as opposed to the alienation of new land, contributing to more sustainable land use.
Extent and duration of impact:	Long term, local to regional

Consequence of impact or risk:	Risk – visual impact of operation within landscape and suburb
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	High
Indirect impacts:	Loss of sense of place due to the removal of the natural vegetation that is appealing to nature lovers
Cumulative impact prior to mitigation:	Short term impacts associated with changes of the built infrastructure.
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Low
Degree to which the impact can be mitigated:	High
Proposed mitigation:	→ Implement landscaping strategies to minimize the visual impact of construction and operational activities. → Incorporate green design principles into the development to enhance aesthetics and mitigate negative visual effects. → Communicate with the community to ensure understanding and acceptance of the changes in the visual character. → Consider the use of native vegetation in landscaping to maintain a natural feel and reduce visual disruptions.
Residual impacts:	None
Cumulative impact post mitigation:	Typical visual impacts associated with operational phase
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Low negative

POST-CONSTRUCTION PHASE

Potential impact and risk:	3. Ecological
Potential impact:	Loss of current moderate levels of ecological connectivity across the site (essentially only W-E connectivity is now available), and associated habitat fragmentation. Loss of ability for natural fires Loss of sensitive botanical areas and vegetation Reduction in natural habitat
Nature of impact:	Negative – ecological impacts Positive – infill development within urban area as opposed to alienation of new land
Extent and duration of impact:	Permanent, local to regional
Consequence of impact:	Loss of all available natural or partly natural faunal habitat on site. Loss of natural spaces, corridors and high ecological species.
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	High
Degree to which the impact can be reversed:	N/A

Indirect impacts:	Loss of moderate current ecological connectivity across the site and associated habitat fragmentation.
Cumulative impact prior to mitigation:	Loss of all natural spaces, corridors and vegetation on site.
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Very High
Degree to which the impact can be avoided:	Possible
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium
Proposed mitigation:	→ No erven should intrude significantly into the seasonal wetland portions of the site that support mostly habitat of High ecological sensitivity (as per Figure 4). This means that the following erven should be removed from any authorised layout: 1, 2, 7, 8, 10, 11, 12 and 13. The proposed access road (erf 14) should also be largely removed so that it does not cross the wetland and ecological corridor and can instead access erf 9 along the southern boundary. → No pipelines, cabling or infrastructure should be installed across the High sensitivity areas or wetlands. → Any boundary fencing used must be permeable to small animals at ground level. → The authorised erf and road boundaries should be surveyed and pegged out and fenced on site prior to any site development. → No areas of natural or partly natural vegetation should be disturbed outside the pegged/fenced out and authorised erven. No vehicular activity or dumping of material may take place outside the authorised erven or roads. → All alien invasive vegetation should be removed from within the natural portions of the project area, prior to any authorised development. Removal of the alien vegetation must be undertaken by a trained and licensed alien vegetation removal team and must be undertaken using methodology outlined in the Best Practise Guidelines (see Martens et al 2021). → The Homeowners Association (HoA, or similar) for the proposed development must ensure that all alien invasive vegetation (as per NEMBA legislation) is removed from the Public Open Space area on an annual basis by qualified contractors, using methodology as prescribed in Martens et al (2021; see below for reference). The HoA must ensure that there is adequate funding for this every year. → In order to try and safeguard the ecological integrity of the No Go wetland areas on Erven 1-8 (also shown in Figure 1) these areas that should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way. Landowners and the HoA must be made aware of these constraints both prior to and after purchase. Alien invasive plant species should be removed from these areas on an annual basis, as part of the management actions required for the adjacent Private Open Space.
Residual impacts	Loss of sensitive vegetation, open spaces, corridors

Cumulative impact post mitigation:	Loss of natural spaces, loss of ecological connectivity, corridors and vegetation
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	High negative
POST-CONSTRUCTION PHASE	
Potential impact and risk:	4. Wetland loss within the delineated UVBW
Potential impact:	Site clearance, infilling and compaction will result in alteration of the flow regime for the onsite wetland and even loss of the entire wetland. Pollutants may enter the onsite wetland via stormwater or sewage leaks (although highly unlikely).
Nature of impact:	Negative
Extent and duration of impact:	Local; permanent
Consequence of impact:	High loss of ecological infrastructure as well as aquatic species
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	Loss of High ecological sensitivity and hydrological connectivity
Cumulative impact prior to mitigation:	High
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium High, High, or Very-High)	High
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	N/A
Degree to which the impact can be mitigated:	N/A
Proposed mitigation:	→ The significance of this impact can be largely mitigated by demarcating the UVBW as No-Go area during construction. → Bunded, impervious areas that are more than 15 m away from the UVBW must be designated by an Environmental Control Officer for temporary toilets, vehicle parking/servicing areas, and for pouring and mixing of concrete/cement, paint, and chemicals. → The significance of this impact can be largely mitigated by ensuring that SW generated onsite flows into the wetland through an appropriately designed broad, vegetated earth swale (to avoid erosion). → If possible, conduct any rehabilitation activities during summer months (November to March). It is recommended that a suitably qualified aquatic specialist compiles detailed method statements once the final layout of the proposed project has been formalized. → Additionally, a suitable Rehabilitation and Management Plan should be drafted for the wetland area onsite.
Residual impacts	Loss of wetland and ecological connectivity as well as the hydrological connectivity.

Cumulative impact post mitigation:	Loss of wetland and ecological connectivity as well as the hydrological connectivity.
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	High Negative
POST-CONSTRUCTION PHASE	
Potential impact and risk:	5. Faunal impacts
Potential impact:	- Infringement of development footprint on ESA2 corridor. - Cape dwarf chameleon, <i>Bradypodion pumilum</i> habitat loss and movement impediment.
Nature of impact:	Negative
Extent and duration of impact:	Local and long erm
Consequence of impact:	High
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	High
Degree to which the impact can be reversed:	Irreversible
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	High
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	High
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Low
Degree to which the impact can be mitigated:	Low
Proposed mitigation:	Amending layout
Residual impacts:	Loss of all faunal species on the development footprint
Cumulative impact post mitigation:	High Loss of faunal connectivity on site as a result of development footprint
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
DECOMMISSIONING AND CLOSURE PHASE	
Potential impact and risk:	N/A
Nature of impact:	-
Extent and duration of impact:	-
Consequence of impact or risk:	-
Probability of occurrence:	-
Degree to which the impact may cause irreplaceable loss of resources:	-
Degree to which the impact can be reversed:	-
Indirect impacts:	-
Cumulative impact prior to mitigation:	-

Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	-
Degree to which the impact can be avoided:	-
Degree to which the impact can be managed:	-
Degree to which the impact can be mitigated:	-
Proposed mitigation:	-
Residual impacts:	-
Cumulative impact post mitigation:	-
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	-

ALTERNATIVE 3

PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	1. Socioeconomic impacts
Potential impact	Job creation during the development /construction phase of the Erven
Nature of impact:	Positive
Extent and duration of impact:	local; short-term
Consequence of impact or risk:	Improved livelihoods of the community
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	Job creation for local community
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High Positive
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	1. Ensure labour force is sourced locally as far as possible. 2. A gender balance to be considered during employment.
Residual impacts:	1. Improved livelihoods 2. Improvement of local economy, skills transfer, investment in the area
Cumulative impact post mitigation:	Job creation and skills transfer to local community
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High positive
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	2. Dust
Potential impact	Dust generated from site clearing and site preparation
Nature of impact:	Negative

Extent and duration of impact:	Local, short term
Consequence of impact or risk:	Visual impacts Nuisance for residents adjacent to the site
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	Low
Degree to which the impact can be reversed:	High
Indirect impacts:	Potential for reduced visibility, temporary visual impacts to the general area
Cumulative impact prior to mitigation:	Dust may be generated as a result of earthmoving activities required for construction and development
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
Degree to which the impact can be avoided:	High
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	→ Maintain ground cover for as long as possible to reduce the total surface area exposed to wind. Do not clear entire plots and rather clear building sites only → Ensure vehicle speed limits on site are kept to a minimum. → Delivery vehicles to keep loads covered. → Cover fine material stockpiles. → Wet dry and dusty surfaces using non-potable water. → Staff to wear correct PPE if dust is generated for long periods. → Road surfaces to be swept and kept clean of sand and fine materials
Residual impacts:	None
Cumulative impact post mitigation:	Dust generated during construction; mitigation successful
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Very-Low Negative

PLANNING, DESIGN AND DEVELOPMENT PHASE

Potential impact and risk:	3. Noise
Potential impact	Noise generated from vehicles and machinery during the construction phase.
Nature of impact:	Negative
Extent and duration of impact:	Local, short term
Consequence of impact or risk:	Noise disturbance to transient receptors, i.e. motorists, pedestrians, residents.
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	No resources will be impacted.
Degree to which the impact can be reversed:	High
Indirect impacts:	None
Cumulative impact prior to mitigation:	Noise generated from construction works
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative

Degree to which the impact can be avoided:	Medium – High
Degree to which the impact can be managed:	Medium – High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	→ Limit noise levels (e.g. install and maintain silencers on machinery). → Provide protective wear for workers i.e. ear plugs. → Ensure that construction vehicles and machinery are maintained regularly to reduce noise generation. → Restrict construction to normal working hours
Residual impacts:	None
Cumulative impact post mitigation:	Typical noise impacts associated with a construction site
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Low Negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	4. Visual
Potential Impact	Visual impacts of construction site and construction activities.
Nature of impact:	Negative
Extent and duration of impact:	Local, short term
Consequence of impact or risk:	Reduce aesthetic value of the site and surrounds
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	High
Indirect impacts:	None
Cumulative impact prior to mitigation:	Short term visual impacts associated with construction
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	→ Good housekeeping of construction site and working areas. → Screen the visual elements of the site camp with netting. → Locate the site camp in a transformed area. → Site officer to walk the site on a daily basis to check for visual impacts and general site aesthetics, particularly prior to weekends and holidays → Officer to ensure that waste and batching areas are correctly screened and secured to prevent spread by wind, rain or animals.
Residual impacts:	None
Cumulative impact post mitigation:	Typical visual impacts associated with a construction site
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Low Negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	

Potential impact and risk:	5. Ecological Impact
Potential impact:	During the removal of vegetation for the proposed subdivision and development would be permanent loss of all or most of the existing natural and partly natural vegetation and faunal habitat in the development footprints (most of it gazetted as Endangered vegetation type). The proposed residential erven with the new alternative layout now exclude most of the High sensitivity areas (as required in my first bullet point of mitigation), and only about 500m² of high sensitivity habitat will now be lost.
Nature of impact:	Negative
Extent and duration of impact:	Local, Regional; Permanent
Consequence of impact:	Vegetation loss, species loss, diversity loss, connectivity loss Exposure of soil and degradation thereof
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	Medium
Degree to which the impact can be reversed:	Low
Indirect impacts:	Continued loss of Hangklip Sand Fynbos (CR)
Cumulative impact prior to mitigation:	Loss of natural vegetation and faunal habitat and threatened plant species to ongoing agriculture, urban development and alien plant invasion
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	High
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium
Proposed mitigation:	→ No erven should intrude significantly into the seasonal wetland portions of the site that support mostly habitat of High ecological sensitivity. This means that the following erven should be removed from any authorised layout: 1, 2, 7, 8, 10, 11, 12 and 13. The proposed access road (erf 14) should also be largely removed so that it does not cross the wetland and ecological corridor and can instead access erf 9 along the southern boundary. The proposed new layout (Alternative 3) is amended and changed according to the above mitigation measures and thus revolved into an “acceptable” ecological impact rating. → No pipelines, cabling or infrastructure should be installed across the High sensitivity areas or wetlands. → Any boundary fencing used must be permeable to small animals at ground level. → The authorised erf and road boundaries should be surveyed and pegged out and fenced on site prior to any site development. → No areas of natural or partly natural vegetation should be disturbed outside the pegged/fenced out and authorised

	erven. No vehicular activity or dumping of material may take place outside the authorised erven or roads. → All alien invasive vegetation should be removed from within the natural portions of the project area, prior to any authorised development. Removal of the alien vegetation must be undertaken by a trained and licensed alien vegetation removal team and must be undertaken using methodology outlined in the Best Practise Guidelines (see Martens <i>et al</i> 2021). → The Homeowners Association (HoA, or similar) for the proposed development must ensure that all alien invasive vegetation (as per NEMBA legislation) is removed from the Public Open Space area on an annual basis by qualified contractors, using methodology as prescribed in Martens <i>et al</i> (2021; see below for reference). The HoA must ensure that there is adequate funding for this every year. → In order to try and safeguard the ecological integrity of the No Go wetland areas on Erven 1-8 (also shown in Figure 1) these areas that should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way. Landowners and the HoA must be made aware of these constraints both prior to and after purchase. Alien invasive plant species should be removed from these areas on an annual basis, as part of the management actions required for the adjacent Private Open Space.	
Residual impacts	Loss of high sensitivity vegetation	
Cumulative impact post mitigation:	Loss of high sensitivity vegetation	
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low (-)	Medium (-)
PLANNING, DESIGN AND DEVELOPMENT PHASE		
Potential impact and risk:	1. Wetland loss within the delineated UVBW	
Potential impact:	Site clearance, infilling and compaction will result in alteration of the flow regime for the onsite wetland and even loss of the entire wetland. Pollutants may enter the onsite wetland via stormwater or sewage leaks (although highly unlikely).	
Nature of impact:	Negative	
Extent and duration of impact:	Local; permanent	
Consequence of impact:	loss of ecological infrastructure as well as aquatic species.	
Probability of occurrence:	Definite	
Degree to which the impact may cause irreplaceable loss of resources:	Low	
Degree to which the impact can be reversed:	Low	
Indirect impacts:	Loss of High ecological sensitivity and hydrological connectivity	
Cumulative impact prior to mitigation:	Medium	
Significance rating of impact prior to mitigation	Medium High	

(e.g. Low, Medium, Medium-High, High, or Very-High)	
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium
Proposed mitigation:	→ An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist.
Residual impacts	Loss of wetland and ecological connectivity as well as the hydrological connectivity.
Cumulative impact post mitigation:	Loss of wetland and ecological connectivity as well as the hydrological connectivity.
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Medium negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	2. Disturbance of Wetland Habitat
Potential impact:	Disturbance of wetland habitat within the UVBW may occur due to the proximity of the proposed residential development, including but not limited to vegetation clearing, infilling, and construction of the housing; as well as the upgrade of the existing sewer pipeline.
Nature of impact:	Negative
Extent and duration of impact:	Local; Short-term
Consequence of impact:	Disturbance to aquatic habitat
Probability of occurrence:	Possible
Degree to which the impact may cause irreplaceable loss of resources:	Low
Degree to which the impact can be reversed:	Medium
Indirect impacts:	Reduction to aquatic biodiversity
Cumulative impact prior to mitigation:	Medium
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Low-Medium
Degree to which the impact can be managed:	Medium – High
Degree to which the impact can be mitigated:	Medium High
Proposed mitigation:	→ Designate the UVB wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline). Clearly demarcate the construction footprint (including construction camp, access roads, stockpile areas and working servitudes) with orange hazard tape, fencing or similar prior to the commencement of any activity, and strictly prohibit the movement of construction vehicles and personnel outside of the demarcated areas. → Locate site camps, laydown areas, stockpile areas, construction material, equipment storage areas, vehicle parking areas, bunded vehicle servicing areas and re-fuelling areas in designated areas of already hardened surface or

	disturbed areas located outside of the No Go area. These areas should preferably be located on level ground in a previously disturbed area of vegetation approved by the Environmental Control Officer (ECO). Cut and fill must be avoided where possible during the set-up of the construction site camp. → Demarcation of the construction footprint/working servitude must be signed off by an ECO (or similar). Demarcation should not be removed until construction is complete, and rehabilitation (if applicable) has taken place. → Limit access into the construction footprint to existing access roads. → Prohibit the dumping of excavated material, building materials or removed vegetation within the No Go area. Building material must be stored at the designated storage area located outside of the no-go area. Spoil material must be appropriately disposed of at a registered waste disposal facility. → Undisturbed topsoil and subsoils removed from the construction footprint must be stored separately at the designated stockpile area for future rehabilitation. → Vegetation clearance should be restricted to the relevant development components and indigenous vegetation cover should be maintained as far as practically possible. → Vegetation which is considered suitable for rehabilitation activities after construction (such as indigenous grasses and other herbaceous species) should be carefully removed from the construction footprint and stored at an appropriate facility for use in later rehabilitation activities. → Clear and remove any rubble or litter that may have been accidentally deposited into the no-go area because of construction activities and dispose of at an appropriate registered facility. → An ECO must inspect the construction footprint on a weekly basis and must take immediate measures to address unforeseen disturbances to the wetland. Any disturbed / compacted areas falling outside of the demarcated construction footprint must be immediately rehabilitated. Depending on the extent of damage the method of rehabilitation may require input from an aquatic specialist / suitably qualified contractor. → Once construction has been completed, orange hazard fences as well as all construction waste, rubble, and equipment must be removed from the construction footprint. → In line with the NEMBA, all AIPS listed under the amended AIPS Lists (DEFF: GN1003, 2020) must either be removed or controlled on land under the management of the proponent. → An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist. Rehabilitation must take place as soon as possible after construction is completed, and monitoring of rehabilitated areas must be undertaken. A suitably qualified professional must supervise the rehabilitation and monitoring activities.
Residual impacts	Possible decline in aquatic fauna.

Cumulative impact post mitigation:	Low – restoration of the aquatic habitat through rehabilitation of the wetland area on site.
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low (-)
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	3. Altered flow regime
Potential impact:	Site clearance, infilling, and compaction will result in alteration of the flow regime of wetland area on the site. Hardened catchment area would result in increased stormwater runoff, velocity and increased flood peaks within the wetland and would also likely result in sedimentation and erosion.
Nature of impact:	Negative
Extent and duration of impact:	Local; Short-term
Consequence of impact:	Disruption of wetland hydrology, increased erosion and sedimentation, degradation of aquatic habitat
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	Medium
Degree to which the impact can be reversed:	Medium
Indirect impacts:	Altered sediment transport dynamics, loss of wetland function, downstream ecological impacts
Cumulative impact prior to mitigation:	Medium – High
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium – High
Proposed mitigation:	→ Designate the wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline). → The site manager / ECO must check the No Go area for pollution/spills, erosion damage and sedimentation weekly and after every heavy rainfall event. Should pollution, erosion or sedimentation be noted, immediate corrective measures must be undertaken. → Fuel, chemicals, and other hazardous substances should preferably be stored offsite, or as far away as possible from the no-go area. These substances must be stored in suitable secure weather-proof containers with impermeable and bunded floors to limit pilferage, spillage into the environment, flooding, or storm damage. → Inspect all storage facilities, vehicles, and machinery daily for the early detection of deterioration or leaks and strictly prohibit the use of any vehicles or machinery from which leakage has been detected. → Mixing and transferring of chemicals or hazardous substances must take place outside of the No Go area, and must take place on drip trays, shutter boards or other impermeable surfaces.

	→ Drip trays must be utilised at all fuel dispensing areas; and during the maintenance of existing sewer flow as possible. → Vehicles and machinery should preferably be cleaned off site. Should cleaning be required on site it must only take place within designated areas outside of the No Go area and should only occur on bunded areas with a water/oil/grease separator. → Dispose of used oils, wash water from cement and other pollutants at an appropriate licensed landfill site. → Avoid the use of infill material or construction material with pollution / leaching potential. Where possible, in situ earthen materials must be used during construction to reduce the risk of leachate from imported materials contaminating the wetland area. → Concrete should preferably be imported as “ready-mix” concrete from a local supplier. Should onsite concrete mixing be required it must not be done on exposed soils. Concrete must be mixed on an impermeable surface in an area of low environmental sensitivity identified by the ECO outside of the no-go area. Surplus or waste concrete must be sent back to the supplier who will dispose of it. → Construct temporary bunds around areas where cement is to be cast in situ. → Dispose of concrete and cement-related mortars in an environmental sensitive manner (can be toxic to aquatic life). Disposal of any of these waste materials into the No Go area is strictly prohibited. → Washout must not be discharged into the no-go area. A washout area should be designated, and wash water should be treated on-site. → Clean up any spillages immediately with the use of a chemical spill kit and dispose of contaminated material at an appropriately registered facility. → Provide portable toilets where work is being undertaken (1 toilet per 10 workers). These toilets must be located within an area designated by the ECO outside of the no-go area and should preferably be located on level ground. Portable toilets must be regularly serviced and maintained. → Provide an adequate number of bins on site and encourage construction personnel to dispose of their waste responsibly. → Waste generated by construction personnel must be removed from the site and disposed of at a registered waste disposal facility on a weekly basis.
Residual impacts	Altered runoff characteristics, potential for minor ongoing erosion if vegetation fails to establish
Cumulative impact post mitigation:	Low – altered runoff characteristics may occur during the flooding event. However, the impact will be managed through proposed mitigation measures.
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low (-)

PLANNING, DESIGN AND DEVELOPMENT PHASE		
Potential impact and risk:	4. Faunal impact	
Potential impact:	Cape dwarf chameleon, <i>Bradypodion pumilum</i> habitat loss and movement impediment	
Nature of impact:	Negative	
Extent and duration of impact:	Local; long-term	
Consequence of impact:	Medium	
Probability of occurrence:	Definite	
Degree to which the impact may cause irreplaceable loss of resources:	Medium	
Degree to which the impact can be reversed:	Irreversible	
Indirect impacts:	N/A	
Cumulative impact prior to mitigation:	Medium - Disturbance and loss of faunal habitat	
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium	
Degree to which the impact can be avoided:	Medium	
Degree to which the impact can be managed:	Medium	
Degree to which the impact can be mitigated:	High	
Proposed mitigation:	→ The fence traversing the ecological corridor should be permeable to allow for movement of small sized animals e.g. otters, small antelope between the nature reserve and wetland system. → Search and Rescue of chameleons and other slow-moving animals is feasible due to the presence of the adjacent nature reserve. A search and rescue effort should be implemented before and during construction where animals that are found are released in the adjacent nature reserve. → Long term maintenance of ecological integrity of the 'private open space' is critical. Therefore, measures should be put in place for constant removal of alien vegetation, cleanup of litter and prevention of illegal dumping. → Pre and post construction site preparation should include rehabilitation of the 'private open space' by removing current building rubble and litter from this area.	
Residual impacts	Medium	
Cumulative impact post mitigation:	Medium - It is likely that some of their habitat will be lost on the development footprint and the disturbance during construction phase	
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low (-)	Medium (-)
POST CONSTRUCTION		
Potential impact and risk:	1. Socioeconomic	
Potential Impact	Access to employment for the community during the operational phase, Job creation, Provision of residential erven in response to provincial demand, investment in the area	

Nature of impact:	Positive
Extent and duration of impact:	Local; long term
Consequence of impact or risk:	Improved livelihoods beneficiaries, influx of people to the area, investment in the area, spending in the area
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	Access to employment for the community during the operational phase, Job creation, Provision of residential erven in response to provincial demand, investment in the area
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High positive
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	N/A
Proposed mitigation:	-
Residual impacts:	Investment in the area, attraction to the area, spending in the area
Cumulative impact post mitigation:	Investment in the area, attraction to the area, spending in the area Access to employment for the community during the operational phase, Job creation, Provision of residential erven in response to provincial demand, investment in the area
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High positive

POST CONSTRUCTION

Potential impact and risk:	2. Visual Impact
Potential Impact	Typical Visual impacts associated with the operational phase of a residential dwelling or group of residential dwellings that may lead to changes in sense of place of the individual from what was there and to what has now changed.
Nature of impact:	Negative – changes in the visual aesthetics of the area during the operational phase. Positive- infill development within an urban area as opposed to the alienation of new land, contributing to more sustainable land use.
Extent and duration of impact:	Long term, local to regional
Consequence of impact or risk:	Risk – visual impact of operation within landscape and suburb
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	High
Indirect impacts:	Loss of sense of place due to the removal of the natural vegetation that is appealing to nature lovers
Cumulative impact prior to mitigation:	Short term impacts associated with changes of the built infrastructure.
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Low
Degree to which the impact can be mitigated:	High

Proposed mitigation:	- Implement landscaping strategies to minimize the visual impact of construction and operational activities. - Incorporate green design principles into the development to enhance aesthetics and mitigate negative visual effects. - Communicate with the community to ensure understanding and acceptance of the changes in the visual character. - Consider the use of native vegetation in landscaping to maintain a natural feel and reduce visual disruptions.
Residual impacts:	None
Cumulative impact post mitigation:	Typical visual impacts associated with operational phase
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Low negative
POST CONSTRUCTION	
Potential impact and risk:	3. Ecological
Potential impact:	Loss of current moderate levels of ecological connectivity across the site (essentially only W-E connectivity is now available), and associated habitat fragmentation. Loss of ability for natural fires Loss of sensitive botanical areas and vegetation Reduction in natural habitat
Nature of impact:	Negative – ecological impacts Positive – infill development within urban area as opposed to alienation of new land
Extent and duration of impact:	Permanent, local to regional
Consequence of impact:	Loss of all available natural or partly natural faunal habitat on site. Loss of natural spaces, corridors and high ecological species.
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	High
Degree to which the impact can be reversed:	N/A
Indirect impacts:	Loss of moderate current ecological connectivity across the site and associated habitat fragmentation.
Cumulative impact prior to mitigation:	Loss of all natural spaces, corridors and vegetation on site.
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium
Proposed mitigation:	- No areas of natural or partly natural vegetation should be disturbed outside the pegged/fenced out and authorised erven. No vehicular activity or dumping of material may take place outside the authorised erven or roads. - All alien invasive vegetation should be removed from within the natural portions of the project area, prior to any authorised development. Removal of the alien vegetation

	must be undertaken by a trained and licensed alien vegetation removal team and must be undertaken using methodology outlined in the Best Practise Guidelines (see Martens et al 2021). - The Homeowners Association (HoA, or similar) for the proposed development must ensure that all alien invasive vegetation (as per NEMBA legislation) is removed from the Public Open Space area on an annual basis by qualified contractors, using methodology as prescribed in Martens et al (2021; see below for reference). The HoA must ensure that there is adequate funding for this every year. - In order to try and safeguard the ecological integrity of the No Go wetland areas on Erven 1-8 (also shown in Figure 1) these areas that should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way. Landowners and the HoA must be made aware of these constraints both prior to and after purchase. Alien invasive plant species should be removed from these areas on an annual basis, as part of the management actions required for the adjacent Private Open Space.	
Residual impacts	Loss of sensitive vegetation, open spaces, corridors	
Cumulative impact post mitigation:	Loss of natural spaces, loss of ecological connectivity, corridors and vegetation	
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	Low (-)	Medium (-)
POST CONSTRUCTION		
Potential impact and risk:	4. Habitat Disturbance	
Potential impact:	Disturbance of wetland habitat within the UVBW may occur due to the proximity of the proposed residential development, including but not limited to vegetation clearing, infilling, and construction of the housing; as well as the upgrade of the existing sewer pipeline.	
Nature of impact:	Negative	
Extent and duration of impact:	Local; short-term	
Consequence of impact:	Continued loss of wetland habitat species due to footprint.	
Probability of occurrence:	Likely	
Degree to which the impact may cause irreplaceable loss of resources:	Low	
Degree to which the impact can be reversed:	Low-Medium	
Indirect impacts:	Reduction in wetland habitat.	
Cumulative impact prior to mitigation:	High	
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Low	
Degree to which the impact can be avoided:	Medium	
Degree to which the impact can be managed:	Medium	
Degree to which the impact can be mitigated:	Medium – High	

Proposed mitigation:	→ Prohibit littering and dumping within the wetland area. Clear and remove any rubble or litter that may have been accidentally deposited into the wetland and dispose of at an appropriate registered facility. Monitoring of litter/dumping within the wetland must be managed by a Homeowners Association (HoA). → In line with the NEMBA, all AIPS listed under the amended AIPS Lists (DEFF: GN1003, 2020) must either be removed or controlled on land under the management of the proponent. → Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings).
Residual impacts	Wetland d ecosystem recovery due to introduction of indigenous wetland species during rehabilitation.
Cumulative impact post mitigation:	Low-
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low negative
POST CONSTRUCTION	
Potential impact and risk:	5. Altered flow regime
Potential impact:	Site clearance, infilling and compaction will result in alteration of the flow regime for the UVBW. Site clearance, infilling, and compaction will result in alteration of the flow regime of wetland area. Hardened catchment area would result in increased stormwater runoff, velocity and increased flood peaks within the wetland and would also likely result in sedimentation and erosion.
Nature of impact:	Negative
Extent and duration of impact:	Local; short-term
Consequence of impact:	Accumulation of sediment material and sand to stormwater culverts and permeable swales due to stormwater runoff during flooding event contributing to altered hydrological flow in some areas.
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	Low
Degree to which the impact can be reversed:	Medium
Indirect impacts:	→ Disruption of natural drainage patterns → Increased maintenance requirements for stormwater infrastructure → Possible degradation of wetland habitat integrity → Risk of downstream flooding impacts

Cumulative impact prior to mitigation:	Medium
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium
Proposed mitigation:	→ Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1 of the Aquatic Biodiversity Assessment) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings). → Runoff from the proposed development must not increase from the pre-development to the post-development scenario. → The status quo in terms of hydrological connection from Erf 1486 to the downstream system must be maintained / should not be impacted because of the proposed development. → Discharge stormwater from rooftops into rain harvesting tanks. This will limit the volumes of stormwater runoff that will reach the wetland area. Where possible, water collected in rain harvesting tanks can be utilized for flushing of toilets, washing etc. → Stormwater runoff should preferably be discharged as diffuse flow into well vegetated areas outside of the wetland. → Energy dissipaters / erosion protection measures (such as lining with stones, grass, reno-mattresses, or gabions) must be constructed where stormwater is released to reduce the runoff velocity and therefore erosion. → Sheet runoff from hardened surfaces must be intercepted and the treatment and infiltration of runoff must be promoted. → Sediment traps should be incorporated into stormwater drains / swales upstream of any discharge points. → Monitor the wetland area for erosion and sedimentation after heavy rainfall events. Any erosion noted must be immediately addressed. Rehabilitation measures may include the removal of accumulated sediment by hand, filling of erosion gullies and rills, the stabilisation of gullies with silt fences, riprap, and the revegetation of stabilised areas. → Stormwater systems will require ongoing maintenance. Any build-up of silt or debris within stormwater drains or swales will need to be cleared to ensure the continued functioning of the systems. → Any damage to stormwater infrastructure, and any flaws identified in the functionality of stormwater infrastructure, must be rectified immediately. → Appropriately designed raft foundations for residential dwellings may significantly reduce the impact on subsurface flow and therefore reduce risk. → Rainwater harvesting schemes may reduce runoff intensity and thereby mitigate the impact of catchment hardening.
Residual impacts	Possible minor alterations to local hydrology; some stormwater infrastructure may require long-term monitoring and adaptation
Cumulative impact post mitigation:	Low

Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low (-)	Medium (-)
POST CONSTRUCTION		
Potential impact and risk:	6. Water Quality impairment	
Potential impact:	Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1 of the Aquatic Biodiversity Assessment) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings). Pollutants may enter the wetland via stormwater or sewage leaks (although highly unlikely). However, with the inclusion of stormwater design measures which allow for the infiltration and treatment of stormwater this impact can be greatly reduced	
Nature of impact:	Negative	
Extent and duration of impact:	Local; short-term	
Consequence of impact:	Degradation of water quality in the UVBW wetland system; increased nutrient loads may promote algal growth, reduce dissolved oxygen levels, and harm aquatic biota.	
Probability of occurrence:	Likely	
Degree to which the impact may cause irreplaceable loss of resources:	Low	
Degree to which the impact can be reversed:	Medium	
Indirect impacts:	• Reduction in aquatic species diversity • Bioaccumulation of pollutants in wetland fauna • Loss of ecosystem services such as water purification and nutrient cycling • Impacts on downstream water users and aquatic habitats	
Cumulative impact prior to mitigation:	Medium (when considered in combination with other regional developments and climate change-related runoff changes)	
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium	
Degree to which the impact can be avoided:	Medium	
Degree to which the impact can be managed:	Medium	
Degree to which the impact can be mitigated:	Medium	
Proposed mitigation:	→ Design a SWMP which will allow for the infiltration and treatment of stormwater. All stormwaters must receive basic filtering and treatment prior to its release. → Incorporate measures into the stormwater design to trap solid waste, debris and sediment carried by stormwater. Measures may include the use of curb inlet drain grates and debris baskets/bags. → Stormwater generated from areas with a higher risk of contamination such as parking areas and roads (as applicable) must receive basic filtering and treatment prior to its release into surrounding areas. → Stormwater systems must be monitored and maintained into perpetuity and collections of debris and solid waste removed from grates and baskets. The developer must confirm who will	

	be responsible for this monitoring and maintenance as well as their roles (likely HoA). → Operational phase mitigation implemented during the design/construction phase: ○ Construct sewage pipelines in accordance with the relevant SANS / SABS specifications. ○ Design the pipelines to accommodate the operating and surge pressures. ○ Provide surge protection e.g. air valves. ○ Allow for scour valves along pipelines to ensure sewage pipelines can be emptied in a controlled manner if required. ○ Allow for surcharge containment and emergency storage of 2 hours of peak flow at manholes located within areas upslope of the wetland. Containment/emergency storage may include a concrete box or earthen bund surrounding the manholes. The backup storage capacity of manholes may also be improved by raising the manholes by one meter. → The sewage system must be monitored and maintained into perpetuity. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles. → The wetland area must be regularly inspected for waste. Any waste or litter noted must be immediately removed and disposed of at a registered waste disposal facility. The developer must confirm who will be responsible for this monitoring of the wetland area (HoA).
Residual impacts	Minimal if infrastructure and mitigation are effectively implemented and maintained.
Cumulative impact post mitigation:	Low
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low negative
POST CONSTRUCTION	
Potential impact and risk:	7. Faunal impact
Potential impact:	• Infringement on ESA2 corridor which will influence connectivity facilitating animal movement. • Cape dwarf chameleon, <i>Bradypodion pumilum</i> habitat loss and movement impediment
Nature of impact:	Negative
Extent and duration of impact:	Local; long-term
Consequence of impact:	Medium
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	Medium-Low
Degree to which the impact can be reversed:	Irreversible
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	Disturbance and loss of faunal habitat

Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium	
Degree to which the impact can be avoided:	Medium- Low	
Degree to which the impact can be managed:	Medium- Low	
Degree to which the impact can be mitigated:	Low	
Proposed mitigation:	→ The fence traversing the ecological corridor should be permeable to allow for movement of small sized animals e.g. otters, small antelope between the nature reserve and wetland system. → Search and Rescue of chameleons and other slow-moving animals is feasible due to the presence of the adjacent nature reserve. A search and rescue effort should be implemented before and during construction where animals that are found are released in the adjacent nature reserve. → Long term maintenance of ecological integrity of the 'private open space' is critical. Therefore, measures should be put in place for constant removal of alien vegetation, cleanup of litter and prevention of illegal dumping. → Pre and post construction site preparation should include rehabilitation of the 'private open space' by removing current building rubble and litter from this area. → Pets (especially domestic cats) should not be allowed to free-roam the 'private open space'.	
Residual impacts	Medium- Low	
Cumulative impact post mitigation:	It is likely that some of their habitat will be lost on the development footprint and the disturbance during construction phase	
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low (-)	Medium (-)
DECOMMISSIONING AND CLOSURE PHASE		
Potential impact and risk:	N/A	
Nature of impact:	-	
Extent and duration of impact:	-	
Consequence of impact or risk:	-	
Probability of occurrence:	-	
Degree to which the impact may cause irreplaceable loss of resources:	-	
Degree to which the impact can be reversed:	-	
Indirect impacts:	-	
Cumulative impact prior to mitigation:		
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	-	
Degree to which the impact can be avoided:	--	
Degree to which the impact can be managed:	-	
Degree to which the impact can be mitigated:	-	
Proposed mitigation:	-	
Residual impacts:	-	
Cumulative impact post mitigation:	-	
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	-	

ALTERNATIVE 4 (PREFERRED)

PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	1. Socioeconomic impacts
Potential impact	Job creation during the development /construction phase of the Erven
Nature of impact:	Positive
Extent and duration of impact:	local; short-term
Consequence of impact or risk:	Improved livelihoods of the community
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	Job creation for local community
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High Positive
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	1. Ensure labour force is sourced locally as far as possible. 2. A gender balance to be considered during employment.
Residual impacts:	1. Improved livelihoods 2. Improvement of local economy, skills transfer, investment in the area
Cumulative impact post mitigation:	Job creation and skills transfer to local community
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High positive
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	2. Dust
Potential impact	Dust generated from site clearing and site preparation
Nature of impact:	Negative
Extent and duration of impact:	Local, short term
Consequence of impact or risk:	Visual impacts Nuisance for residents adjacent to the site
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	Low
Degree to which the impact can be reversed:	High
Indirect impacts:	Potential for reduced visibility, temporary visual impacts to the general area
Cumulative impact prior to mitigation:	Dust may be generated as a result of earthmoving activities required for construction and development

Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
Degree to which the impact can be avoided:	High
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	→ Maintain ground cover for as long as possible to reduce the total surface area exposed to wind. Do not clear entire plots and rather clear building sites only → Ensure vehicle speed limits on site are kept to a minimum. → Delivery vehicles to keep loads covered. → Cover fine material stockpiles. → Wet dry and dusty surfaces using non-potable water. → Staff to wear correct PPE if dust is generated for long periods. → Road surfaces to be swept and kept clean of sand and fine materials
Residual impacts:	None
Cumulative impact post mitigation:	Dust generated during construction; mitigation successful
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Very-Low Negative

PLANNING, DESIGN AND DEVELOPMENT PHASE

Potential impact and risk:	3. Noise
Potential impact	Noise generated from vehicles and machinery during the construction phase.
Nature of impact:	Negative
Extent and duration of impact:	Local, short term
Consequence of impact or risk:	Noise disturbance to transient receptors, i.e. motorists, pedestrians, residents.
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	No resources will be impacted.
Degree to which the impact can be reversed:	High
Indirect impacts:	None
Cumulative impact prior to mitigation:	Noise generated from construction works
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
Degree to which the impact can be avoided:	Medium – High
Degree to which the impact can be managed:	Medium – High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	→ Limit noise levels (e.g. install and maintain silencers on machinery). → Provide protective wear for workers i.e. ear plugs. → Ensure that construction vehicles and machinery are maintained regularly to reduce noise generation. → Restrict construction to normal working hours
Residual impacts:	None

Cumulative impact post mitigation:	Typical noise impacts associated with a construction site
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Low Negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	4. Visual
Potential Impact	Visual impacts of construction site and construction activities.
Nature of impact:	Negative
Extent and duration of impact:	Local, short term
Consequence of impact or risk:	Reduce aesthetic value of the site and surrounds
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	High
Indirect impacts:	None
Cumulative impact prior to mitigation:	Short term visual impacts associated with construction
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	→ Good housekeeping of construction site and working areas. → Screen the visual elements of the site camp with netting. → Locate the site camp in a transformed area. → Site officer to walk the site on a daily basis to check for visual impacts and general site aesthetics, particularly prior to weekends and holidays → Officer to ensure that waste and batching areas are correctly screened and secured to prevent spread by wind, rain or animals.
Residual impacts:	None
Cumulative impact post mitigation:	Typical visual impacts associated with a construction site
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Low Negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	5. Ecological Impact
Potential impact:	During the removal of vegetation for the proposed subdivision and development would be permanent loss of all or most of the existing natural and partly natural vegetation and faunal habitat in the development footprints (most of it gazetted as Endangered vegetation type). The proposed residential erven with the new alternative layout now exclude most of the High sensitivity areas (as required in my first bullet point of mitigation), and only about 500m² of high sensitivity habitat will now be lost.
Nature of impact:	Negative

Extent and duration of impact:	Local, Regional; Permanent
Consequence of impact:	Vegetation loss, species loss, diversity loss, connectivity loss Exposure of soil and degradation thereof
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	Medium
Degree to which the impact can be reversed:	Low
Indirect impacts:	Continued loss of Hangklip Sand Fynbos (CR)
Cumulative impact prior to mitigation:	Loss of natural vegetation and faunal habitat and threatened plant species to ongoing agriculture, urban development and alien plant invasion
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	High
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium
Proposed mitigation:	→ No erven should intrude significantly into the seasonal wetland portions of the site that support mostly habitat of High ecological sensitivity. The proposed new layout (Alternative 4) is amended and changed according to the above mitigation measures and thus revolved into an “acceptable” ecological impact rating. → No pipelines, cabling or infrastructure should be installed across the High sensitivity areas or wetlands. → Any boundary fencing used must be permeable to small animals at ground level. → The authorised erf and road boundaries should be surveyed and pegged out and fenced on site prior to any site development. → No areas of natural or partly natural vegetation should be disturbed outside the pegged/fenced out and authorised erven. No vehicular activity or dumping of material may take place outside the authorised erven or roads. → All alien invasive vegetation should be removed from within the natural portions of the project area, prior to any authorised development. Removal of the alien vegetation must be undertaken by a trained and licensed alien vegetation removal team and must be undertaken using methodology outlined in the Best Practise Guidelines (see Martens <i>et al</i> 2021). → The Homeowners Association (HoA, or similar) for the proposed development must ensure that all alien invasive vegetation (as per NEMBA legislation) is removed from the Public Open Space area on an annual basis by qualified contractors, using methodology as prescribed in Martens <i>et al</i> (2021; see below for reference). The HoA must ensure that there is adequate funding for this every year.

	→ Areas outside the designated road and residential erf boundaries should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way. Landowners and the HoA must be made aware of these constraints both prior to and after purchase.
Residual impacts	Loss of high sensitivity vegetation
Cumulative impact post mitigation:	Loss of high sensitivity vegetation
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low - Medium (-)
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	5. Wetland loss within the delineated UVBW
Potential impact:	Site clearance, infilling and compaction will result in alteration of the flow regime for the onsite wetland and even loss of the entire wetland. Pollutants may enter the onsite wetland via stormwater or sewage leaks (although highly unlikely).
Nature of impact:	Negative
Extent and duration of impact:	Local; permanent
Consequence of impact:	loss of ecological infrastructure as well as aquatic species.
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	Low
Degree to which the impact can be reversed:	Low
Indirect impacts:	Loss of High ecological sensitivity and hydrological connectivity
Cumulative impact prior to mitigation:	Medium
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium
Proposed mitigation:	→ Designate the wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline). → The site manager / ECO must check the No Go area for pollution/spills, erosion damage and sedimentation weekly and after every heavy rainfall event. Should pollution, erosion or sedimentation be noted, immediate corrective measures must be undertaken. → Fuel, chemicals, and other hazardous substances should preferably be stored offsite, or as far away as possible from the no-go area. These substances must be stored in suitable secure weather-proof containers with impermeable and bunded floors to limit pilferage, spillage into the environment, flooding, or storm damage. → Inspect all storage facilities, vehicles, and machinery daily for the early detection of deterioration or leaks and strictly

	prohibit the use of any vehicles or machinery from which leakage has been detected. → Mixing and transferring of chemicals or hazardous substances must take place outside of the No Go area, and must take place on drip trays, shutter boards or other impermeable surfaces. → Drip trays must be utilised at all fuel dispensing areas; and during the maintenance of existing sewer flow as possible. → Vehicles and machinery should preferably be cleaned off site. Should cleaning be required on site it must only take place within designated areas outside of the No Go area and should only occur on bunded areas with a water/oil/grease separator. → Dispose of used oils, wash water from cement and other pollutants at an appropriate licensed landfill site. → Avoid the use of infill material or construction material with pollution / leaching potential. Where possible, in situ earthen materials must be used during construction to reduce the risk of leachate from imported materials contaminating the wetland area. → Concrete should preferably be imported as “ready-mix” concrete from a local supplier. Should onsite concrete mixing be required it must not be done on exposed soils. Concrete must be mixed on an impermeable surface in an area of low environmental sensitivity identified by the ECO outside of the no-go area. Surplus or waste concrete must be sent back to the supplier who will dispose of it. → Construct temporary bunds around areas where cement is to be cast in situ. → Dispose of concrete and cement-related mortars in an environmental sensitive manner (can be toxic to aquatic life). Disposal of any of these waste materials into the No Go area is strictly prohibited. → Washout must not be discharged into the no-go area. A washout area should be designated, and wash water should be treated on-site. → Clean up any spillages immediately with the use of a chemical spill kit and dispose of contaminated material at an appropriately registered facility. → Provide portable toilets where work is being undertaken (1 toilet per 10 workers). These toilets must be located within an area designated by the ECO outside of the no-go area and should preferably be located on level ground. Portable toilets must be regularly serviced and maintained. → Provide an adequate number of bins on site and encourage construction personnel to dispose of their waste responsibly. Waste generated by construction personnel must be removed
--	---

	from the site and disposed of at a registered waste disposal facility on a weekly basis. →
Residual impacts	Loss of wetland and ecological connectivity as well as the hydrological connectivity.
Cumulative impact post mitigation:	Loss of wetland and ecological connectivity as well as the hydrological connectivity.
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Medium negative
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	6. Disturbance of Wetland Habitat
Potential impact:	Disturbance of wetland habitat within the UVBW may occur due to the proximity of the proposed residential development, including but not limited to vegetation clearing, infilling, and construction of the housing; as well as the upgrade of the existing sewer pipeline.
Nature of impact:	Negative
Extent and duration of impact:	Local; Short-term
Consequence of impact:	Disturbance to aquatic habitat
Probability of occurrence:	Possible
Degree to which the impact may cause irreplaceable loss of resources:	Low
Degree to which the impact can be reversed:	Medium
Indirect impacts:	Reduction to aquatic biodiversity
Cumulative impact prior to mitigation:	Medium
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Low-Medium
Degree to which the impact can be managed:	Medium – High
Degree to which the impact can be mitigated:	Medium High
Proposed mitigation:	→ Prohibit littering and dumping within the wetland area. Clear and remove any rubble or litter that may have been accidentally deposited into the wetland and dispose of at an appropriate registered facility. Monitoring of litter/dumping within the wetland must be managed by a Homeowners Association (HoA). → Care should be taken to not disturb indigenous wetland vegetation during any maintenance of the pipeline. In line with the NEMBA, all AIPS listed under the amended AIPS Lists (DEFF: GN1003, 2020) must either be removed or controlled on land under the management of the proponent. → Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1) should be planted with

	indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings). → Designate the UVB wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline). Clearly demarcate the construction footprint (including construction camp, access roads, stockpile areas and working servitudes) with orange hazard tape, fencing or similar prior to the commencement of any activity, and strictly prohibit the movement of construction vehicles and personnel outside of the demarcated areas. → Locate site camps, laydown areas, stockpile areas, construction material, equipment storage areas, vehicle parking areas, banded vehicle servicing areas and re-fuelling areas in designated areas of already hardened surface or disturbed areas located outside of the No Go area. These areas should preferably be located on level ground in a previously disturbed area of vegetation approved by the Environmental Control Officer (ECO). Cut and fill must be avoided where possible during the set-up of the construction site camp. → Demarcation of the construction footprint/working servitude must be signed off by an ECO (or similar). Demarcation should not be removed until construction is complete, and rehabilitation (if applicable) has taken place. → Limit access into the construction footprint to existing access roads. → Prohibit the dumping of excavated material, building materials or removed vegetation within the No Go area. Building material must be stored at the designated storage area located outside of the no-go area. Spoil material must be appropriately disposed of at a registered waste disposal facility. → Undisturbed topsoil and subsoils removed from the construction footprint must be stored separately at the designated stockpile area for future rehabilitation. → Vegetation clearance should be restricted to the relevant development components and indigenous vegetation cover should be maintained as far as practically possible. → Vegetation which is considered suitable for rehabilitation activities after construction (such as indigenous grasses and other herbaceous species) should be carefully removed from the construction footprint and stored at an appropriate facility for use in later rehabilitation activities. → Clear and remove any rubble or litter that may have been accidentally deposited into the no-go area because of
--	---

	construction activities and dispose of at an appropriate registered facility. → An ECO must inspect the construction footprint on a weekly basis and must take immediate measures to address unforeseen disturbances to the wetland. Any disturbed / compacted areas falling outside of the demarcated construction footprint must be immediately rehabilitated. Depending on the extent of damage the method of rehabilitation may require input from an aquatic specialist / suitably qualified contractor. → Once construction has been completed, orange hazard fences as well as all construction waste, rubble, and equipment must be removed from the construction footprint. → In line with the NEMBA, all AIPS listed under the amended AIPS Lists (DEFF: GN1003, 2020) must either be removed or controlled on land under the management of the proponent. → An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist. Rehabilitation must take place as soon as possible after construction is completed, and monitoring of rehabilitated areas must be undertaken. A suitably qualified professional must supervise the rehabilitation and monitoring activities.
Residual impacts	Possible decline in aquatic fauna.
Cumulative impact post mitigation:	Low – restoration of the aquatic habitat through rehabilitation of the wetland area on site.
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low (-)
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	7. Altered flow regime
Potential impact:	Site clearance, infilling, and compaction will result in alteration of the flow regime of wetland area on the site. Hardened catchment area would result in increased stormwater runoff, velocity and increased flood peaks within the wetland and would also likely result in sedimentation and erosion.
Nature of impact:	Negative
Extent and duration of impact:	Local; Short-term
Consequence of impact:	Disruption of wetland hydrology, increased erosion and sedimentation, degradation of aquatic habitat
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	Medium
Degree to which the impact can be reversed:	Medium
Indirect impacts:	Altered sediment transport dynamics, loss of wetland function, downstream ecological impacts
Cumulative impact prior to mitigation:	Medium – High

Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium – High
Proposed mitigation:	→ Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings). → Runoff from the proposed development must not increase from the pre-development to the post-development scenario. → The status quo in terms of hydrological connection from Erf 1486 to the downstream system must be maintained / should not be impacted because of the proposed development. → Discharge stormwater from rooftops into rain harvesting tanks. This will limit the volumes of stormwater runoff that will reach the wetland area. Where possible, water collected in rain harvesting tanks can be utilized for flushing of toilets, washing etc. → Stormwater runoff should preferably be discharged as diffuse flow into well vegetated areas outside of the wetland. → Energy dissipaters / erosion protection measures (such as lining with stones, grass, reno-mattresses, or gabions) must be constructed where stormwater is released to reduce the runoff velocity and therefore erosion. → Sheet runoff from hardened surfaces must be intercepted and the treatment and infiltration of runoff must be promoted. → Sediment traps should be incorporated into stormwater drains / swales upstream of any discharge points. → Monitor the wetland area for erosion and sedimentation after heavy rainfall events. Any erosion noted must be immediately addressed. Rehabilitation measures may include the removal of accumulated sediment by hand, filling of erosion gullies and rills, the stabilisation of gullies with silt fences, riprap, and the revegetation of stabilised areas. → Stormwater systems will require ongoing maintenance. Any build-up of silt or debris within stormwater drains or swales will need to be cleared to ensure the continued functioning of the systems. → Any damage to stormwater infrastructure, and any flaws identified in the functionality of stormwater infrastructure, must be rectified immediately. → Appropriately designed raft foundations for residential dwellings may significantly reduce the impact on subsurface flow and therefore reduce risk. → Rainwater harvesting schemes may reduce runoff intensity and thereby mitigate the impact of catchment hardening.

Residual impacts	Altered runoff characteristics, potential for minor ongoing erosion if vegetation fails to establish
Cumulative impact post mitigation:	Low – altered runoff characteristics may occur during the flooding event. However, the impact will be managed through proposed mitigation measures.
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low (-)
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	8. Water Quality impairment
Potential impact:	Accidentally spilled cement, construction chemicals, sewage during the upgrade of the pipeline, or petrochemicals from construction vehicles may find their way into the wetland area. Additionally, litter and dumping may occur due to the proximity of the proposed development to the wetland area.
Nature of impact:	Negative
Extent and duration of impact:	Local; short-term to medium-term
Consequence of impact:	Contamination of watercourses during the construction phase contributing to loss of aquatic fauna.
Probability of occurrence:	Low – Medium
Degree to which the impact may cause irreplaceable loss of resources:	Low – Medium
Degree to which the impact can be reversed:	Moderate
Indirect impacts:	Potential downstream contamination of the broader wetland system linking Hoek van die Berg to the Vermont Salt Pan, and cumulative degradation of aquatic habitat quality within this ecological corridor if pollution incidents are not promptly identified and remediated.
Cumulative impact prior to mitigation:	Medium
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Medium
Degree to which the impact can be avoided:	High
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	→ Design a SWMP which will allow for the infiltration and treatment of stormwater. All stormwaters must receive basic filtering and treatment prior to its release. → Incorporate measures into the stormwater design to trap solid waste, debris and sediment carried by stormwater. Measures may include the use of curb inlet drain grates and debris baskets/bags. → Stormwater generated from areas with a higher risk of contamination such as parking areas and roads (as applicable) must receive basic filtering and treatment prior to its release into surrounding areas. → Stormwater systems must be monitored and maintained into perpetuity and collections of debris and solid waste removed from grates and baskets. The developer must confirm who

	will be responsible for this monitoring and maintenance as well as their roles (likely HoA). → Operational phase mitigation implemented during the design/construction phase: ○ Construct sewage pipelines in accordance with the relevant SANS / SABS specifications. ○ Design the pipelines to accommodate the operating and surge pressures. ○ Provide surge protection e.g. air valves. ○ Allow for scour valves along pipelines to ensure sewage pipelines can be emptied in a controlled manner if required. ○ Allow for surcharge containment and emergency storage of 2 hours of peak flow at manholes located within areas upslope of the wetland. Containment/emergency storage may include a concrete box or earthen bund surrounding the manholes. The backup storage capacity of manholes may also be improved by raising the manholes by one meter. → Repair all sewage leaks as soon as reasonably possible after detection. Inspection of all sewage pipes should be conducted by a plumber once every 10 years. The sewage system must be monitored and maintained into perpetuity. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles. → The wetland area must be regularly inspected for waste. Any waste or litter noted must be immediately removed and disposed of at a registered waste disposal facility. The developer must confirm who will be responsible for this monitoring of the wetland area (HoA).
Residual impacts	Low
Cumulative impact post mitigation:	Low
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low (-)
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	9. Faunal impact
Potential impact:	Cape dwarf chameleon, <i>Bradypodion pumilum</i> habitat loss and movement impediment
Nature of impact:	Negative
Extent and duration of impact:	Local; long-term
Consequence of impact:	Medium
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	Medium
Degree to which the impact can be reversed:	Irreversible

Indirect impacts:	N/A
Cumulative impact prior to mitigation:	Medium - Disturbance and loss of faunal habitat
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	High
Proposed mitigation:	→ The fence traversing the ecological corridor should be permeable to allow for movement of small sized animals e.g. otters, small antelope between the nature reserve and wetland system. → Search and Rescue of chameleons and other slow-moving animals is feasible due to the presence of the adjacent nature reserve. A search and rescue effort should be implemented before and during construction where animals that are found are released in the adjacent nature reserve. → Long term maintenance of ecological integrity of the 'private open space' is critical. Therefore, measures should be put in place for constant removal of alien vegetation, cleanup of litter and prevention of illegal dumping. → Pre and post construction site preparation should include rehabilitation of the 'private open space' by removing current building rubble and litter from this area.
Residual impacts	Medium
Cumulative impact post mitigation:	Medium - It is likely that some of their habitat will be lost on the development footprint and the disturbance during construction phase
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low - Medium (-)

POST CONSTRUCTION

Potential impact and risk:	8. Socioeconomic
Potential Impact	Access to employment for the community during the operational phase, Job creation, Provision of residential erven in response to provincial demand, investment in the area
Nature of impact:	Positive
Extent and duration of impact:	Local; long term
Consequence of impact or risk:	Improved livelihoods beneficiaries, influx of people to the area, investment in the area, spending in the area
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	Access to employment for the community during the operational phase, Job creation, Provision of residential erven in response to provincial demand, investment in the area
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High positive
Degree to which the impact can be avoided:	N/A

Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	N/A
Proposed mitigation:	-
Residual impacts:	Investment in the area, attraction to the area, spending in the area
Cumulative impact post mitigation:	Investment in the area, attraction to the area, spending in the area Access to employment for the community during the operational phase, Job creation, Provision of residential even in response to provincial demand, investment in the area
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High positive
POST CONSTRUCTION	
Potential impact and risk:	9. Visual Impact
Potential Impact	Typical Visual impacts associated with the operational phase of a residential dwelling or group of residential dwellings that may lead to changes in sense of place of the individual from what was there and to what has now changed.
Nature of impact:	Negative – changes in the visual aesthetics of the area during the operational phase. Positive- infill development within an urban area as opposed to the alienation of new land, contributing to more sustainable land use.
Extent and duration of impact:	Long term, local to regional
Consequence of impact or risk:	Risk – visual impact of operation within landscape and suburb
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	High
Indirect impacts:	Loss of sense of place due to the removal of the natural vegetation that is appealing to nature lovers
Cumulative impact prior to mitigation:	Short term impacts associated with changes of the built infrastructure.
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Low
Degree to which the impact can be mitigated:	High
Proposed mitigation:	• Implement landscaping strategies to minimize the visual impact of construction and operational activities. • Incorporate green design principles into the development to enhance aesthetics and mitigate negative visual effects. • Communicate with the community to ensure understanding and acceptance of the changes in the visual character. • Consider the use of native vegetation in landscaping to maintain a natural feel and reduce visual disruptions.
Residual impacts:	None
Cumulative impact post mitigation:	Typical visual impacts associated with operational phase
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	Low negative

POST CONSTRUCTION	
Potential impact and risk:	10. Ecological
Potential impact:	Loss of current moderate levels of ecological connectivity across the site (essentially only W-E connectivity is now available), and associated habitat fragmentation. Loss of ability for natural fires Loss of sensitive botanical areas and vegetation Reduction in natural habitat
Nature of impact:	Negative – ecological impacts Positive – infill development within urban area as opposed to alienation of new land
Extent and duration of impact:	Permanent, local to regional
Consequence of impact:	Loss of all available natural or partly natural faunal habitat on site. Loss of natural spaces, corridors and high ecological species.
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	High
Degree to which the impact can be reversed:	N/A
Indirect impacts:	Loss of moderate current ecological connectivity across the site and associated habitat fragmentation.
Cumulative impact prior to mitigation:	Loss of all natural spaces, corridors and vegetation on site.
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Low
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium
Proposed mitigation:	- No areas of natural or partly natural vegetation should be disturbed outside the pegged/fenced out and authorised erven. No vehicular activity or dumping of material may take place outside the authorised erven or roads. - All alien invasive vegetation should be removed from within the natural portions of the project area, prior to any authorised development. Removal of the alien vegetation must be undertaken by a trained and licensed alien vegetation removal team and must be undertaken using methodology outlined in the Best Practise Guidelines (see Martens et al 2021). - The Homeowners Association (HoA, or similar) for the proposed development must ensure that all alien invasive vegetation (as per NEMBA legislation) is removed from the Public Open Space area on an annual basis by qualified contractors, using methodology as prescribed in Martens et al (2021; see below for reference). The HoA must ensure that there is adequate funding for this every year. - Areas outside the designated road and residential erf boundaries should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way.

	Landowners and the HoA must be made aware of these constraints both prior to and after purchase.
Residual impacts	Loss of sensitive vegetation, open spaces, corridors
Cumulative impact post mitigation:	Loss of natural spaces, loss of ecological connectivity, corridors and vegetation
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	Low - Medium (-)
POST CONSTRUCTION	
Potential impact and risk:	11. Habitat Disturbance
Potential impact:	Disturbance of wetland habitat within the UVBW may occur due to the proximity of the proposed residential development, including but not limited to vegetation clearing, infilling, and construction of the housing; as well as the upgrade of the existing sewer pipeline.
Nature of impact:	Negative
Extent and duration of impact:	Local; short-term
Consequence of impact:	Continued loss of wetland habitat species due to footprint.
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	Low
Degree to which the impact can be reversed:	Low-Medium
Indirect impacts:	Reduction in wetland habitat.
Cumulative impact prior to mitigation:	High
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Low
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium – High
Proposed mitigation:	→ Prohibit littering and dumping within the wetland area. Clear and remove any rubble or litter that may have been accidentally deposited into the wetland and dispose of at an appropriate registered facility. Monitoring of litter/dumping within the wetland must be managed by a Homeowners Association (HoA). → In line with the NEMBA, all AIPS listed under the amended AIPS Lists (DEFF: GN1003, 2020) must either be removed or controlled on land under the management of the proponent. → Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings).
Residual impacts	Wetland d ecosystem recovery due to introduction of indigenous wetland species during rehabilitation.
Cumulative impact post mitigation:	Low-

Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low negative
POST CONSTRUCTION	
Potential impact and risk:	12. Altered flow regime
Potential impact:	Site clearance, infilling and compaction will result in alteration of the flow regime for the UVBW. Site clearance, infilling, and compaction will result in alteration of the flow regime of wetland area. Hardened catchment area would result in increased stormwater runoff, velocity and increased flood peaks within the wetland and would also likely result in sedimentation and erosion.
Nature of impact:	Negative
Extent and duration of impact:	Local; short-term
Consequence of impact:	Accumulation of sediment material and sand to stormwater culverts and permeable swales due to stormwater runoff during flooding event contributing to altered hydrological flow in some areas.
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	Low
Degree to which the impact can be reversed:	Medium
Indirect impacts:	→ Disruption of natural drainage patterns → Increased maintenance requirements for stormwater infrastructure → Possible degradation of wetland habitat integrity → Risk of downstream flooding impacts
Cumulative impact prior to mitigation:	Medium
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium
Proposed mitigation:	→ Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1 of the Aquatic Biodiversity Assessment) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings). → Runoff from the proposed development must not increase from the pre-development to the post-development scenario. → The status quo in terms of hydrological connection from Erf 1486 to the downstream system must be maintained / should not be impacted because of the proposed development. → Discharge stormwater from rooftops into rain harvesting tanks. This will limit the volumes of stormwater runoff that will

	reach the wetland area. Where possible, water collected in rain harvesting tanks can be utilized for flushing of toilets, washing etc. → Stormwater runoff should preferably be discharged as diffuse flow into well vegetated areas outside of the wetland. → Energy dissipaters / erosion protection measures (such as lining with stones, grass, reno-mattresses, or gabions) must be constructed where stormwater is released to reduce the runoff velocity and therefore erosion. → Sheet runoff from hardened surfaces must be intercepted and the treatment and infiltration of runoff must be promoted. → Sediment traps should be incorporated into stormwater drains / swales upstream of any discharge points. → Monitor the wetland area for erosion and sedimentation after heavy rainfall events. Any erosion noted must be immediately addressed. Rehabilitation measures may include the removal of accumulated sediment by hand, filling of erosion gullies and rills, the stabilisation of gullies with silt fences, riprap, and the revegetation of stabilised areas. → Stormwater systems will require ongoing maintenance. Any build-up of silt or debris within stormwater drains or swales will need to be cleared to ensure the continued functioning of the systems. → Any damage to stormwater infrastructure, and any flaws identified in the functionality of stormwater infrastructure, must be rectified immediately. → Appropriately designed raft foundations for residential dwellings may significantly reduce the impact on subsurface flow and therefore reduce risk. → Rainwater harvesting schemes may reduce runoff intensity and thereby mitigate the impact of catchment hardening.
Residual impacts	Possible minor alterations to local hydrology; some stormwater infrastructure may require long-term monitoring and adaptation
Cumulative impact post mitigation:	Low
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low - Medium (-)
POST CONSTRUCTION	
Potential impact and risk:	13. Water Quality impairment
Potential impact:	Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1 of the Aquatic Biodiversity Assessment) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings). Pollutants may enter the wetland via stormwater or sewage leaks (although highly unlikely). However, with the inclusion of stormwater design measures which allow for the infiltration and treatment of stormwater this impact can be greatly reduced
Nature of impact:	Negative
Extent and duration of impact:	Local; short-term

Consequence of impact:	Degradation of water quality in the UVBW wetland system; increased nutrient loads may promote algal growth, reduce dissolved oxygen levels, and harm aquatic biota.
Probability of occurrence:	Likely
Degree to which the impact may cause irreplaceable loss of resources:	Low
Degree to which the impact can be reversed:	Medium
Indirect impacts:	• Reduction in aquatic species diversity • Bioaccumulation of pollutants in wetland fauna • Loss of ecosystem services such as water purification and nutrient cycling • Impacts on downstream water users and aquatic habitats
Cumulative impact prior to mitigation:	Medium (when considered in combination with other regional developments and climate change-related runoff changes)
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Medium
Degree to which the impact can be managed:	Medium
Degree to which the impact can be mitigated:	Medium
Proposed mitigation:	→ Design a SWMP which will allow for the infiltration and treatment of stormwater. All stormwaters must receive basic filtering and treatment prior to its release. → Incorporate measures into the stormwater design to trap solid waste, debris and sediment carried by stormwater. Measures may include the use of curb inlet drain grates and debris baskets/bags. → Stormwater generated from areas with a higher risk of contamination such as parking areas and roads (as applicable) must receive basic filtering and treatment prior to its release into surrounding areas. → Stormwater systems must be monitored and maintained into perpetuity and collections of debris and solid waste removed from grates and baskets. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles (likely HoA). → Operational phase mitigation implemented during the design/construction phase: ○ Construct sewage pipelines in accordance with the relevant SANS / SABS specifications. ○ Design the pipelines to accommodate the operating and surge pressures. ○ Provide surge protection e.g. air valves. ○ Allow for scour valves along pipelines to ensure sewage pipelines can be emptied in a controlled manner if required. ○ Allow for surcharge containment and emergency storage of 2 hours of peak flow at manholes located within areas upslope of the wetland. Containment/emergency storage may include a concrete box or earthen bund surrounding the manholes. The backup storage capacity of manholes may also be improved by raising the manholes by one meter.

	→ The sewage system must be monitored and maintained into perpetuity. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles. → The wetland area must be regularly inspected for waste. Any waste or litter noted must be immediately removed and disposed of at a registered waste disposal facility. The developer must confirm who will be responsible for this monitoring of the wetland area (HoA).
Residual impacts	Minimal if infrastructure and mitigation are effectively implemented and maintained.
Cumulative impact post mitigation:	Low
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low negative
POST CONSTRUCTION	
Potential impact and risk:	14. Faunal impact
Potential impact:	- Infringement on ESA2 corridor which will influence connectivity facilitating animal movement. - Cape dwarf chameleon, <i>Bradypodion pumilum</i> habitat loss and movement impediment
Nature of impact:	Negative
Extent and duration of impact:	Local; long-term
Consequence of impact:	Medium
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	Medium-Low
Degree to which the impact can be reversed:	Irreversible
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	Disturbance and loss of faunal habitat
Significance rating of impact prior to mitigation (e.g. Low, Medium, MediumHigh, High, or Very-High)	Medium
Degree to which the impact can be avoided:	Medium- Low
Degree to which the impact can be managed:	Medium- Low
Degree to which the impact can be mitigated:	Low
Proposed mitigation:	→ The fence traversing the ecological corridor should be permeable to allow for movement of small sized animals e.g. otters, small antelope between the nature reserve and wetland system. → Search and Rescue of chameleons and other slow-moving animals is feasible due to the presence of the adjacent nature reserve. A search and rescue effort should be implemented before and during construction where animals that are found are released in the adjacent nature reserve. → Long term maintenance of ecological integrity of the 'private open space' is critical. Therefore, measures should be put in place for constant removal of alien vegetation, cleanup of litter and prevention of illegal dumping.

	→ Pre and post construction site preparation should include rehabilitation of the 'private open space' by removing current building rubble and litter from this area. → Pets (especially domestic cats) should not be allowed to free-roam the 'private open space'.
Residual impacts	Medium- Low
Cumulative impact post mitigation:	It is likely that some of their habitat will be lost on the development footprint and the disturbance during construction phase
Significance rating of impact after mitigation e.g. Low, Medium, Medium High, High, or Very-High)	Low - Medium (-)
DECOMMISSIONING AND CLOSURE PHASE	
Potential impact and risk:	N/A
Nature of impact:	-
Extent and duration of impact:	-
Consequence of impact or risk:	-
Probability of occurrence:	-
Degree to which the impact may cause irreplaceable loss of resources:	-
Degree to which the impact can be reversed:	-
Indirect impacts:	-
Cumulative impact prior to mitigation:	
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	-
Degree to which the impact can be avoided:	--
Degree to which the impact can be managed:	-
Degree to which the impact can be mitigated:	-
Proposed mitigation:	-
Residual impacts:	-
Cumulative impact post mitigation:	-
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	-

NO GO

PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	1. Ecological impact
Potential impact	No development and status quo remain.
Nature of impact:	Positive
Extent and duration of impact:	Local; long term
Consequence of impact or risk:	Risk of alien vegetation due to landscaping and poor Management Loss of other natural spaces, corridors and vegetation
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	Low
Degree to which the impact can be reversed:	High
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	Risk of alien vegetation due to landscaping and poor Management Loss of natural spaces, corridors and vegetation
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High
Degree to which the impact can be avoided:	High
Degree to which the impact can be managed:	High
Degree to which the impact can be mitigated:	High
Proposed mitigation:	by placing biodiversity offsets in areas of high ecological sensitivity during the construction.
Residual impacts:	Loss of other natural vegetation and species
Cumulative impact post mitigation:	Less negative impacts associated with the clearance of sensitive vegetation.
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High positive
PLANNING, DESIGN AND DEVELOPMENT PHASE	
Potential impact and risk:	2. Socioeconomic impacts
Potential impact	No scope of available job creation, skills transfer and investments
Nature of impact:	Negative
Extent and duration of impact:	Local, short-term
Consequence of impact or risk:	No job creation for communities in the area. No opportunities for investment in the area or provision of residential erven for growth of the area.
Probability of occurrence:	Definite

Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	High
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	low
Degree to which the impact can be mitigated:	low
Proposed mitigation:	Change layout
Residual impacts:	N/A
Cumulative impact post mitigation:	Low
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative- no development may take place
OPERATIONAL PHASE	
Potential impact and risk:	1. Socioeconomic impacts
Potential impact	No access to employment for the community
Nature of impact:	Negative- few people employed
Extent and duration of impact:	Local to provincial, long term
Consequence of impact or risk:	Improved livelihood beneficiaries, low number of people to the area, few investment opportunities,
Probability of occurrence:	Definite
Degree to which the impact may cause irreplaceable loss of resources:	N/A
Degree to which the impact can be reversed:	N/A
Indirect impacts:	N/A
Cumulative impact prior to mitigation:	No employment or investments on the site because there will be no development taking place.
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
Degree to which the impact can be avoided:	N/A
Degree to which the impact can be managed:	Low
Degree to which the impact can be mitigated:	Low
Proposed mitigation:	
Residual impacts:	N/A
Cumulative impact post mitigation:	No access to jobs, no development and no investments
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	High negative
OPERATIONAL PHASE	
Potential impact and risk:	2. Ecological
Potential impact:	Status quo remains
Nature of impact:	--
Extent and duration of impact:	-
Consequence of impact:	-

Probability of occurrence:	-
Degree to which the impact may cause irreplaceable loss of resources:	-
Degree to which the impact can be reversed:	-
Indirect impacts:	-
Cumulative impact prior to mitigation:	-
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium High, High, or Very-High)	-
Degree to which the impact can be avoided:	-
Degree to which the impact can be managed:	-
Degree to which the impact can be mitigated:	-
Proposed mitigation:	-
Residual impacts	-
Cumulative impact post mitigation:	-
Significance rating of impact after mitigation e.g. Low, Medium, MediumHigh, High, or Very-High)	High Positive
DECOMMISSIONING AND CLOSURE PHASE	
Potential impact and risk:	Not Applicable
Nature of impact:	-
Extent and duration of impact:	-
Consequence of impact or risk:	-
Probability of occurrence:	-
Degree to which the impact may cause irreplaceable loss of resources:	-
Degree to which the impact can be reversed:	-
Indirect impacts:	-
Cumulative impact prior to mitigation:	
Significance rating of impact prior to mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	-
Degree to which the impact can be avoided:	--
Degree to which the impact can be managed:	-
Degree to which the impact can be mitigated:	-
Proposed mitigation:	-
Residual impacts:	-
Cumulative impact post mitigation:	-
Significance rating of impact after mitigation (e.g. Low, Medium, Medium-High, High, or Very-High)	-

SECTION I: FINDINGS, IMPACT MANAGEMENT AND MITIGATION MEASURES

1.	Provide a summary of the findings and impact management measures identified by all Specialist and an indication of how these findings and recommendations have influenced the proposed development.
Terrestrial Biodiversity Impact Assessment Summary → The site comprises Hangklip Sand Fynbos, a Critically Endangered vegetation type. However, much of the vegetation is senescent and degraded due to the absence of natural fire cycles. → Disturbed areas dominated by alien species (e.g., Kikuyu grass) were identified, especially around the existing building, wetland edge, and garden south western portion. → No plants Species of Conservation Concern (SoCC) were recorded on-site, and many red-listed species flagged by the Screening Tool, only one may likely occur on site (<i>Disa hallackii</i>: Endangered). → Two species of frogs were heard calling on site, and populations on site are probably viable and significant. <i>Hyperolius marmoratus</i> (painted reed frogs) were calling from the standing water, whilst <i>Strongylopus grayii</i> (clicking stream frogs) were calling across most of the site. <i>Cacosternum australis</i> may also occur here but was not heard. → <i>Bradypodion pumilum</i> (Cape Dwarf Chameleon) has been regularly recorded from similar nearby habitat (iNaturalist.org) and is likely to be present on site. → No other Redlisted reptiles are likely to be present. → In terms of birds two threatened harrier species may occasionally visit this site. African Marsh Harrier (<i>Circus ranivorus</i>; Endangered) and the Black Harrier (<i>Circus maurus</i>; Endangered) are both known from the general area, and travel widely. → Tracks and scat of mammal species were observed onsite, this includes porcupine (<i>Hystrix africae australis</i>), vlei rat (<i>Otomys unisulcatus</i>), Cape Grey Mongoose (<i>Herpestes pulverulentus</i>) and Water Mongoose (<i>Atilax paludinosus</i>), and other likely species include Large Grey Mongoose (<i>Herpestes ichneumon</i>), Striped Fieldmouse (<i>Rhabdomys pumilio</i>) and Cape Genet (<i>Genetta tigrina</i>). → No threatened butterflies are likely to utilise the site. → The proposed residential erven now exclude most of the High sensitivity areas, and only about 500m² of high sensitivity habitat will now be lost. → The revised layout (Alternative 4) is a good compromise and has a substantially lower ecological impact than the alternative assessed in the botanical report of May 2023 and is also preferred over Alternative 3. The proposed residential erven now exclude most high-sensitivity areas and only about 500m² of highly sensitive vegetation will be lost. → The proposed residential erven now exclude most of the High sensitivity areas (as required in my first bullet point of mitigation), and it is estimated that less than 500m² of high sensitivity habitat will now be lost. Some 58% of the total erf will now be conservation area (Private Open Space), up from about 36%. → Ecological impact was reduced from unacceptable High negative (Alt 2) to Low - Medium negative (Alt 4).	

Impact management measures:

- No erven should intrude significantly into the seasonal wetland portions of the site that support mostly habitat of High ecological sensitivity.
- No pipelines, cabling or infrastructure should be installed across the High sensitivity areas or wetlands.
- Any boundary fencing used must be permeable to small animals at ground level.
- The authorised erf and road boundaries should be surveyed and pegged out and fenced on site prior to any site development.
- No areas of natural or partly natural vegetation should be disturbed outside the pegged/fenced out and authorised erven. No vehicular activity or dumping of material may take place outside the authorised erven or roads.
- All alien invasive vegetation should be removed from within the natural portions of the project area, prior to any authorised development. Removal of the alien vegetation must be undertaken by a trained and licensed alien vegetation removal team and must be undertaken using methodology outlined in the Best Practise Guidelines (see Martens et al 2021).
- The Homeowners Association (HoA, or similar) for the proposed development must ensure that all alien invasive vegetation (as per NEMBA legislation) is removed from the Public Open Space area on an annual basis by qualified contractors, using methodology as prescribed in Martens et al (2021; see below for reference). The HoA must ensure that there is adequate funding for this every year.
- Areas outside the designated road and residential erf boundaries should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way. Landowners and the HoA must be made aware of these constraints both prior to and after purchase.

Aquatic Biodiversity Impact Assessment

Wetland Presence and Status

- A natural Unchanneled Valley-Bottom (UVB) wetland was delineated onsite.
- The wetland is part of a 1.4 km system that connects to the Vermont Pan and has been disturbed by excavation, infill, alien vegetation, and urban runoff.
- The wetland has a Present Ecological State (PES) of Category D (largely modified), with moderate Ecological Importance and Sensitivity (EIS) and moderately high Wetland Ecosystem Services (WES) scores, indicating ecological significance despite degradation.
- Vegetation within the erf was extensively disturbed, with a mixture of indigenous species such as *Senecio halimifolius*, the wetland obligate *Juncus kraussi*, and *Typha capensis*.
- Alien vegetation is also present alongside invasive species such as Kikuyu grass (*Cenchrus clandestinum*) and pampas grass (*Cortaderia selloana*).
- Terrestrial soils within the study area are dark grey, sandy and appear to be well drained.
- Soils that were sampled in wetter areas near the depression did not differ markedly from terrestrial soils, aside from appearing darker and with a higher organic content than the terrestrial baseline.

Impact Assessment Summary

- All the potential impacts to the UVBW were the lowest (both prior, and after, the implementation of mitigation measures) for Alternative Layout 3 and 4. The revised layouts represent a refinement of previously assessed layouts and incorporates a larger open space area surrounding the delineated wetland. These two layouts are preferred from an aquatic perspective, as it entails all proposed residential erven to be located outside the delineated permanent wetland area.

- The revised layouts further reduce potential encroachment into the seasonal wetland zone, with only minor edge encroachments associated with the northern erven
- Wetland loss is rated as Medium
- Altered flow regime is Very low
- Water quality impairment is rated as Very low
- The No-Go option would result in the continuation of impact to the wetland due to adjacent land uses – and would therefore still result in negative impact to the wetland onsite.

Risk Assessment

- The moderate risk class for wetland loss confirms the need for a Water Use Licence (WUL) – Submitted.
- A Wetland Offset, Rehabilitation, and Management Plan was implemented to align with the "no net loss" policy.

Hydrology:

- The natural flow regime of the UVB Wetland (UVBW) has been altered as a result of disturbances such as the excavation to create the centre depressional area on the erf itself, historical vegetation clearing and infilling, and catchment hardening associated with the roads, dirt tracks, residential areas.
- Although there is an overflow pipe that crosses beneath Lynx Road and flows into the wetland on the far side, the construction of Lynx Road, and excavation within the centre of the site, has created a dam within the centre of the UVBW.
- The hydrology of the UVBW has been impacted by the presence of urban residential land use within the wetland itself, and in the wetland's immediate catchment area. Urban land use such as residential areas and tarred roads has resulted in flow diversion and catchment hardening which is associated with increased runoff and storm peak flows.
- The wetland has been canalized, leading to concentration of flow, and likely the drying out of the wetland in various locations.
- Additionally, a stormwater outlet is in the southeast corner of the erf, which discharges runoff from the neighbouring housing development into the wetland. Additional stormwater outlets into the wetland are observed downstream of the erf.

Vegetation:

- Several indigenous hydrophytic species were noted, and there is moderate disturbance within the wetland area as a result of:
 - Excavation of the dam on the subject property.
 - Large areas of the UVBW were brush cut during 2004, and the large area down was cleared.
 - Construction activities associated with the derelict houses on the erf, and downstream residential areas;
 - Dumping of rubble within the wetland area.
- The vegetation present within the wetland is characterised by a mixture of alien and indigenous vegetation. Alien invasive species noted onsite include dense clumps of Kikuyu grass (*Cenchrus clandestinum*) and pampas grass (*Cortaderia selloana*).
- No species of conservation concern were noted. According to the Botanist appointed for the proposed project, at least one plant SoCC (*Disa hallackii*) may be present in low numbers (Nick Helme Botanical Surveys, 2023).

Geomorphology:

- The geomorphology of the UVBW wetland was largely modified by the excavation of the depressional / dam area in the centre of the erf.

- Additionally, historical vegetation clearing, infilling, and hardening across large areas of the wetland has resulted in extensive disturbance to its natural geomorphic state.
- The wetland system extends from the study area in a south-easterly direction and ultimately augments the Vermont Salt Pan. The construction of Lynx Road, Kolgans Close Road, and numerous other roads, has seriously altered this portion of the UVBW's geomorphology.

Water Quality:

- The water quality within the UVB wetland has been disturbed because of the adjacent infilling and compaction of the southern portion of the Erf; along with large portions which have been infilled downstream within the wetland due to residential development, which has resulted in:
 - Leaching of toxicants and nutrients from the infilling materials such as hydroxyl ions from cement particles and nitrates from laterite.
- The water quality within the wetland is likely to be impacted by the residential nature of the catchment.
- It is likely that runoff entering the wetland through the stormwater outlets is likely polluted by the surrounding catchment area for example, runoff from roads is likely to contain contaminants such as laterite, oil, fuel, rubber from car tires and other pollutants.

Impact management measures

- An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist.
- Designate the UVB wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline). Clearly demarcate the construction footprint (including construction camp, access roads, stockpile areas and working servitudes) with orange hazard tape, fencing or similar prior to the commencement of any activity, and strictly prohibit the movement of construction vehicles and personnel outside of the demarcated areas.
- Locate site camps, laydown areas, stockpile areas, construction material, equipment storage areas, vehicle parking areas, banded vehicle servicing areas and re-fuelling areas in designated areas of already hardened surface or disturbed areas located outside of the No Go area. These areas should preferably be located on level ground in a previously disturbed area of vegetation approved by the Environmental Control Officer (ECO). Cut and fill must be avoided where possible during the set-up of the construction site camp.
- Demarcation of the construction footprint/working servitude must be signed off by an ECO (or similar). Demarcation should not be removed until construction is complete, and rehabilitation (if applicable) has taken place.
- Limit access into the construction footprint to existing access roads.
- Prohibit the dumping of excavated material, building materials or removed vegetation within the No Go area. Building material must be stored at the designated storage area located outside of the no-go area. Spoil material must be appropriately disposed of at a registered waste disposal facility.
- Undisturbed topsoil and subsoils removed from the construction footprint must be stored separately at the designated stockpile area for future rehabilitation.
- Vegetation clearance should be restricted to the relevant development components and indigenous vegetation cover should be maintained as far as practically possible.
- Vegetation which is considered suitable for rehabilitation activities after construction (such as indigenous grasses and other herbaceous species) should be carefully removed from the construction footprint and stored at an appropriate facility for use in later rehabilitation activities.
- Clear and remove any rubble or litter that may have been accidentally deposited into the no-go area because of construction activities and dispose of at an appropriate registered facility.

- An ECO must inspect the construction footprint on a weekly basis and must take immediate measures to address unforeseen disturbances to the wetland. Any disturbed / compacted areas falling outside of the demarcated construction footprint must be immediately rehabilitated. Depending on the extent of damage the method of rehabilitation may require input from an aquatic specialist / suitably qualified contractor.
- Once construction has been completed, orange hazard fences as well as all construction waste, rubble, and equipment must be removed from the construction footprint.
- In line with the NEMBA, all AIPS listed under the amended AIPS Lists (DEFF: GN1003, 2020) must either be removed or controlled on land under the management of the proponent.
- An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist. Rehabilitation must take place as soon as possible after construction is completed, and monitoring of rehabilitated areas must be undertaken. A suitably qualified professional must supervise the rehabilitation and monitoring activities.
- Designate the wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline).
- The status quo in terms of hydrological connection from Erf 1486 to the downstream system must be maintained / should not be impacted because of the proposed development.
- If possible, conduct construction activities of dwellings, associated stormwater infrastructure and any rehabilitation activities during summer months (November to March).
- Ensure that effective stormwater management measures are implemented during construction. Stormwater management must ensure that no runoff, which will impair the water quality and lead to increased sedimentation, may enter the downstream wetland area. Additionally, clean SW which does enter the downstream wetland system should do so in a manner that ensures no erosion occurs, specifically during storm events, such as through vegetated swales.
- Appropriately designed raft foundations for residential dwellings may significantly reduce the impact on subsurface flow and therefore reduce this impact / risk.
- Rainwater harvesting schemes may reduce runoff intensity and thereby mitigate the impact of catchment hardening.
- The alien invasive vegetation present within the wetland area must be removed and replanted with indigenous wetland vegetation.
- An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist.
- Designate the wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline).
- The site manager / ECO must check the No Go area for pollution/spills, erosion damage and sedimentation weekly and after every heavy rainfall event. Should pollution, erosion or sedimentation be noted, immediate corrective measures must be undertaken.
- Fuel, chemicals, and other hazardous substances should preferably be stored offsite, or as far away as possible from the no-go area. These substances must be stored in suitable secure weather-proof containers with impermeable and bunded floors to limit pilferage, spillage into the environment, flooding, or storm damage.
- Inspect all storage facilities, vehicles, and machinery daily for the early detection of deterioration or leaks and strictly prohibit the use of any vehicles or machinery from which leakage has been detected.
- Mixing and transferring of chemicals or hazardous substances must take place outside of the No Go area, and must take place on drip trays, shutter boards or other impermeable surfaces.
- Drip trays must be utilised at all fuel dispensing areas; and during the maintenance of existing sewer flow as possible.
- Vehicles and machinery should preferably be cleaned off site. Should cleaning be required on site it must only take place within designated areas outside of the No Go area and should only occur on bunded areas with a water/oil/grease separator.
- Dispose of used oils, wash water from cement and other pollutants at an appropriate licensed landfill site.

- Avoid the use of infill material or construction material with pollution / leaching potential. Where possible, in situ earthen materials must be used during construction to reduce the risk of leachate from imported materials contaminating the wetland area.
- Concrete should preferably be imported as “ready-mix” concrete from a local supplier. Should onsite concrete mixing be required it must not be done on exposed soils. Concrete must be mixed on an impermeable surface in an area of low environmental sensitivity identified by the ECO outside of the no-go area. Surplus or waste concrete must be sent back to the supplier who will dispose of it.
- Construct temporary bunds around areas where cement is to be cast in situ.
- Dispose of concrete and cement-related mortars in an environmental sensitive manner (can be toxic to aquatic life). Disposal of any of these waste materials into the No Go area is strictly prohibited.
- Washout must not be discharged into the no-go area. A washout area should be designated, and wash water should be treated on-site.
- Clean up any spillages immediately with the use of a chemical spill kit and dispose of contaminated material at an appropriately registered facility.
- Provide portable toilets where work is being undertaken (1 toilet per 10 workers). These toilets must be located within an area designated by the ECO outside of the no-go area and should preferably be located on level ground. Portable toilets must be regularly serviced and maintained.
- Provide an adequate number of bins on site and encourage construction personnel to dispose of their waste responsibly.
- Waste generated by construction personnel must be removed from the site and disposed of at a registered waste disposal facility on a weekly basis.
- Prohibit littering and dumping within the wetland area. Clear and remove any rubble or litter that may have been accidentally deposited into the wetland and dispose of at an appropriate registered facility. Monitoring of litter/dumping within the wetland must be managed by a Homeowners Association (HoA).
- In line with the NEMBA, all AIPS listed under the amended AIPS Lists (DEFF: GN1003, 2020) must either be removed or controlled on land under the management of the proponent.
- Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings).
- Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings).
- Runoff from the proposed development must not increase from the pre-development to the post-development scenario.
- The status quo in terms of hydrological connection from Erf 1486 to the downstream system must be maintained / should not be impacted because of the proposed development.
- Discharge stormwater from rooftops into rain harvesting tanks. This will limit the volumes of stormwater runoff that will reach the wetland area. Where possible, water collected in rain harvesting tanks can be utilized for flushing of toilets, washing etc.
- Stormwater runoff should preferably be discharged as diffuse flow into well vegetated areas outside of the wetland.
- Energy dissipaters / erosion protection measures (such as lining with stones, grass, reno-mattresses, or gabions) must be constructed where stormwater is released to reduce the runoff velocity and therefore erosion.
- Sheet runoff from hardened surfaces must be intercepted and the treatment and infiltration of runoff must be promoted.
- Sediment traps should be incorporated into stormwater drains / swales upstream of any discharge points.
- Monitor the wetland area for erosion and sedimentation after heavy rainfall events. Any erosion noted must be immediately addressed. Rehabilitation measures may include the removal of accumulated sediment by hand,

filling of erosion gullies and rills, the stabilisation of gullies with silt fences, riprap, and the revegetation of stabilised areas.

- Stormwater systems will require ongoing maintenance. Any build-up of silt or debris within stormwater drains or swales will need to be cleared to ensure the continued functioning of the systems.
- Any damage to stormwater infrastructure, and any flaws identified in the functionality of stormwater infrastructure, must be rectified immediately.
- Appropriately designed raft foundations for residential dwellings may significantly reduce the impact on subsurface flow and therefore reduce risk.
- Rainwater harvesting schemes may reduce runoff intensity and thereby mitigate the impact of catchment hardening.
- Design a SWMP which will allow for the infiltration and treatment of stormwater. All stormwaters must receive basic filtering and treatment prior to its release.
- Incorporate measures into the stormwater design to trap solid waste, debris and sediment carried by stormwater. Measures may include the use of curb inlet drain grates and debris baskets/bags.
- Stormwater generated from areas with a higher risk of contamination such as parking areas and roads (as applicable) must receive basic filtering and treatment prior to its release into surrounding areas.
- Stormwater systems must be monitored and maintained into perpetuity and collections of debris and solid waste removed from grates and baskets. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles (likely HoA).
- Operational phase mitigation implemented during the design/construction phase:
 - Construct sewage pipelines in accordance with the relevant SANS / SABS specifications.
 - Design the pipelines to accommodate the operating and surge pressures.
 - Provide surge protection e.g. air valves.
 - Allow for scour valves along pipelines to ensure sewage pipelines can be emptied in a controlled manner if required.
 - Allow for surcharge containment and emergency storage of 2 hours of peak flow at manholes located within areas upslope of the wetland. Containment/emergency storage may include a concrete box or earthen bund surrounding the manholes. The backup storage capacity of manholes may also be improved by raising the manholes by one meter.
- The sewage system must be monitored and maintained into perpetuity. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles.
- The wetland area must be regularly inspected for waste. Any waste or litter noted must be immediately removed and disposed of at a registered waste disposal facility. The developer must confirm who will be responsible for this monitoring of the wetland area (HoA).

Terrestrial Animal Site Sensitivity Verification Report and Species Specialist Assessment Report:

- The presence of an ecological corridor that supports movement of ground-dwelling species between the Hoek van der Berg Private Nature Reserve and wetlands is crucial.
- Maintaining the 'private open space' and its ecological integrity is essential.
- From a faunal connectivity perspective, the proposed development risk is rated as 'medium'
- The survey confirmed the presence of several faunal species (e.g., Cape Spurfowl, Yellow-billed Duck, Cape Weaver, amphibians, and mammals).
- No animal species of conservation concern identified. The Cape Dwarf Chameleon, though not observed on site, is likely present due to nearby records and suitable habitat.

- The overall SEI for the Project Area of Influence (PAOI) is rated 'Medium,' primarily due to the ecological corridor (ESA2) and potential habitat for the Cape Dwarf Chameleon.
- The small size of the proposed development and the provision of 'private open space' offer sufficient forage habitat for black harriers. Given their wide range, the minor loss of forage habitat is unlikely to significantly affect them. Additionally, the development does not notably impact potential breeding sites or prey species. Consequently, the potential impact on Black Harrier (*Circus maurus*) is assessed as 'low'.
- Similarly, the small development footprint and 'private open space' provide adequate forage habitat for marsh harriers. With their extensive range, the minor loss of forage habitat is not expected to have a significant effect. The development site does not significantly influence breeding sites or prey species. Thus, the potential impact on African Marsh Harrier (*Circus ranivorus*) is also classified as 'low'.
- The habitat within the development site is unsuitable for Denham's bustard (*Neotis denhami*), so the impact of the development on this species is considered 'low'.
- The dense wetland vegetation on the site does not provide suitable habitat for the Hottentot Buttonquail (*Turnix hottentotus*). Therefore, the likelihood of this species occurring at the site is low, and the impact of the development on it is also expected to be 'low'.
- While the habitat at the site is not ideal for Stiped Flufftail (*Sarothrura affinis*), its presence cannot be ruled out entirely. If present, some habitat loss is possible, and construction disturbances might cause temporary displacement. However, the adjacent nature reserve and wetland system could offer refuge. Hence, the potential impact on Stiped Flufftail is classified as 'low'.
- The dense wetland vegetation and strata at the development site are unsuitable for the Southern Adder (*Bitis armata*). The likelihood of this species occurring at the site is low, leading to a likely 'low' impact from the development.
- The habitat at the site is deemed highly suitable for the Cape Dwarf Chameleon (*Bradypodion pumilum*). While some habitat loss is expected and construction disturbances may have a negative impact, the adjacent nature reserve and wetland system offer space for the species to relocate. A search and rescue operation for this species before construction could mitigate some impacts. The potential impact on Cape Dwarf Chameleon is therefore classified as 'Medium'.
- The proposed development is assessed as having a 'low' impact on the Agile Grasshopper (*Aneuryphymus montanus*) due to the lack of species data from the area, absence of direct evidence, unsuitability of the habitat, the small size of the development relative to surrounding vegetation, and the wide regional distribution of the species.
- Alternative 4 (preferred) provides for a private open space that facilitates a more functional ecological corridor. This represents an improvement compared to the earlier alternatives in terms of Cape Dwarf Chameleon (*Bradypodion pumilum*) habitat functionality. The anticipated impact of development on habitat loss and movement impediment for this species is therefore rated as Low to Medium after mitigation.

Impact mitigation measures

- During the construction phase the construction area should be clearly demarcated and blocked off from the 'private open space' area to avoid damage and pollution.
- Pre and post construction site preparation should include rehabilitation of the 'private open space' by removing current building rubble and litter from this area.
- Long term maintenance of ecological integrity of the 'private open space' is critical. Therefore, measures should be put in place for constant removal of alien vegetation, cleanup of litter and prevention of illegal dumping. Clear legal responsibility for the maintenance of the space should be entrenched to be the responsibility of the homeowners association.
- The fence traversing the ecological corridor should always be permeable to allow for movement of small sized animals e.g. small antelope, genets, mongoose between the nature reserve and wetland system.

- Search and Rescue of chameleons and other slow-moving animals is feasible due to the presence of the adjacent nature reserve where they can be released. A search and rescue effort should be implemented before and during construction where animals that are found are released in the adjacent nature reserve. The necessary permission and permits should be attained before this is done.
- Pets (especially domestic cats) should not be allowed to free-roam the 'private open space'.

Wetland Offset, Rehabilitation, and Management Plan

- A 0.9-ha UVB wetland covers 60% of the 1.5-ha site, classified as 'Very High' aquatic sensitivity despite its disturbed state (Present Ecological State [PES] Category D, largely modified)
- The preferred layout (Alternative 4) results in the loss of 0.024 ha (3%) of the wetland due to access road construction.
- The total development footprint (0.5 ha, 37.9% of the site) cannot avoid wetland encroachment entirely, as the wetland dominates the site.
- Using Macfarlane et al. (2016) guidelines, the lost wetland portion is valued at 0.0139 Hectare Equivalents (HE) of function and 0.1890 HE of habitat.
- The remaining 0.9361 ha of wetland is suitable for rehabilitation, potentially yielding 0.1214 HE of function and 1.3841 HE of habitat, resulting in a surplus of 0.1075 HE (function) and 1.2518 HE (habitat), satisfying offset requirements.
- The wetland is degraded by foreign fill material, alien invasive species (e.g., *kikuyu grass*, *pampas grass*, *Acacia saligna*, *Acacia cyclops*), and garden plants.
- Rehabilitation aims to improve the PES from Category D to upper Category C (minimum PES score of 79%).

Wetland Loss and Mitigation Opportunities

Rehabilitation mitigations

- Application of maximum viable rehabilitation effort to increase the PES of the onsite offset wetland area to upper category C with a minimum PES Score of 79 %.
- Removal of dumped rubble and fill material within the wetland. Reshaping of the wetland specifically in the areas where infill has been removed to ensure very slight gradual decline towards the permanent zone.
- Removal of all Alien Invasive vegetation Species (AIS) from this offset wetland area such as Kikuyu grass (*Cenchrus clandestinum*), Pampas grass (*Cortaderia selloana*), Australian myrtle (*Leptospermum laevigatum*), sweet needlebush (*Hakea drupacea*), Port Jackson (*Acacia saligna*) and rooikrans (*Acacia cyclops*), as well as all planted garden species in the southwest corner of the Erf coinciding with the wetland.
- Establishment of a healthy and moderately diverse indigenous vegetation community within any areas that have been cleared (areas historically cleared of indigenous vegetation and cleared of AIS) as well as the areas where infill / rubble has been removed within the offset wetland area. Revegetate with indigenous wetland plant species based on the relevant species list (refer to **Table 8-1** of the Wetland Offset, Rehabilitation and Management Plan);
- Implementation of the Stormwater Mitigation measures outlined in the Wetland Offset, Rehabilitation and Management Plan.
- Ensuring that the onsite offset area is managed in accordance with this plan, such that the rehabilitated state is maintained in perpetuity.

Recommended mitigation measures to be included in the Stormwater Management Plan:

- Discharge stormwater from rooftops into rain harvesting tanks. This will limit the volumes of stormwater runoff that will reach the wetland. Where possible, water collected in rain harvesting tanks can be utilised for flushing of toilets, washing etc.
- Vegetated swales must be utilised rather than concrete drains or underground stormwater pipes in order to encourage infiltration, particularly next to roadways.
- Energy dissipaters / erosion protection measures (such as lining with stones, grass, reno-mattresses, or gabions) must be constructed where stormwater is released in order to reduce the runoff velocity and therefore erosion.
- Sheet runoff from hardened surfaces must be intercepted and the treatment and infiltration of runoff must be promoted.
- Sediment traps should be incorporated into stormwater drains / swales upstream of all discharge points into the wetland.
- All stormwater draining into the wetland must receive basic filtering and treatment prior to its release.
- Incorporate measures into the stormwater design to trap solid waste, debris and sediment carried by stormwater. Measures may include the use of curb inlet drain grates and debris baskets/bags.
- Stormwater generated from areas with a higher risk of contamination such as parking areas and roads must receive basic filtering and treatment prior to its release into surrounding areas. Treatment methods may include sand filter traps and oil-water separators which will require maintenance.
- The extent of hardened surfaces must be minimised. E.g. where required permeable paving must be used.
- Homeowners must be encouraged to landscape their gardens with the use of indigenous species to decrease the area of hardened surface and increase infiltration.
- Homeowners should store any potential pollutants in such a way that pollution will not occur to the wetland (such as any fuel, etc.). Potential pollutants should be stored in an adequately bunded area.
- The use of herbicides, pesticides and any other poisons within private gardens must be strictly prohibited. The home owner's association must be responsible for ensuring that residents are compliant with this.
- Backwashing of swimming pools directly into the wetland must be strictly prohibited. Backwash water can be collected in settling tanks where dirt and debris settle to the bottom. The cleaner water can then be reused for non-potable purposes or even filtered back into the pool system. Backwash water can be diverted to greywater tanks.
- Monitor the proposed development and adjacent wetland for erosion and sedimentation after heavy rainfall events. Any erosion noted must be immediately addressed. Rehabilitation measures may include the removal of accumulated sediment by hand, filling of erosion gullies and rills, the stabilisation of gullies with silt fences, riprap, and the revegetation of stabilised areas.
- Stormwater systems will require ongoing maintenance. Any build-up of silt or debris within stormwater drains or swales will need to be cleared to ensure the continued functioning of the systems.
- Any damage to stormwater infrastructure, and any flaws identified in the functionality of stormwater infrastructure, must be rectified immediately.
- Stormwater systems must be monitored and maintained into perpetuity and collections of debris and solid waste removed from grates and baskets. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles.
- The stormwater system must be designed by a suitably qualified engineer with input from an aquatic specialist.

Stormwater Management Plan

- The site is in a winter rainfall region (591 mm MAP), with flat terrain draining east to the Vermont Salt Pan.
- The catchment includes a steep northern mountainous area (CA1) and the site (CA2).
- Post-development runoff slightly increases (e.g., Q100: 3.211 m³/s vs. 3.107 m³/s pre-development), with minimal wetland water level rise (e.g., Q100: 0.69 m vs. 0.67 m).

Mitigation measures through Low Impact Development (LID)

- **Permeable Paving** (South of Wetland): 2114 m² area, reduces runoff (e.g., Q100: 3.10 m³/s) and treats water (50% TP, 65% TN, 60% heavy metals reduction).
- **Vegetated Swale** (North of Wetland): 5283 m² area, further reduces runoff and matches water quality targets.
- **Culvert Management**: Control runoff from CA1 through a 2 x 900 mm pipe to prevent flooding.
- **Gabions**: It is proposed that all outlet structures be provided with the gabion control measure for litter and erosion control (refer to Page 19 of the Stormwater Management Plan).

- | | |
|----|--|
| 2. | List the impact management measures that were identified by all Specialist that will be included in the EMPr |
|----|--|

Terrestrial Biodiversity Impact Assessment:

- No erven should intrude significantly into the seasonal wetland portions of the site that support mostly habitat of High ecological sensitivity.
- No pipelines, cabling or infrastructure should be installed across the High sensitivity areas or wetlands.
- Any boundary fencing used must be permeable to small animals at ground level.
- The authorised erf and road boundaries should be surveyed and pegged out and fenced on site prior to any site development.
- No areas of natural or partly natural vegetation should be disturbed outside the pegged/fenced out and authorised erven. No vehicular activity or dumping of material may take place outside the authorised erven or roads.
- All alien invasive vegetation should be removed from within the natural portions of the project area, prior to any authorised development. Removal of the alien vegetation must be undertaken by a trained and licensed alien vegetation removal team, and must be undertaken using methodology outlined in the Best Practise Guidelines (see Martens et al 2021).
- The Homeowners Association (HoA, or similar) for the proposed development must ensure that all alien invasive vegetation (as per NEMBA legislation) is removed from the Public Open Space area on an annual basis by qualified contractors, using methodology as prescribed in Martens et al (2021; see below for reference). The HoA must ensure that there is adequate funding for this every year.
- Areas outside the designated road and residential erf boundaries should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way. Landowners and the HoA must be made aware of these constraints both prior to and after purchase.

Aquatic Biodiversity Impact Assessment:

The following mitigation measures are recommended by the specialist:

- An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist.
- Designate the UVB wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline). Clearly demarcate the construction footprint (including construction camp, access roads, stockpile areas and working servitudes) with orange hazard tape, fencing or similar prior to the commencement of any activity, and strictly prohibit the movement of construction vehicles and personnel outside of the demarcated areas.
- Locate site camps, laydown areas, stockpile areas, construction material, equipment storage areas, vehicle parking areas, banded vehicle servicing areas and re-fuelling areas in designated areas of already hardened surface or disturbed areas located outside of the No Go area. These areas should preferably be located on level

- ground in a previously disturbed area of vegetation approved by the Environmental Control Officer (ECO). Cut and fill must be avoided where possible during the set-up of the construction site camp.
- Demarcation of the construction footprint/working servitude must be signed off by an ECO (or similar). Demarcation should not be removed until construction is complete, and rehabilitation (if applicable) has taken place.
 - Limit access into the construction footprint to existing access roads.
 - Prohibit the dumping of excavated material, building materials or removed vegetation within the No Go area. Building material must be stored at the designated storage area located outside of the no-go area. Spoil material must be appropriately disposed of at a registered waste disposal facility.
 - Undisturbed topsoil and subsoils removed from the construction footprint must be stored separately at the designated stockpile area for future rehabilitation.
 - Vegetation clearance should be restricted to the relevant development components and indigenous vegetation cover should be maintained as far as practically possible.
 - Vegetation which is considered suitable for rehabilitation activities after construction (such as indigenous grasses and other herbaceous species) should be carefully removed from the construction footprint and stored at an appropriate facility for use in later rehabilitation activities.
 - Clear and remove any rubble or litter that may have been accidentally deposited into the no-go area because of construction activities and dispose of at an appropriate registered facility.
 - An ECO must inspect the construction footprint on a weekly basis and must take immediate measures to address unforeseen disturbances to the wetland. Any disturbed / compacted areas falling outside of the demarcated construction footprint must be immediately rehabilitated. Depending on the extent of damage the method of rehabilitation may require input from an aquatic specialist / suitably qualified contractor.
 - Once construction has been completed, orange hazard fences as well as all construction waste, rubble, and equipment must be removed from the construction footprint.
 - In line with the NEMBA, all AIPS listed under the amended AIPS Lists (DEFF: GN1003, 2020) must either be removed or controlled on land under the management of the proponent.
 - An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist. Rehabilitation must take place as soon as possible after construction is completed, and monitoring of rehabilitated areas must be undertaken. A suitably qualified professional must supervise the rehabilitation and monitoring activities.
 - Designate the wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline).
 - The status quo in terms of hydrological connection from Erf 1486 to the downstream system must be maintained / should not be impacted because of the proposed development.
 - If possible, conduct construction activities of dwellings, associated stormwater infrastructure and any rehabilitation activities during summer months (November to March).
 - Ensure that effective stormwater management measures are implemented during construction. Stormwater management must ensure that no runoff, which will impair the water quality and lead to increased sedimentation, may enter the downstream wetland area. Additionally, clean SW which does enter the downstream wetland system should do so in a manner that ensures no erosion occurs, specifically during storm events, such as through vegetated swales.
 - Appropriately designed raft foundations for residential dwellings may significantly reduce the impact on subsurface flow and therefore reduce this impact / risk.
 - Rainwater harvesting schemes may reduce runoff intensity and thereby mitigate the impact of catchment hardening.
 - The alien invasive vegetation present within the wetland area must be removed and replanted with indigenous wetland vegetation.
 - Designate the wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline).

- The site manager / ECO must check the No Go area for pollution/spills, erosion damage and sedimentation weekly and after every heavy rainfall event. Should pollution, erosion or sedimentation be noted, immediate corrective measures must be undertaken.
- Fuel, chemicals, and other hazardous substances should preferably be stored offsite, or as far away as possible from the no-go area. These substances must be stored in suitable secure weather-proof containers with impermeable and bunded floors to limit pilferage, spillage into the environment, flooding, or storm damage.
- Inspect all storage facilities, vehicles, and machinery daily for the early detection of deterioration or leaks and strictly prohibit the use of any vehicles or machinery from which leakage has been detected.
- Mixing and transferring of chemicals or hazardous substances must take place outside of the No Go area, and must take place on drip trays, shutter boards or other impermeable surfaces.
- Drip trays must be utilised at all fuel dispensing areas; and during the maintenance of existing sewer flow as possible.
- Vehicles and machinery should preferably be cleaned off site. Should cleaning be required on site it must only take place within designated areas outside of the No Go area and should only occur on bunded areas with a water/oil/grease separator.
- Dispose of used oils, wash water from cement and other pollutants at an appropriate licensed landfill site.
- Avoid the use of infill material or construction material with pollution / leaching potential. Where possible, in situ earthen materials must be used during construction to reduce the risk of leachate from imported materials contaminating the wetland area.
- Concrete should preferably be imported as “ready-mix” concrete from a local supplier. Should onsite concrete mixing be required it must not be done on exposed soils. Concrete must be mixed on an impermeable surface in an area of low environmental sensitivity identified by the ECO outside of the no-go area. Surplus or waste concrete must be sent back to the supplier who will dispose of it.
- Construct temporary bunds around areas where cement is to be cast in situ.
- Dispose of concrete and cement-related mortars in an environmental sensitive manner (can be toxic to aquatic life). Disposal of any of these waste materials into the No Go area is strictly prohibited.
- Washout must not be discharged into the no-go area. A washout area should be designated, and wash water should be treated on-site.
- Clean up any spillages immediately with the use of a chemical spill kit and dispose of contaminated material at an appropriately registered facility.
- Provide portable toilets where work is being undertaken (1 toilet per 10 workers). These toilets must be located within an area designated by the ECO outside of the no-go area and should preferably be located on level ground. Portable toilets must be regularly serviced and maintained.
- Provide an adequate number of bins on site and encourage construction personnel to dispose of their waste responsibly.
- Waste generated by construction personnel must be removed from the site and disposed of at a registered waste disposal facility on a weekly basis.
- Prohibit littering and dumping within the wetland area. Clear and remove any rubble or litter that may have been accidentally deposited into the wetland and dispose of at an appropriate registered facility. Monitoring of litter/dumping within the wetland must be managed by a Homeowners Association (HoA).
- Care should be taken to not disturb indigenous wetland vegetation during any maintenance of the pipeline.
- In line with the NEMBA, all AIPS listed under the amended AIPS Lists (DEFF: GN1003, 2020) must either be removed or controlled on land under the management of the proponent.
- Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings).

- Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings).
- Runoff from the proposed development must not increase from the pre-development to the post-development scenario.
- The status quo in terms of hydrological connection from Erf 1486 to the downstream system must be maintained / should not be impacted because of the proposed development.
- Discharge stormwater from rooftops into rain harvesting tanks. This will limit the volumes of stormwater runoff that will reach the wetland area. Where possible, water collected in rain harvesting tanks can be utilized for flushing of toilets, washing etc.
- Stormwater runoff should preferably be discharged as diffuse flow into well vegetated areas outside of the wetland.
- Energy dissipaters / erosion protection measures (such as lining with stones, grass, reno-mattresses, or gabions) must be constructed where stormwater is released to reduce the runoff velocity and therefore erosion.
- Sheet runoff from hardened surfaces must be intercepted and the treatment and infiltration of runoff must be promoted.
- Sediment traps should be incorporated into stormwater drains / swales upstream of any discharge points.
- Monitor the wetland area for erosion and sedimentation after heavy rainfall events. Any erosion noted must be immediately addressed. Rehabilitation measures may include the removal of accumulated sediment by hand, filling of erosion gullies and rills, the stabilisation of gullies with silt fences, riprap, and the revegetation of stabilised areas.
- Stormwater systems will require ongoing maintenance. Any build-up of silt or debris within stormwater drains or swales will need to be cleared to ensure the continued functioning of the systems.
- Any damage to stormwater infrastructure, and any flaws identified in the functionality of stormwater infrastructure, must be rectified immediately.
- Appropriately designed raft foundations for residential dwellings may significantly reduce the impact on subsurface flow and therefore reduce risk.
- Rainwater harvesting schemes may reduce runoff intensity and thereby mitigate the impact of catchment hardening.
- Design a SWMP which will allow for the infiltration and treatment of stormwater. All stormwaters must receive basic filtering and treatment prior to its release.
- Incorporate measures into the stormwater design to trap solid waste, debris and sediment carried by stormwater. Measures may include the use of curb inlet drain grates and debris baskets/bags.
- Stormwater generated from areas with a higher risk of contamination such as parking areas and roads (as applicable) must receive basic filtering and treatment prior to its release into surrounding areas.
- Stormwater systems must be monitored and maintained into perpetuity and collections of debris and solid waste removed from grates and baskets. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles (likely HoA).
- Operational phase mitigation implemented during the design/construction phase:
 - Construct sewage pipelines in accordance with the relevant SANS / SABS specifications.
 - Design the pipelines to accommodate the operating and surge pressures.
 - Provide surge protection e.g. air valves.
 - Allow for scour valves along pipelines to ensure sewage pipelines can be emptied in a controlled manner if required.
 - Allow for surcharge containment and emergency storage of 2 hours of peak flow at manholes located within areas upslope of the wetland. Containment/emergency storage may include a concrete box or earthen bund surrounding the manholes. The backup storage capacity of manholes may also be improved by raising the manholes by one meter.

- Repair all sewage leaks as soon as reasonably possible after detection. Inspection of all sewage pipes should be conducted by a plumber once every 10 years. The sewage system must be monitored and maintained into perpetuity. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles.
- The sewage system must be monitored and maintained into perpetuity. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles.
- The wetland area must be regularly inspected for waste. Any waste or litter noted must be immediately removed and disposed of at a registered waste disposal facility. The developer must confirm who will be responsible for this monitoring of the wetland area (HoA).
- The wetland area must be regularly inspected for waste. Any waste or litter noted must be immediately removed and disposed of at a registered waste disposal facility. The developer must confirm who will be responsible for this monitoring of the wetland area (HoA).

Terrestrial Faunal compliance statement:

The following mitigation measures are recommended for this development.

- During the construction phase the construction area should be clearly demarcated and blocked off from the 'private open space' area to avoid damage and pollution.
- Pre and post construction site preparation should include rehabilitation of the 'private open space' by removing current building rubble and litter from this area.
- Long term maintenance of ecological integrity of the 'private open space' is critical. Therefore, measures should be put in place for constant removal of alien vegetation, cleanup of litter and prevention of illegal dumping. Clear legal responsibility for the maintenance of the space should be entrenched to be the responsibility of the homeowners association.
- The fence traversing the ecological corridor should always be permeable to allow for movement of small sized animals e.g. small antelope, genets, mongoose between the nature reserve and wetland system.
- Search and Rescue of chameleons and other slow-moving animals is feasible due to the presence of the adjacent nature reserve where they can be released. A search and rescue effort should be implemented before and during construction where animals that are found are released in the adjacent nature reserve. The necessary permission and permits should be attained before this is done.
- Pets (especially domestic cats) should not be allowed to free-roam the 'private open space'.

Wetland Offset, Rehabilitation and Management Plan

Recommended Mitigation Measures

Rehabilitation mitigations

- Application of maximum viable rehabilitation effort to increase the PES of the onsite offset wetland area to upper category C with a minimum PES Score of 79 %.
- Removal of dumped rubble and fill material within the wetland. Reshaping of the wetland specifically in the areas where infill has been removed to ensure very slight gradual decline towards the permanent zone.
- Removal of all Alien Invasive vegetation Species (AIS) from this offset wetland area such as Kikuyu grass (*Cenchrus clandestinum*), Pampas grass (*Cortaderia selloana*), Australian myrtle (*Leptospermum laevigatum*), sweet needlebush (*Hakea drupacea*), Port Jackson (*Acacia saligna*) and rooikrans (*Acacia cyclops*), as well as all planted garden species in the southwest corner of the Erf coinciding with the wetland.

- Establishment of a healthy and moderately diverse indigenous vegetation community within any areas that have been cleared (areas historically cleared of indigenous vegetation and cleared of AIS) as well as the areas where infill / rubble has been removed within the offset wetland area. Revegetate with indigenous wetland plant species based on the relevant species list (refer to **Table 8-1** of the Wetland Offset, Rehabilitation and Management Plan);
- Implementation of the Stormwater Mitigation measures outlined in the Wetland Offset, Rehabilitation and Management Plan.
- Ensuring that the onsite offset area is managed in accordance with this plan, such that the rehabilitated state is maintained in perpetuity.

Recommended mitigation measures to be included in the Stormwater Management Plan:

- Discharge stormwater from rooftops into rain harvesting tanks. This will limit the volumes of stormwater runoff that will reach the wetland. Where possible, water collected in rain harvesting tanks can be utilised for flushing of toilets, washing etc.
- Vegetated swales must be utilised rather than concrete drains or underground stormwater pipes in order to encourage infiltration, particularly next to roadways.
- Energy dissipaters / erosion protection measures (such as lining with stones, grass, reno-mattresses, or gabions) must be constructed where stormwater is released in order to reduce the runoff velocity and therefore erosion.
- Sheet runoff from hardened surfaces must be intercepted and the treatment and infiltration of runoff must be promoted.
- Sediment traps should be incorporated into stormwater drains / swales upstream of all discharge points into the wetland.
- All stormwater draining into the wetland must receive basic filtering and treatment prior to its release.
- Incorporate measures into the stormwater design to trap solid waste, debris and sediment carried by stormwater. Measures may include the use of curb inlet drain grates and debris baskets/bags.
- Stormwater generated from areas with a higher risk of contamination such as parking areas and roads must receive basic filtering and treatment prior to its release into surrounding areas. Treatment methods may include sand filter traps and oil-water separators which will require maintenance.
- The extent of hardened surfaces must be minimised. E.g. where required permeable paving must be used.
- Homeowners must be encouraged to landscape their gardens with the use of indigenous species to decrease the area of hardened surface and increase infiltration.
- Homeowners should store any potential pollutants in such a way that pollution will not occur to the wetland (such as any fuel, etc.). Potential pollutants should be stored in an adequately bunded area.
- The use of herbicides, pesticides and any other poisons within private gardens must be strictly prohibited. The homeowner's association must be responsible for ensuring that residents are compliant with this.
- Backwashing of swimming pools directly into the wetland must be strictly prohibited. Backwash water can be collected in settling tanks where dirt and debris settle to the bottom. The cleaner water can then be reused for non-potable purposes or even filtered back into the pool system. Backwash water can be diverted to greywater tanks.
- Monitor the proposed development and adjacent wetland for erosion and sedimentation after heavy rainfall events. Any erosion noted must be immediately addressed. Rehabilitation measures may include the removal of accumulated sediment by hand, filling of erosion gullies and rills, the stabilisation of gullies with silt fences, riprap, and the revegetation of stabilised areas.
- Stormwater systems will require ongoing maintenance. Any build-up of silt or debris within stormwater drains or swales will need to be cleared to ensure the continued functioning of the systems.
- Any damage to stormwater infrastructure, and any flaws identified in the functionality of stormwater infrastructure, must be rectified immediately.

- Stormwater systems must be monitored and maintained into perpetuity and collections of debris and solid waste removed from grates and baskets. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles.
- The stormwater system must be designed by a suitably qualified engineer with input from an aquatic specialist.

Stormwater Management Plan

Mitigation measures through Low Impact Development (LID)

- Installation of Permeable Paving (South of Wetland): 2114 m² area, reduces runoff (e.g., Q100: 3.10 m³/s) and treats water (50% TP, 65% TN, 60% heavy metals reduction).
- Installation of Enhanced Swale (North of Wetland): 5283 m² area, further reduces runoff and matches water quality targets.
- Culvert Management: Control runoff from CA1 through a 2x900 mm pipe to prevent flooding.

- | | |
|----|--|
| 3. | List the specialist investigations and the impact management measures that will not be implemented and provide an explanation as to why these measures will not be implemented. |
|----|--|

N/A

- | | |
|----|---|
| 4. | Explain how the proposed development will impact the surrounding communities. |
|----|---|

- The subdivision and development will create new residential erven. This responds to the growing demand for housing in the Vermont area, a coastal region within the Overstrand Municipality experiencing population growth and tourism-driven development pressures.
- The development will attract new residents, including permanent residents, retirees, or seasonal homeowners, contributing to the area's demographic diversity. This aligns with regional planning goals to accommodate urban expansion in the Western Cape.
- The development will create temporary jobs during construction, including opportunities for unskilled labour (e.g., site clearing, landscaping, general labour) and skilled roles (e.g., builders, engineers). This benefits unemployed or underemployed individuals in nearby communities like Hermanus, Hawston, and Zwelihle, where unemployment rates are significant.
- Post-construction, the Homeowners Association (HOA) and ongoing maintenance (e.g., wetland rehabilitation, alien vegetation control, stormwater system upkeep) will generate jobs for local workers, such as gardeners, cleaners, and maintenance staff.
- Wages earned by local workers will circulate in the community, supporting local businesses (e.g., shops, transport) and improving household livelihoods.
- The development will increase the supply of residential properties, attracting investors interested in Vermont's coastal appeal and proximity to Hermanus. This could boost property values in the area, benefiting existing homeowners and stimulating the real estate market.
- The development will generate property rates and service fees for the Overstrand Municipality, potentially funding community infrastructure improvements (e.g sewer upgrades, roads).

- | | |
|----|--|
| 5. | Explain how the risk of climate change may influence the proposed activity or development and how has the potential impacts of climate change been considered and addressed. |
|----|--|

Extract from the Aquatic Biodiversity Impact Assessment "The wetland in question does not contain peat, however the soils present do contain high amounts of carbon. However, the wetland is small and degraded in nature. The wetland is

therefore unlikely to contribute significantly towards climatic-change resilience and limited construction within the seasonal wetland is unlikely to lead to a significant release of carbon into the atmosphere. No further assessment of potential climate impact is necessary.”

Additionally, the development incorporates stormwater management measures and structured wetland management, which enhance the site’s resilience to potential climate-related impacts such as increased rainfall intensity, erosion, and runoff. These measures ensure that the development can proceed without significant risk from climate change while maintaining the ecological function of the wetland system.

Climate Change Projections for the Overberg region

According to the Western Cape SmartAgri (Smart Agriculture for Climate Resilience) report, the Overberg region is likely to warm by between 1°C and 1.5°C by 2050, with more frequent winter droughts and an increase in heavy rainfall events during April and September. This is consistent with projections from the Western Cape Department of Agriculture (2017) and the Climate System Analysis Group, which show rising temperatures and shifting mean annual rainfall patterns across the Overberg District Municipal Area. CSIR (2019) modelling under the RCP 8.5 emissions scenario similarly projects that by 2050 the district will be affected by higher annual average temperatures, adversely affecting water and food security, with evaporation rates likely to increase and agricultural outputs likely to reduce.

These regional trends warmer conditions, more frequent winter drought, and an increase in heavy rainfall events concentrated in specific months carry direct implications for a site containing a wetland feature, given the sensitivity of wetland hydrology to both drought stress and episodic high-intensity inflow events.

Taken together, the specialist’s finding that the wetland’s contribution to climate resilience is limited, and the incorporation of stormwater attenuation measures designed to accommodate increased rainfall intensity, support the conclusion that the effect of climate change on the proposed development is unlikely to result in a significant increase in risk to the development, the wetland system, or the surrounding environment, provided the recommended stormwater management measures are implemented and maintained as designed.

6.	Explain whether there are any conflicting recommendations between the specialists. If so, explain how these have been addressed and resolved.
----	---

N/A

7.	Explain how the findings and recommendations of the different specialist studies have been integrated to inform the most appropriate mitigation measures that should be implemented to manage the potential impacts of the proposed activity or development.
----	--

The development proposal for Erf 1486 has been informed by a comprehensive suite of specialist studies, including freshwater ecology, faunal assessments, botanical assessments, and environmental planning studies. Collectively, these studies highlight the ecological and hydrological significance of the site, including its location within an Ecological Support Area (ESA2), proximity to the Vermont Salt Pan, and the presence of a degraded but functionally important wetland. Each specialist study has provided critical insights into the site’s sensitivity and informed strategies to avoid, minimize, or offset potential environmental impacts. These findings have been systematically incorporated into the development design and directly shaped the proposed mitigation measures.

The freshwater ecology studies, including the most recent assessment by Delta Ecology (2025), confirmed the presence of a seasonal unchanneled valley-bottom (UVB) wetland. Despite historical degradation from infilling and invasive alien vegetation, the wetland remains functionally important, particularly for maintaining hydrological connectivity to the Vermont Salt Pan. In response, the revised layout (Alternative 4) significantly minimises encroachment into wetland areas, especially seasonal portions. Key mitigation measures include the appointment of a HOA representative to oversee the

open space and wetland area and the implementation of a Wetland Offset, Rehabilitation and Management Plan to actively restore and maintain degraded portions of the wetland.

The botanical assessment identified remnants of Hangklip Sand Fynbos, a Critically Endangered vegetation type, on the property. Although much of the natural vegetation has been historically disturbed, ecologically significant pockets remain, particularly within the wetland zone. To mitigate the loss of these areas, the layout was revised to reduce the number and footprint of erven, retaining a larger proportion of vegetated areas within designated open space. Additional mitigation measures include alien vegetation clearing and indigenous replanting, which serve to restore ecological function and enhance the connectivity of the ecological corridor.

Overall, the integration of specialist findings has resulted in a coordinated and holistic mitigation strategy, which includes:

- Redesign of infrastructure to avoid sensitive ecological areas.
- Implementation of ecological buffers and servitudes.
- Development of detailed management and offset plans for wetland and biodiversity protection.
- Appointment of responsible parties (e.g., HOA representative) for ongoing maintenance and oversight.
- Commitment to long-term ecological monitoring to ensure compliance and adaptive management.

These integrated measures ensure that the development proceeds in an environmentally responsible manner, is legally compliant, and aligns with sustainable land-use principles, while maintaining both biodiversity and hydrological function on the site.

8. Explain how the mitigation hierarchy has been applied to arrive at the best practicable environmental option.

The mitigation hierarchy — avoidance, minimisation, rehabilitation, and offset — was applied throughout the impact assessment and layout refinement process to ensure that environmental impacts associated with the proposed development on Erf 1486 Vermont were reduced to the lowest practicable level. The evolution of layout alternatives from Alternative 1 through to the revised preferred layout (Alternative 4) reflects the progressive incorporation of specialist findings, public participation inputs, and authority feedback.

A comprehensive suite of specialist studies informed this process, including the Aquatic Biodiversity Impact Assessment, Terrestrial Biodiversity Impact Assessment, Botanical Assessment, and Faunal Assessment. These studies confirmed that the site contains a seasonal unchanneled valley-bottom (UVB) wetland, degraded patches of Critically Endangered Hangklip Sand Fynbos, and functions as part of an Ecological Support Area (ESA2) that contributes to ecological connectivity between the Vermont Salt Pan and Walker Bay Nature Reserve. The mitigation hierarchy was applied as follows:




Figure 23: Mitigation hierarchy

Avoidance

Avoidance of environmentally sensitive areas was prioritised from the outset of the planning process. Early layout alternatives (Alternative 1-2) resulted in unacceptable impacts on wetland and terrestrial biodiversity systems.

The Aquatic Biodiversity Impact Assessment confirmed the presence of a functionally important seasonal wetland system, despite its degraded condition. The wetland contributes to hydrological connectivity with the Vermont Salt Pan, and the concerns raised recommended that development footprints should be located outside the delineated wetland boundary wherever possible.

The Animal Species Assessment identified the site as part of an ESA2 ecological corridor, indicating that habitat continuity and connectivity should be maintained. The specialist recommended reducing development footprint and retaining open space to support faunal movement.

The Botanical Assessment identified remnant patches of Hangklip Sand Fynbos (Critically Endangered), particularly associated with the wetter portions of the site, and recommended that these areas be retained where possible.

These specialist findings directly informed the refinement of the layout from Alternative 1 through to Alternative 4.

- Alternative 1 did not incorporate environmental sensitivities and allowed development within the wetland.
- Alternative 2 avoided the permanent wetland but still encroached into seasonal wetland areas.
- Alternative 3 reduced impacts further but still included portions of erven within the seasonal wetland and raised concerns regarding long-term protection and management feasibility.


The revised preferred layout (Alternative 4) demonstrates the strongest application of avoidance measures by:

- Avoiding the permanent wetland entirely

- Allocating approximately 9,361 m² of the site as private open space
- Retaining the ecological corridor
- Realigning the sewer pipeline outside the wetland
- Relocating the vegetated swale system outside the wetland
- Reducing the number of erven and development footprint

Under Alternative 4, all primary residential development footprints are located outside the delineated wetland area.

However, the freshwater specialist confirmed that very minor encroachment into the outer edge of the seasonal wetland remains unavoidable, primarily associated with access infrastructure and limited erf edge intrusion. Given the small size of the property and central location of the wetland, complete avoidance is not feasible, and the remaining impact represents the minimum practicable disturbance.





Minimisation

Where complete avoidance of impact was not possible, every effort was made to minimise adverse effects. The Western Cape Biodiversity Spatial Plan (2017), referenced during the assessment, classifies the entire site as Ecological Support Area 2 (ESA2) due to its role in maintaining ecological processes and connectivity between the nature reserve and the salt pan. According to the updated WCBSP Handbook and Guidelines (2023), ESA2 areas are not essential for meeting biodiversity targets but are crucial for supporting the functionality of Protected Areas and Critical Biodiversity Areas. The guidelines state that such areas should be maintained in at least a functional, preferably natural state, though limited habitat loss may be acceptable.

Under Alternative 4, the number of residential erven has been reduced to six (6), with smaller erf sizes and an overall reduced development footprint. The final Site Development Plan (SDP) provides for two access roads: one extending northward to provide access to the northern erven, and a second access road serving the two erven located to the south. This replaces the single internal road originally proposed under Alternative 2.

These design refinements significantly minimise the extent of wetland encroachment, limiting wetland loss to approximately 0.024 ha. According to the freshwater specialist, this level of impact is considered acceptable, as the wetland loss has been reduced to the minimum practicable extent given the spatial constraints of the site.

In addition, the total loss of high-sensitivity indigenous vegetation has been substantially reduced to less than 500 m². This represents a marked improvement compared to Alternatives 1 and 2. The botanical specialist has confirmed that this level of vegetation loss falls within acceptable limits, particularly because development avoids areas identified as having confirmed conservation priority.

From a faunal standpoint, Alternative 4 provides for a private open space that facilitates a more functional ecological corridor, which represents an improvement compared to the earlier alternatives in terms of Cape Dwarf Chameleon

(*Bradypodion pumilum*) habitat functionality. The anticipated impact of development on habitat loss and movement impediment for this species is therefore has been minimised and now rated as Low to Medium after mitigation.

Engineering alternatives have also been included to minimise the impact of development on this site.

Rehabilitation

Despite minimisation efforts, the proposed access road in Alternative 4 will still result in the loss of 0.024 ha of seasonal/temporary wetland. This impact cannot be entirely mitigated on-site through design changes, as the wetland occupies much of the central and southern portions of the property. The freshwater specialist (van Zyl, 2024) confirms that further footprint reduction is not viable. Given this, wetland rehabilitation is proposed as a key mitigation measure.

The preferred and only viable approach is to implement a Wetland Offset, Rehabilitation, and Management Plan. This plan seeks to improve the Present Ecological State (PES) score of the wetland from Category D (largely modified) to Category C (moderately modified). It includes measures such as alien clearing, indigenous replanting, stormwater swale construction, and erosion control. If fully implemented, these interventions will enhance the functionality and biodiversity value of both the wetland and the surrounding open space. The freshwater specialist has deemed this an acceptable offset and rehabilitation strategy.

Offset

The Terrestrial Biodiversity Impact Assessment indicated that most vegetation on site is in a state of senescence, with many species declining due to the absence of natural ecological processes such as fire. The vegetation has not burned in over 20 years, which has altered its structure and species composition. While large areas are considered natural or semi-natural, many are no longer in optimal ecological condition.

Under the preferred layout (Alternative 4), the development now reduces the loss of high sensitivity areas, with only about <500 m² of such habitat lost primarily due to road construction. The majority of development occurs mostly on low sensitivity areas, which are already disturbed. Importantly, the revised layout preserves 58% of the site as Private Open Space, a substantial increase from the 36% in earlier layouts. This space will function both as a buffer and an ecological corridor, contributing to biodiversity conservation and connectivity on site. Therefore, significant impact rating for the preferred layout (Alternative 4) is Low Medium after mitigation. As a result a Biodiversity Offset in terms of the National Biodiversity Offset Guideline for vegetation loss, is not applicable.

Given the limited scale of wetland loss, the botanical specialist confirmed that a formal biodiversity offset for vegetation loss is not required, provided that the open space and wetland are rehabilitated and protected in perpetuity.


Long-term protection and management of the wetland and open space area will be secured through:

- Implementation of the Wetland Offset, Rehabilitation and Management Plan
- Establishment of a Homeowners Association (HoA)
- Inclusion of environmental obligations in the HoA constitution
- Levy-funded ecological management
- Ongoing ecological monitoring

These measures ensure that the offset and rehabilitation interventions are sustainable and enforceable over the long term.

It is important to note that the commitment of rehabilitation and long-term protection of the central wetland system of site allows for opportunity to reinstate the broader ecological corridor linking Walker Bay Nature Reserve to the Vermont Salt Pan and this could provide an opportunity for collaboration with adjacent landowners and local conservation groups.

Summary of the Application of the mitigation hierarchy to reach the final preferred layout Alternative 4:



SECTION J: GENERAL

1. Environmental Impact Statement

1.1.	Provide a summary of the key findings of the EIA.
The proposed development on Erf 1486, Vermont, involves the construction of residential erven, roads, and an open space on a 15069 m². The site is characterized by Hangklip Sand Fynbos, a critically endangered ecosystem gazetted under national legislation, and features a wetland delineated by the Freshwater specialist. The wetland comprises permanent and seasonal / temporary zones, with approximately 70 % of the site classified as having high ecological sensitivity due to its biodiversity and hydrological value.	
Alternative 2	
During the first round of public participation, Alternative 2 was the preferred layout. However, it faced significant opposition due to its high ecological impact. Erven 1, 2, 7, 8, 10, 11, 12, and 13 encroached near the permanent wetland zone, while Erf 14 (a road) crossed the wetland, resulting in an unacceptably high negative ecological significance. The Freshwater Specialist's assessment, including wetland delineation and a risk assessment matrix, rated the impact of wetland loss as medium to high under Alternative 2. Mitigation measures recommended removing the encroaching erven and rerouting the road to avoid crossing the wetland, which would reduce the impact to an acceptable level.	
Alternative 3	
In response to specialist findings from the Freshwater Ecologist and Terrestrial Biodiversity assessments, the layout evolved into Alternative 3, being the previous preferred option. This evolution sees the reduction of development within the areas of high ecological sensitivity, complete avoidance of the permanent wetland, and avoidance of the majority of the seasonal wetland, reducing wetland loss to 0.024 ha of a degraded portion, as noted by the aquatic specialist (van Zyl et al., 2023). This layout saw the reduction in erf numbers as well as the realignment of the internal roads. A mechanism for a conservation servitude and development exclusion zones on residential erven provide further avoidance of sensitive areas. While wetland loss typically carries a 'high' impact rating, the limited extent and degraded condition of the affected area lower the significance to an acceptable level.	
Alternative 4 – Preferred	
The residential erven now largely avoid high-sensitivity areas, with only approximately <500 m² of high-sensitivity habitat lost shifting from an unacceptable high negative impact (Alternative 2) to an acceptable low to medium impact (Alternative 4). The private access road no longer crosses the wetland, replaced by two separate access roads. The remaining delineated wetland area is designated as Private Open Space to preserve its ecological function.	
Moreover, comments received during the public participation process highlighted concerns regarding the alternative option for the sewer pipeline alignment, which traversed the wetland area. In response, the sewer pipeline has been realigned under the revised preferred layout (Alternative 4) to run parallel with the water pipeline route, thereby completely avoiding the delineated wetland. This adjustment directly addresses the concerns raised and ensures that unnecessary impacts on the wetland system are prevented.	

Aquatic Biodiversity Impact Assessment

- A natural Unchanneled Valley-Bottom (UVB) wetland, confirmed and delineated over the years by various experts, most recently by van Zyl (2023). This wetland, part of a 1.4 km system feeding into the Vermont Salt Pan, has been shaped through excavated depression with an overflow pipe under Lynx Road, a stormwater outlet from the neighbouring residential development, and patches of alien Kikuyu grass crowding out native plants.
- The assessment utilised WET-Health tools to assess the wetland Present Ecological State (PES) which was found to fall under Category D indicating largely modified state, with a combined score of 58%. Past excavations, vegetation clearing, and urban runoff have altered its flow, geomorphology, and water quality, though some wetland plants like *Juncus kraussi* and *Typha capensis* still persist.
- The wetland Ecological Importance and Sensitivity (EIS) scored a moderate 2.0, reflecting its role in a Critically Endangered Southwest Sand Fynbos system and potential as a habitat for species like the Vulnerable Cape Dwarf Chameleon, even though no rare species were spotted onsite.
- The Wetland Ecosystem Services (WES) assessment showed moderately high value of the wetland for trapping sediment and toxins though its small size and condition limit broader benefits like flood control. The Recommended Ecological Category (REC) suggests maintaining its current D status, though rehabilitation efforts if feasible may promote its REC to C status.
- The development's impacts were scrutinized across construction and operational phases, focusing on the preferred layout (Alternative 4), which minimizes wetland encroachment to about 0.024 hectares (3%) of the seasonal/temporary zone.
- Impacts from Alternative 4, including Medium-rated wetland loss and Low-rated flow and water quality changes post-mitigation, are addressed through measures such as No-Go zones during construction, swales, and invasive species removal, replanting of indigenous vegetation, rehabilitation efforts as well as stormwater management plan.
- Operation phase activities such as sewage leaks or runoff pollutants are manageable with quick repairs regular pipe checks, supported by rehabilitation efforts that could avoid such effects.
- The No-Go scenario would result to Very-low negative impact as the wetland slowly degrades under existing pressures due to invasion by alien plants, and stormwater runoff.
- The Moderate risk rating of the development for wetland loss requires a Water Use License under GN509, plus an on-site wetland offset plan to align with the "no net loss" policy. The Wetland Offset, Rehabilitation, and Management Plan targets the remaining 0.9361 ha, projecting a net gain in function (0.1075 Hectare Equivalents) and habitat (1.2518 HE) via rehabilitation, aiming to elevate the PES to Category C and secure "no net loss" compliance.
- The revised site layout (Alternative 4) has been refined to increase the extent of open space associated with the central wetland and ecological corridor. A considerable portion of the site is retained as private open space, thereby maintaining ecological connectivity across the property and reducing potential disturbance to sensitive habitats. The central wetland area was previously mapped by the botanical specialist as having high ecological sensitivity, and this area is retained within the designated open space. Consequently, the residential erven have been positioned within lower sensitivity areas that are already disturbed and dominated by alien vegetation, particularly *Cenchrus clandestinus* (kikuyu grass), minimising direct impacts to intact wetland and associated habitat.
- All the potential impacts to the UVBW were the lowest (both prior, and after, the implementation of mitigation measures) for Alternative Layout 3 and 4. The revised layouts represent a refinement of previously assessed layouts and incorporates a larger open space area surrounding the delineated wetland. These two layouts are preferred from an aquatic perspective, as it entails all proposed residential erven to be located outside the

delineated permanent wetland area. The revised layouts further reduce potential encroachment into the seasonal wetland zone, with only minor edge encroachments associated with the northern erven.

Terrestrial Animal Site Sensitivity Verification Report and Species Specialist Assessment Report

- The site visit, supported by a desktop study using iNaturalist and GBIF records, aimed to confirm the presence of eight Species of Conservation Concern (SCC) identified by the screening tool which includes five birds (Black Harrier, African Marsh Harrier, Martial Eagle, Denham's Bustard, Hottentot Buttonquail), one additional bird (Striped Flufftail), one reptile (Southern Adder), and one invertebrate (Yellow-winged Agile Grasshopper) plus an additional near-threatened species, the Cape Dwarf Chameleon, identified during the desktop review.
- The Terrestrial Animal Site Sensitivity Verification rated the site's overall Site Ecological Importance (SEI) as Medium, driven by connectivity functions and habitat suitability for the Vulnerable Cape Dwarf Chameleon, though no Species of Conservation Concern (SCC) were observed onsite.
- Limited bird and reptile observations, 14 common species (e.g., Cape Spurfowl, Yellow-billed Duck, Cape River Frog, Four-striped Field Mouse) were recorded, none of which are SCC. The desktop study, however, confirmed regional records of the listed SCC, suggesting potential use of the site by some species. The project area of influence (PAOI) was set at a 100-meter buffer around the development footprint, excluding buildings and main roads, to assess impacts on herpetofauna, particularly the Cape Dwarf Chameleon.
- Applying the Site Ecological Importance (SEI) methodology from SANBI (2020), the report evaluated the site's biodiversity importance (BI) and receptor resilience (RR) for each SCC and connectivity functions. The overall SEI for the PAOI was rated "Medium," driven primarily by two factors: connectivity for animal species and habitat suitability for the Cape Dwarf Chameleon, which was not observed on site.
- The current preferred layout (Alternative 4) includes very minor encroachment into the edge of the seasonal wetland to accommodate the internal access road and some erven. However, the impacts are significantly reduced compared to the previous layout (Alternative 3). The ecological connectivity of the site has been rated as Medium in terms of its Site Ecological Importance (SEI), reflecting moderate conservation value and low resilience to further fragmentation. This rating highlights the need for mitigation measures to maintain faunal movement and ensure continued ecological connectivity across the site, which has been achieved through these refinements.
- For the SCC birds, the assessment found minimal impact. The Black Harrier, African Marsh Harrier, and Martial Eagle, all endangered, may forage onsite, but the small development footprint and retained open space mean habitat loss is insignificant relative to their wide ranges, earning a "Low" SEI rating.
- Denham's Bustard and Hottentot Buttonquail, also endangered, are unlikely to occur due to unsuitable dense wetland vegetation, resulting in a "Very Low" SEI.
- The Striped Flufftail, rated "Low" SEI, has marginally suitable habitat, but its presence couldn't be confirmed (call playbacks were inconclusive due to wind), and adjacent habitats offer refuge if present.
- The Southern Adder and Yellow-winged Agile Grasshopper, both vulnerable, were deemed absent due to unsuitable wetland-dominated conditions, also receiving a "Very Low" SEI.
- In contrast, the Cape Dwarf Chameleon, confirmed in the immediate vicinity, faces a "Medium" SEI due to suitable breeding and foraging habitat onsite, with permanent habitat loss and construction disturbance posing risks, though nearby reserves provide escape routes.
- Recommended mitigation measures include demarcating construction zones to protect the open space, rehabilitating it by removing rubble and alien vegetation, ensuring permeable fencing for small animal movement, and conducting a pre-construction search-and-rescue for chameleons and slow-moving species, with releases into the adjacent nature reserve.
- Long-term maintenance by a homeowners' association and restrictions on free-roaming pets (e.g., cats) were also advised.
- Post-mitigation, residual impacts remain "**Low Medium**," but the measures enhance ecological functionality.

Terrestrial Biodiversity Impact Assessment

- The site originally supports Hangklip Sand Fynbos, a Critically Endangered vegetation type with less than 68% of its historical extent remaining and under 18% conserved nationally.
- The site visit on 23 May 2023 revealed a landscape shaped by a central, unchanneled valley-bottom wetland covering about 70% of the property, bordered by senescent fynbos unburnt for over 20 years and disturbed patches dominated by alien invasive Kikuyu grass. This wetland, mapped as an Ecological Support Area (ESA2) in the CapeNature Spatial Biodiversity Plan, serves as a vital ecological corridor linking the Hoek van der Berg Private Nature Reserve to the west with the Vermont Salt Pan to the east, a role underscored by its role as a primary water source for the pan.
- The initial botanical survey identified no plant Species of Conservation Concern (SoCC) onsite, though *Disa hallackii* (Endangered) may occur, given records from nearby similar habitats and its fire-dependent nature, potentially masked by the site's long unburnt state.
- Faunal observations included common species like painted reed frogs (*Hyperolius marmoratus*) and clicking stream frogs (*Strongylopus grayii*), with the Cape Dwarf Chameleon (*Bradypodion pumilum*, Vulnerable) likely present based on regional iNaturalist records.
- Two endangered birds, such as African Marsh Harrier (*Circus ranivorus*) and Black Harrier (*Circus maurus*) may forage onsite occasionally, though their wide ranges suggest minimal reliance on this small area.
- The Southern Adder (*Bitis armata*, Vulnerable), flagged by the DFFE Screening Tool, was deemed unlikely due to unsuitable wetland conditions.
- About 70% of the site was classified as High ecological sensitivity, driven by its Critically Endangered vegetation, wetland presence, and corridor function.
- The original layout assessed in May 2023 (Alternative 2) proposed erven and an access road encroaching significantly into High sensitivity areas, including the wetland, leading to a High negative ecological impact rating for both construction and operational phases before mitigation.
- Construction impacts included permanent loss of Critically Endangered vegetation and faunal habitat across eight erven (1, 2, 7, 8, 10, 11, 12, 13) and the access road (erf 14), affecting slow-moving species like frogs and the Cape Dwarf Chameleon, which may occur onsite.
- The No-Go alternative maintaining the status quo with minor alien vegetation management was strongly preferred, which is rated Neutral to Low negative.
- The specialist recommendations emphasised avoidance, requiring removal of erven 1, 2, 7, 8, 10, 11, 12, and 13 and rerouting the access road to avoid the wetland, reducing direct impacts to an acceptable Medium negative. Additional mitigation included prohibiting infrastructure across High sensitivity areas, using permeable fencing, pegging boundaries to limit disturbance, and removing alien invasives pre-construction using best practices (Martens et al., 2021). Without these changes, the project was deemed ecologically unacceptable. The report concluded that while the site's High sensitivity warranted protection, a revised layout adhering to these measures could balance development and conservation.
- The botanical specialist reviewed Alternative 4, a refined layout responding to the initial concerns. This version excludes most High sensitivity areas from residential erven, limiting habitat loss to approximately <500 m², and introduces two access roads to avoid crossing the wetland, aligning with Helme's mitigation requirements.
- The private open space increases to 58% of the erf (up from 36%), enhancing conservation potential. Consequently, the ecological significance drops from an unacceptable High negative (Alternative 2) to an acceptable Low to Medium negative (Alternative 4), making the project viable with proper mitigation.
- All prior mitigation measures remain, with an added requirement: the Homeowners Association (HoA) must annually remove alien invasive vegetation from the open space, per NEMBA legislation and Martens et al. (2021) guidelines, with adequate funding secured.
- The specialist supports proceeding with Alternative 4, provided these measures are fully implemented.

Stormwater Management Findings

- The Stormwater Management Plan for Erf 1486 prepared by DECA Consulting Engineers provides a comprehensive approach to managing stormwater for the proposed residential development.
- The site is located at the corner of the R43 and Lynx Avenue in Vermont, in a notably flat terrain, with a wetland area present on site and drains eastward into the Vermont Salt Pan (wetland area). Given its position within a larger catchment that includes steep mountainous terrain to the north, the report emphasizes the need to address both the quantity and quality of stormwater runoff in order to protect the proposed development and the receiving environment. This is particularly critical as the site forms only a small part of the broader catchment, meaning upstream flows significantly influence local conditions.
- One of the most noticeable results is the minimum difference between pre- and post-development peak flow runoff for the site in question (Catchment Area 2, south of the R43), where numbers show only slight reductions post-development (e.g., Q50 from 0.76 m³/s to 0.75 m³/s).
- However, when considering the natural attenuation provided by the wetland (approximately 10,000 m²), the report highlights a slight increase in runoff through the Lynx Avenue culvert post-development (e.g., Q50 rising from 2.491 m³/s to 2.575 m³/s). To address this, the plan proposes Low Impact Development (LID) methods, specifically permeable paving to the south of the wetland area and an enhanced swale system to the north of the wetland, which will effectively reduce post-development runoff to pre-development levels or lower (e.g., Q50 reduced to 2.45 m³/s with LID).
- This complies with the policy of the City of Cape Town to have a 50-year return interval peak flow equal to existing conditions.
- The report also covers water quality, a key consideration as the site is located next to the wetland. The City of Cape Town Management of Urban Stormwater Impacts Policy stipulates an 80% removal of suspended solids (SS) and a 45% removal of total phosphorus (TP) for a 1-in-2-year storm event.
- The proposed permeable paving and upgraded swale systems meet these requirements, offering a 50% reduction in TP, 65% in total nitrogen, and 60% in heavy metals, although specific SS reduction figures are not provided. These systems, detailed with technical specifications like a 400 mm storage height and 43% void ratio, are designed to filter runoff effectively, balancing on-site and regional treatment as required by the policy.
- Another critical finding is the management of stormwater crossing the R43 from the northern mountainous catchment (Catchment Area 1). This area, unaffected by the development, discharges stormwater through culverts into the site, posing a flood risk.
- The plan includes controlling this flow with either twin 900 mm diameter pipes through Erf 1486, ensuring safe passage of stormwater to the wetland. Furthermore, it recommends elevating properties by a minimum of 1.0 m above the wetland elevation to offer flood protection, a practical measure given the slight water level increases post-development (e.g., Q100 rising from 0.67 m to 0.69 m) which would be reduced back to 0.67 m with LID.
- Lastly, the plan emphasises the importance of ongoing maintenance to sustain these systems. For the permeable paving, monthly checks and vacuum sweeping three to four times a year are advised, while the enhanced swale requires regular inspection of vegetation, soil filtration, and debris removal. These measures ensure long-term functionality and environmental protection.

Wetland Offset, Rehabilitation and Management Plan

- After exploring various layout options, the preferred development plan (Alternative 4) minimizes wetland impact by limiting encroachment to the eastern and southern boundary access roads, resulting in a loss of approximately 0.024 hectares or 3% of the wetland. However, the assessment found that completely avoiding wetland loss was unfeasible due to the wetland's extensive coverage across the site, even with a reduced footprint.

- Applying the mitigation hierarchy fully, specialists determined that some wetland loss was unavoidable, though it had been reduced as far as practically possible. To address this, Delta Ecology was tasked with developing a comprehensive Wetland Offset, Rehabilitation, and Management Plan. This plan identifies the remaining 0.9361 hectares of the onsite wetland as the offset area, detailing rehabilitation and management actions to compensate for the loss while aligning with national offset guidelines (Macfarlane et al., 2016).
- Using the Macfarlane et al. (2016) wetland offset calculator, the lost wetland portion was valued at 0.0139 Hectare Equivalents (HE) of function and 0.1323 HE of habitat. Rehabilitation of the remaining wetland, through measures like removing foreign fill material, controlling alien invasive species (e.g., Kikuyu and Pampas grass), and revegetating with indigenous species, is projected to yield a gain of 0.1214 HE of function and 1.3841 HE of habitat. This results in a net surplus of 0.1075 HE of function and 1.2518 HE of habitat, exceeding the offset requirements.
- At the time of assessment, the wetland's Present Ecological State (PES) was Category D (largely modified), but the proposed interventions aim to elevate it to an upper Category C (moderately modified), enhancing its ecological health and functionality.
- The rehabilitation measures include practical steps such as clearing dumped rubble, reshaping the wetland profile, and implementing stormwater management to mitigate runoff impacts from the development.
- Revegetation will involve planting locally indigenous species, targeting 80% vegetation cover within 8-12 months, while ongoing management will ensure these gains are sustained.
- The plan also recommends formal protection of the wetland via a conservation servitude, preventing future development.
- Specialists concluded that this approach is implementable without compromising the development's feasibility, offering substantial biodiversity gains.

- | | |
|------|---|
| 1.2. | Provide a map that that superimposes the preferred activity and its associated structures and infrastructure on the environmental sensitivities of the preferred site indicating any areas that should be avoided, including buffers. (Attach map to this BAR as Appendix B2) |
|------|---|

See **Appendix D.**

- | | |
|------|---|
| 1.3. | Provide a summary of the positive and negative impacts and risks that the proposed activity or development and alternatives will have on the environment and community. |
|------|---|

ALTERNATIVE ONE

Positive:

- Alternative 1 offers socio-economic advantages by supplying residential erven to meet the high demand for housing in Vermont and Hermanus, fostering infill development within a growing urban area.
- Investment in the local economy, including potential upgrades or contributions to service infrastructure such as water and sewer systems.
- Job creation during construction and related activities would provide short-term employment opportunities, benefiting the community.

Negative:

- This alternative is severely flawed due to its complete disregard for the onsite wetland, a critical feature delineated as part of a 1.4 km system feeding the Vermont Salt Pan.
- The layout lacks any provision for wetland protection, risking total loss of its hydrological and ecological functions, including sediment trapping and habitat provision for species like the Vulnerable Cape Dwarf Chameleon.
- It offers no opportunity for wetland rehabilitation or long-term management to enhance connectivity with adjacent freshwater ecosystems, such as the Salt Pan and Hoek van der Berg Private Nature Reserve. This

approach would likely result in a High negative ecological impact, contravening NEMA principles and triggering significant regulatory hurdles, including the need for a Water Use Licence (GN509) without mitigation or offset feasibility.

ALTERNATIVE TWO

Positive:

- Supply of residential erven to Vermont and Hermanus in response to large demand for residential opportunities.
- Investment in the area
- Upgrade and / or contribution to service infrastructure in the area
- Job creation
- Opportunity to rehabilitate the wetland and provide long term management as well as facilitate connection with the surrounding freshwater ecosystems
- Management of activities on site and not adhoc use as currently experienced

Negative:

- Erven 1, 2, 7, 8, 10, 11, 12, and 13 encroach into the wetland's seasonal/temporary zone, while erf 14 (a private road) crosses its permanent zone, earning a High negative ecological impact rating from Helme (2023) and a Medium to High wetland loss risk from van Zyl et al. (2023). This crossing disrupts hydrological connectivity to the Salt Pan, altering flow regimes and impairing ecosystem services like water quality regulation.
- Permanent loss of Critically Endangered Hangklip Sand Fynbos and habitat for slow-moving fauna (e.g., frogs, Cape Dwarf Chameleon) is a major concern, with the Terrestrial Biodiversity Assessment noting a 50% reduction in the wetland corridor's width, exacerbating fragmentation.
- Community risks include potential flooding or water quality issues downstream if mitigation fails, though these are less pronounced than ecological impacts.

ALTERNATIVE THREE

Positive:

- Alternative 3 delivers socio-economic gains, providing housing for new residents amid high demand, attracting investment, and creating jobs during construction and operational phases.
- Infrastructure upgrades, notably a sewer system upgrade from 110 mm to 160 mm diameter pipelines, enhance service capacity for the surrounding area.
- The layout excludes most High ecological sensitivity areas, limiting wetland loss to 0.024 ha and conserving a total of 0.9361 ha erf as Private Open Space.
- This design, shaped by specialist input, supports wetland rehabilitation targeting a PES shift from Category D to C and long-term management, including alien vegetation removal and stormwater control via permeable paving and vegetated swales.
- The Wetland Offset Plan ensures a net ecological gain (0.1075 Hectare Equivalents function, 1.2518 HE habitat), aligning with the "no net loss" policy and enhancing connectivity to the Salt Pan and nature reserve.
- Community benefits include improved environmental quality and potential flood protection from elevated properties and Low Impact Development (LID) measures.
- Opportunity for reinstatement of the broader ecological corridor and link between the Vermont Salt Pan and Hoek van der Berg in conjunction with the neighbouring landowners and local conservation bodies.

Negative:

- Despite its refinements, Alternative 3 entails a minimal wetland loss of 0.024 ha (seasonal zone), rated Medium post-mitigation due to the affected area's degraded state.
- The Terrestrial Biodiversity Assessment notes a loss of 500 m² of High sensitivity habitat which is far less than Alternative 2 impact, potentially affecting the Cape Dwarf Chameleon, though mitigated by search-and-rescue and permeable fencing (Venter, 2024).
- Construction-phase risks include temporary disturbance to fauna and water quality, manageable with No-Go zones and swales.
- Post-construction phase impacts such as sewage leaks or runoff pollutants pose Low risks, which are addressed by regular maintenance and rehabilitation efforts.
- Community risks are minimal, though long-term success hinges on Homeowners Association diligence in managing the open space.

ALTERNATIVE 4(PREFERRED)

Positive

- Provides residential erven to meet the high demand in Vermont and Hermanus, supporting urban infill development.
- Promotes investment in the local economy and contributes to municipal service upgrades.
- Job creation during construction and operational phases, providing short- and long-term employment opportunities.
- Minimises impacts on the wetland, with only minor encroachment for the access road, compared to previous layouts.
- Consolidates larger open space areas for ecological connectivity and wetland protection
- Supports long-term wetland management and rehabilitation, including alien vegetation removal, indigenous planting, and monitoring through the Wetland Offset, Rehabilitation and Management Plan.
- Improves ecological corridor function, enhancing connectivity to the Vermont Salt Pan and adjacent conservation areas.
- Incorporates stormwater management measures, such as permeable paving and vegetated swales, to protect water quality and reduce erosion.
- Reduced risk to faunal movement compared to Alternative 3, with measures to maintain habitat connectivity.

Negative

- Minor encroachment into the seasonal wetland edge occurs due to the internal access road, although this is minimal and considered acceptable post-mitigation.
- Construction-phase risks include temporary disturbance to fauna, vegetation, and potential sedimentation, mitigated through No-Go zones, monitoring, and best-practice construction management.
-
- Post-construction impacts rely on Homeowners Association diligence for effective wetland management and ongoing ecological maintenance; failure to manage may compromise habitat functionality.
-
- Some loss of degraded vegetation within the footprint of the minor encroachment, though offset through restoration measures.

NO GO – STATUS QUO REMAINS

Positive:

- The No-Go alternative avoids direct development impacts, preserving the site's current ecological footprint.

Negative:

- The No-Go scenario offers no active management or rehabilitation of the wetland, which is currently degraded (PES Category D) due to past excavations, alien Kikuyu grass dominance, and urban runoff.
- The Aquatic Biodiversity Assessment predicts a Very Low negative impact from continued degradation, as unregulated activities, e.g., dumping and invasive species spread persist unchecked.
- The Terrestrial Biodiversity Assessment reinforces continued degradation, noting the absence of alien vegetation control that would diminish the site's ecological value over time.
- The lack of formal conservation measures limits long-term ecological benefits, leaving the site vulnerable to incremental harm.

2. Recommendation of the Environmental Assessment Practitioner ("EAP")

2.1.	Provide Impact management outcomes (based on the assessment and where applicable, specialist assessments) for the proposed activity or development for inclusion in the EMPr
------	--

Based on the findings of the assessment and input from the relevant specialists, the following impact management outcomes are recommended for inclusion in the Environmental Management Programme (EMPr):

- Maintain and manage the designated private open space to ensure functionality of ecological corridors, with specific focus on the movement and persistence of species such as the Cape Dwarf Chameleon (*Bradypodion pumilum*).
- Implement search and rescue protocols prior to site clearance, with particular attention to slow-moving fauna (e.g., reptiles, amphibians).
- Control and progressively remove invasive alien plant species, replacing them with suitable indigenous vegetation to improve habitat quality.
- Ensure all boundary and internal fencing is fauna-permeable to prevent movement impediments.
- Avoid solid walls or impermeable barriers in the development layout where possible.
- Design and manage stormwater outlets with erosion and litter prevention measures to avoid degradation of downstream wetlands.
- Retain natural drainage lines and buffers where feasible, ensuring no direct discharge of untreated stormwater into sensitive habitats.
- Clearly demarcate all no-go areas (private open space, wetland buffer zones, and sensitive vegetation) before commencement of construction.
- Implement strict construction site protocols, including waste management, dust suppression, and spill prevention.
- Develop and implement a maintenance plan for the private open space to ensure continued ecological functionality post-construction.
- Monitor faunal movement and vegetation condition at set intervals to confirm effectiveness of mitigation measures.

- A Homeowners Association (HoA) shall be established prior to the transfer of any residential erven within the development.
- The HoA shall be legally constituted and shall include, within its constitution and governance rules, binding provisions for the protection, rehabilitation, management, and monitoring of the wetland, ecological corridor, and open space areas identified in the approved Site Development Plan (Alternative 4).
- The areas identified as No-Go Areas, including the permanent, seasonal, and temporary wetland areas and associated ecological corridor, shall be:
 - clearly demarcated on the final Site Development Plan;
 - protected from any development, infrastructure installation, infilling, excavation, vegetation clearing (excluding alien clearing), gardening expansion, or disturbance; and
 - managed as natural open space in perpetuity.
- A No-Go/ Regulated Area Management Plan, forming part of the approved Environmental Management Programme (EMPr), must be incorporated into the HoA constitution and shall be binding on all current and future property owners.
- The environmental management obligations described above shall be binding on successors in title and shall be reflected in:
 - the HoA constitution,
 - sale agreements, and
 - any other legally enforceable governance instruments of the development
- Proof of the establishment of the HoA, including the approved constitution reflecting the environmental management obligations, shall be submitted to the Competent Authority prior to commencement of construction.

Terrestrial Biodiversity Impact Assessment:

Terrestrial Biodiversity Impact Assessment and its Addendum to be implemented to mitigate habitat loss, protect ecological connectivity, and manage invasive species, ensuring the development aligns with ecological sustainability principles.

Outcome:

Minimise habitat loss with High Sensitivity Areas. The objective is to prevent significant loss of high sensitivity habitats by limiting terrestrial vegetation clearance to approximately 500 m², as achieved in Alternative 4. This layout avoids the unacceptable high negative ecological impact of the original development proposal and ensures that residual impacts are maintained within a Low to Medium significance range after mitigation.

Recommended mitigation measures:

- No erven should intrude significantly into the seasonal wetland portions – no development zones on some erven as per the Regulated Areas Management Plan
- No pipelines, cabling or infrastructure should be installed across the High sensitivity areas or wetlands.
- Any boundary fencing used must be permeable to small animals at ground level.
- The authorised erf and road boundaries should be surveyed and pegged out and fenced on site prior to any site development.
- No areas of natural or partly natural vegetation should be disturbed outside the pegged/fenced out and authorised erven. No vehicular activity or dumping of material may take place outside the authorised erven or roads.

- All alien invasive vegetation should be removed from within the natural portions of the project area, prior to any authorised development. Removal of the alien vegetation must be undertaken by a trained and licensed alien vegetation removal team and must be undertaken using methodology outlined in the Best Practise Guidelines (see Martens et al 2021).
- The Homeowners Association (HoA, or similar) for the proposed development must ensure that all alien invasive vegetation (as per NEMBA legislation) is removed from the Public Open Space area on an annual basis by qualified contractors, using methodology as prescribed in Martens *et al* (2021; see below for reference). The HoA must ensure that there is adequate funding for this every year.
- Areas outside the designated road and residential erf boundaries should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way. Landowners and the HoA must be made aware of these constraints both prior to and after purchase.

Aquatic Biodiversity Impact Assessment:

Outcome

Rehabilitation and Long-Term Management of the Wetland and Natural Vegetation. The objective is to enhance the wetland's Present Ecological State (PES) from Category D to Category C and maintain ecological functionality of the conserved 58% Private Open Space. The below measures address the impacts associated with the Wetland loss, Altered flow regime, and Water Quality Impairment, within the UVB wetland.

Recommended mitigation measures:

Construction phase

Impact 1: Wetland Loss

- An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist – Complete, See Appendix F8.

Impact 2: Disturbance to Wetland Habitat

- Designate the UVB wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline). Clearly demarcate the construction footprint (including construction camp, access roads, stockpile areas and working servitudes) with orange hazard tape, fencing or similar prior to the commencement of any activity, and strictly prohibit the movement of construction vehicles and personnel outside of the demarcated areas.
- Locate site camps, laydown areas, stockpile areas, construction material, equipment storage areas, vehicle parking areas, bundled vehicle servicing areas and re-fuelling areas in designated areas of already hardened surface or disturbed areas located outside of the No Go area. These areas should preferably be located on level ground in a previously disturbed area of vegetation approved by the Environmental Control Officer (ECO). Cut and fill must be avoided where possible during the set-up of the construction site camp.
- Demarcation of the construction footprint/working servitude must be signed off by an ECO (or similar). Demarcation should not be removed until construction is complete, and rehabilitation (if applicable) has taken place.
- Limit access into the construction footprint to existing access roads.

- Prohibit the dumping of excavated material, building materials or removed vegetation within the No Go area. Building material must be stored at the designated storage area located outside of the no-go area. Spoil material must be appropriately disposed of at a registered waste disposal facility.
- Undisturbed topsoil and subsoils removed from the construction footprint must be stored separately at the designated stockpile area for future rehabilitation.
- Vegetation clearance should be restricted to the relevant development components and indigenous vegetation cover should be maintained as far as practically possible.
- Vegetation which is considered suitable for rehabilitation activities after construction (such as indigenous grasses and other herbaceous species) should be carefully removed from the construction footprint and stored at an appropriate facility for use in later rehabilitation activities.
- Clear and remove any rubble or litter that may have been accidentally deposited into the no-go area because of construction activities and dispose of at an appropriate registered facility.
- An ECO must inspect the construction footprint on a weekly basis and must take immediate measures to address unforeseen disturbances to the wetland. Any disturbed / compacted areas falling outside of the demarcated construction footprint must be immediately rehabilitated. Depending on the extent of damage the method of rehabilitation may require input from an aquatic specialist / suitably qualified contractor.
- Once construction has been completed, orange hazard fences as well as all construction waste, rubble, and equipment must be removed from the construction footprint.
- In line with the NEMBA, all AIPS listed under the amended AIPS Lists (DEFF: GN1003, 2020) must either be removed or controlled on land under the management of the proponent.
- An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist. Rehabilitation must take place as soon as possible after construction is completed, and monitoring of rehabilitated areas must be undertaken. A suitably qualified professional must supervise the rehabilitation and monitoring activities.

Impact 3: Altered flow regime

- Designate the wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline).
- The status quo in terms of hydrological connection from Erf 1486 to the downstream system must be maintained / should not be impacted because of the proposed development.
- If possible, conduct construction activities of dwellings, associated stormwater infrastructure and any rehabilitation activities during summer months (November to March).
- Ensure that effective stormwater management measures are implemented during construction. Stormwater management must ensure that no runoff, which will impair the water quality and lead to increased sedimentation, may enter the downstream wetland area. Additionally, clean SW which does enter the downstream wetland system should do so in a manner that ensures no erosion occurs, specifically during storm events, such as through vegetated swales.
- Appropriately designed raft foundations for residential dwellings may significantly reduce the impact on subsurface flow and therefore reduce this impact / risk.
- Rainwater harvesting schemes may reduce runoff intensity and thereby mitigate the impact of catchment hardening.
- The alien invasive vegetation present within the wetland area must be removed and replanted with indigenous wetland vegetation.
- An Offset, Rehabilitation and Management Plan must be drafted by a suitably qualified specialist.

Impact 4: Water Quality Impairment

- Designate the wetland area as a No Go for construction activities (for both the residential development and the replacement / upgrade of the sewer pipeline).
- The site manager / ECO must check the No Go area for pollution/spills, erosion damage and sedimentation weekly and after every heavy rainfall event. Should pollution, erosion or sedimentation be noted, immediate corrective measures must be undertaken.
- Fuel, chemicals, and other hazardous substances should preferably be stored offsite, or as far away as possible from the no-go area. These substances must be stored in suitable secure weather-proof containers with impermeable and bunded floors to limit pilferage, spillage into the environment, flooding, or storm damage.
- Inspect all storage facilities, vehicles, and machinery daily for the early detection of deterioration or leaks and strictly prohibit the use of any vehicles or machinery from which leakage has been detected.
- Mixing and transferring of chemicals or hazardous substances must take place outside of the No Go area, and must take place on drip trays, shutter boards or other impermeable surfaces.
- Drip trays must be utilised at all fuel dispensing areas; and during the maintenance of existing sewer flow as possible.
- Vehicles and machinery should preferably be cleaned off site. Should cleaning be required on site it must only take place within designated areas outside of the No Go area and should only occur on bunded areas with a water/oil/grease separator.
- Dispose of used oils, wash water from cement and other pollutants at an appropriate licensed landfill site.
- Avoid the use of infill material or construction material with pollution / leaching potential. Where possible, in situ earthen materials must be used during construction to reduce the risk of leachate from imported materials contaminating the wetland area.
- Concrete should preferably be imported as “ready-mix” concrete from a local supplier. Should onsite concrete mixing be required it must not be done on exposed soils. Concrete must be mixed on an impermeable surface in an area of low environmental sensitivity identified by the ECO outside of the no-go area. Surplus or waste concrete must be sent back to the supplier who will dispose of it.
- Construct temporary bunds around areas where cement is to be cast in situ.
- Dispose of concrete and cement-related mortars in an environmental sensitive manner (can be toxic to aquatic life). Disposal of any of these waste materials into the No Go area is strictly prohibited.
- Washout must not be discharged into the no-go area. A washout area should be designated, and wash water should be treated on-site.
- Clean up any spillages immediately with the use of a chemical spill kit and dispose of contaminated material at an appropriately registered facility.
- Provide portable toilets where work is being undertaken (1 toilet per 10 workers). These toilets must be located within an area designated by the ECO outside of the no-go area and should preferably be located on level ground. Portable toilets must be regularly serviced and maintained.
- Provide an adequate number of bins on site and encourage construction personnel to dispose of their waste responsibly.
- Waste generated by construction personnel must be removed from the site and disposed of at a registered waste disposal facility on a weekly basis.

Post-construction phase

Impact 5: Disturbance of Wetland Habitat

- Prohibit littering and dumping within the wetland area. Clear and remove any rubble or litter that may have been accidentally deposited into the wetland and dispose of at an appropriate registered facility. Monitoring of litter/dumping within the wetland must be managed by a Homeowners Association (HoA).

- In line with the NEMBA, all AIPS listed under the amended AIPS Lists (DEFF: GN1003, 2020) must either be removed or controlled on land under the management of the proponent.
- Vegetation which needs to be re-planted (if applicable) within each northern Erf should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings).

Impact 6: Altered flow

- Vegetation which needs to be re-planted (if applicable) within each northern Erf (Figure 7-1) should be planted with indigenous vegetation, which would be considered an adequate buffer during operational phase considering the nature of development (single residential dwellings).
- Runoff from the proposed development must not increase from the pre-development to the post-development scenario.
- The status quo in terms of hydrological connection from Erf 1486 to the downstream system must be maintained / should not be impacted because of the proposed development.
- Discharge stormwater from rooftops into rain harvesting tanks. This will limit the volumes of stormwater runoff that will reach the wetland area. Where possible, water collected in rain harvesting tanks can be utilized for flushing of toilets, washing etc.
- Stormwater runoff should preferably be discharged as diffuse flow into well vegetated areas outside of the wetland.
- Energy dissipaters / erosion protection measures (such as lining with stones, grass, reno-mattresses, or gabions) must be constructed where stormwater is released to reduce the runoff velocity and therefore erosion.
- Sheet runoff from hardened surfaces must be intercepted and the treatment and infiltration of runoff must be promoted.
- Sediment traps should be incorporated into stormwater drains / swales upstream of any discharge points.
- Monitor the wetland area for erosion and sedimentation after heavy rainfall events. Any erosion noted must be immediately addressed. Rehabilitation measures may include the removal of accumulated sediment by hand, filling of erosion gullies and rills, the stabilisation of gullies with silt fences, riprap, and the revegetation of stabilised areas.
- Stormwater systems will require ongoing maintenance. Any build-up of silt or debris within stormwater drains or swales will need to be cleared to ensure the continued functioning of the systems.
- Any damage to stormwater infrastructure, and any flaws identified in the functionality of stormwater infrastructure, must be rectified immediately.
- Appropriately designed raft foundations for residential dwellings may significantly reduce the impact on subsurface flow and therefore reduce risk.
- Rainwater harvesting schemes may reduce runoff intensity and thereby mitigate the impact of catchment hardening.

Impact 7: Water quality impairment

- Design a SWMP which will allow for the infiltration and treatment of stormwater. All stormwaters must receive basic filtering and treatment prior to its release – Complete, See **Appendix F7**.
- Incorporate measures into the stormwater design to trap solid waste, debris and sediment carried by stormwater. Measures may include the use of curb inlet drain grates and debris baskets/bags.
- Stormwater generated from areas with a higher risk of contamination such as parking areas and roads (as applicable) must receive basic filtering and treatment prior to its release into surrounding areas.

- Stormwater systems must be monitored and maintained into perpetuity and collections of debris and solid waste removed from grates and baskets. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles (likely HoA).
- Operational phase mitigation implemented during the design/construction phase:
 - Construct sewage pipelines in accordance with the relevant SANS / SABS specifications.
 - Design the pipelines to accommodate the operating and surge pressures.
 - Provide surge protection e.g. air valves.
 - Allow for scour valves along pipelines to ensure sewage pipelines can be emptied in a controlled manner if required.
 - Allow for surcharge containment and emergency storage of 2 hours of peak flow at manholes located within areas upslope of the wetland. Containment/emergency storage may include a concrete box or earthen bund surrounding the manholes. The backup storage capacity of manholes may also be improved by raising the manholes by one meter.
- The sewage system must be monitored and maintained into perpetuity. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles.
- The wetland area must be regularly inspected for waste. Any waste or litter noted must be immediately removed and disposed of at a registered waste disposal facility. The developer must confirm who will be responsible for this monitoring of the wetland area (HoA).

Terrestrial Animal Site Sensitivity Verification Report and Species Specialist Assessment Report

Outcome:

Provision of private open space to facilitate a functional corridor for terrestrial fauna. The objective is to maintain functional ecological connectivity within the Ecological Support Area (ESA2) corridor, which links the Hoek van der Berg Private Nature Reserve to the Vermont Salt Pan.

Recommended mitigation measures

The following animal impact related mitigation measures are recommended for this development.

- During the construction phase the construction area should be clearly demarcated and blocked off from the 'private open space' area to avoid damage and pollution.
- Pre and post construction site preparation should include rehabilitation of the 'private open space' by removing current building rubble and litter from this area.
- Long term maintenance of ecological integrity of the 'private open space' is critical. Therefore, measures should be put in place for constant removal of alien vegetation, cleanup of litter and prevention of illegal dumping. Clear legal responsibility for the maintenance of the space should be entrenched to be the responsibility of the homeowners association.
- The fence traversing the ecological corridor should always be permeable to allow for movement of small sized animals e.g. small antelope, genets, mongoose between the nature reserve and wetland system.
- Search and Rescue of chameleons and other slow-moving animals is feasible due to the presence of the adjacent nature reserve where they can be released. A search and rescue effort should be implemented before and during construction where animals that are found are released in the adjacent nature reserve. The necessary permission and permits should be attained before this is done. Search and Rescue to be done in collaboration with Whale Coast Conservation (Sheraine van Wyk).
- Pets (especially domestic cats) should not be allowed to free-roam the 'private open space'.

Stormwater Management Plan


Objectives

- Control of Stormwater Quantity and Rate of Runoff
- Improve Quality rate of Runoff.
- Control of Erosion and Litter

To achieve the above objectives, stormwater quantity and rate of runoff, the following Low Impact Development (LID) is proposed:

- Permeable Paving for a section of the road for the section south of the wetland (refer to **Table 9** of the Stormwater management plan for criteria).
- Enhanced swale for the section North of the wetland area (refer to **Table 10** of the Stormwater management plan for criteria).
- All the outlet structures into the wetland area should be provided with erosion and litter prevention measures.

Recommended mitigation measures



- It is proposed that the stormwater runoff through the above 2 x 600mm diameter pipe culvert be controlled by the provision of a channel or lined channel through Erf 1486, Vermont at the following position (indicated with red arrow above):
- The size of the pipe system or lined channel system is proposed to be as follows:
 - 2 x 900mm dia. Pipes
- That the proposed development be protected from flooding by ensuring that the properties are above at least 1.0m from the wetland area.

Mitigation measures recommended by the Freshwater specialist in addition to Stormwater Management Plan

- Discharge stormwater from rooftops into rain harvesting tanks. This will limit the volumes of stormwater runoff that will reach the wetland. Where possible, water collected in rain harvesting tanks can be utilised for flushing of toilets, washing etc.

- Vegetated swales must be utilised rather than concrete drains or underground stormwater pipes in order to encourage infiltration, particularly next to roadways.
- Energy dissipaters / erosion protection measures (such as lining with stones, grass, reno-mattresses, or gabions) must be constructed where stormwater is released in order to reduce the runoff velocity and therefore erosion.
- Sheet runoff from hardened surfaces must be intercepted and the treatment and infiltration of runoff must be promoted.
- Sediment traps should be incorporated into stormwater drains / swales upstream of all discharge points into the wetland.
- All stormwater draining into the wetland must receive basic filtering and treatment prior to its release.
- Incorporate measures into the stormwater design to trap solid waste, debris and sediment carried by stormwater. Measures may include the use of curb inlet drain grates and debris baskets/bags.
- Stormwater generated from areas with a higher risk of contamination such as parking areas and roads must receive basic filtering and treatment prior to its release into surrounding areas. Treatment methods may include sand filter traps and oil-water separators which will require maintenance.
- The extent of hardened surfaces must be minimised. E.g. where required permeable paving must be used.
- Homeowners must be encouraged to landscape their gardens with the use of indigenous species to decrease the area of hardened surface and increase infiltration.
- Homeowners should store any potential pollutants in such a way that pollution will not occur to the wetland (such as any fuel, etc.). Potential pollutants should be stored in an adequately bunded area.
- The use of herbicides, pesticides and any other poisons within private gardens must be strictly prohibited. The home owner's association must be responsible for ensuring that residents are compliant with this.
- Backwashing of swimming pools directly into the wetland must be strictly prohibited. Backwash water can be collected in settling tanks where dirt and debris settle to the bottom. The cleaner water can then be reused for non-potable purposes or even filtered back into the pool system. Backwash water can be diverted to greywater tanks.
- Monitor the proposed development and adjacent wetland for erosion and sedimentation after heavy rainfall events. Any erosion noted must be immediately addressed. Rehabilitation measures may include the removal of accumulated sediment by hand, filling of erosion gullies and rills, the stabilisation of gullies with silt fences, riprap, and the revegetation of stabilised areas.
- Stormwater systems will require ongoing maintenance. Any build-up of silt or debris within stormwater drains or swales will need to be cleared to ensure the continued functioning of the systems.
- Any damage to stormwater infrastructure, and any flaws identified in the functionality of stormwater infrastructure, must be rectified immediately.
- Stormwater systems must be monitored and maintained into perpetuity and collections of debris and solid waste removed from grates and baskets. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles.
- The stormwater system must be designed by a suitably qualified engineer with input from an aquatic specialist.

Wetland Offset, Rehabilitation, and Management Plan

The development, comprising single residential erven, will result in the loss of 0.024 ha (3%) of the wetland due to eastern and southern boundary access roads, despite efforts to minimize encroachment through layout adjustments.

Outcomes

- Offset of Wetland Loss to Achieve No Net Loss of Function and Habitat.
- Restoration of Wetland Habitat Integrity through Rehabilitation

- Enhancement of Wetland Functionality through Stormwater Management
- Long-Term Maintenance of Wetland Offset Gains

Objectives

- The objective is to compensate for the unavoidable loss of 0.024 ha of UVB wetland (0.0139 HE function, 0.1323 HE habitat) through onsite rehabilitation, achieving a net gain in wetland value as per Macfarlane et al. (2016) guidelines.
- Restore the ecological integrity of the 0.9361-ha offset wetland by removing disturbances and re-establishing indigenous vegetation, enhancing habitat quality from a largely modified (Category D) to a moderately modified (upper Category C) state.
- Protect the hydrology and water quality of the offset wetland by mitigating increased runoff and contamination risks from the development's hardened surfaces
- Ensure the rehabilitated wetland's PES (upper Category C) and biodiversity gains are sustained in perpetuity through active management and monitoring.

Recommended mitigation measures

- Discharge stormwater from rooftops into rain harvesting tanks. This will limit the volumes of stormwater runoff that will reach the wetland. Where possible, water collected in rain harvesting tanks can be utilised for flushing of toilets, washing etc.
- Vegetated swales must be utilised rather than concrete drains or underground stormwater pipes in order to encourage infiltration, particularly next to roadways.
- Energy dissipaters / erosion protection measures (such as lining with stones, grass, reno-mattresses, or gabions) must be constructed where stormwater is released in order to reduce the runoff velocity and therefore erosion.
- Sheet runoff from hardened surfaces must be intercepted and the treatment and infiltration of runoff must be promoted.
- Sediment traps should be incorporated into stormwater drains / swales upstream of all discharge points into the wetland.
- All stormwater draining into the wetland must receive basic filtering and treatment prior to its release.
- Incorporate measures into the stormwater design to trap solid waste, debris and sediment carried by stormwater. Measures may include the use of curb inlet drain grates and debris baskets/bags.
- Stormwater generated from areas with a higher risk of contamination such as parking areas and roads must receive basic filtering and treatment prior to its release into surrounding areas. Treatment methods may include sand filter traps and oil-water separators which will require maintenance.
- The extent of hardened surfaces must be minimised. E.g. where required permeable paving must be used.
- Homeowners must be encouraged to landscape their gardens with the use of indigenous species to decrease the area of hardened surface and increase infiltration.
- Homeowners should store any potential pollutants in such a way that pollution will not occur to the wetland (such as any fuel, etc.). Potential pollutants should be stored in an adequately bunded area.
- The use of herbicides, pesticides and any other poisons within private gardens must be strictly prohibited. The home owner's association must be responsible for ensuring that residents are compliant with this.
- Backwashing of swimming pools directly into the wetland must be strictly prohibited. Backwash water can be collected in settling tanks where dirt and debris settle to the bottom. The cleaner water can then be reused for non-potable purposes or even filtered back into the pool system. Backwash water can be diverted to greywater tanks.
- Monitor the proposed development and adjacent wetland for erosion and sedimentation after heavy rainfall events. Any erosion noted must be immediately addressed. Rehabilitation measures may include the removal of

accumulated sediment by hand, filling of erosion gullies and rills, the stabilisation of gullies with silt fences, riprap, and the revegetation of stabilised areas.

- Stormwater systems will require ongoing maintenance. Any build-up of silt or debris within stormwater drains or swales will need to be cleared to ensure the continued functioning of the systems.
- Any damage to stormwater infrastructure, and any flaws identified in the functionality of stormwater infrastructure, must be rectified immediately.
- Stormwater systems must be monitored and maintained into perpetuity and collections of debris and solid waste removed from grates and baskets. The developer must confirm who will be responsible for this monitoring and maintenance as well as their roles.
- The stormwater system must be designed by a suitably qualified engineer with input from an aquatic specialist.

The following recommendations are made for removal of Alien Invasive Species:

Hand Pulling

Use: Seedlings with a stem diameter of <5cm

Hand pulling should be implemented as the preferred clearing technique as far as possible. When implemented correctly, this method is extremely effective, yet its application is limited to seedlings. Thus, regular monitoring and follow-up treatments are important to ensure successful and economical eradication using this technique. The procedure to be implemented is as follows:

- Wearing gloves, grip the plant firmly at the base of the stem and pull hard to remove the entire plant, including the rootstocks.
- If the roots of the plant break off during removal, use a spade to dig them out.
- Shake the plant to remove excess soils and dispose of the plant material at an appropriate waste disposal site.

Tree Popping

Use: Seedlings/Saplings with a stem diameter of approximately 5 cm.

This technique is used for medium tree specimens and involves the use of an implement referred to as a “Tree-Popper”. This tool consists of a base plate and a lever that are joined to form a small pair of jaws (Figure A1). The tree is placed in the jaws of the tool, and the lever is used to pull the entire tree, including the roots, out. This tool is extremely useful for trees that are too large to be effectively removed by hand pulling yet are not yet large enough to require felling. The method to be used is similar as outlined for hand pulling, however the Tree-Popper is used instead of pulling.

Felling

Use: Trees with a stem diameter of >5 cm

Once the stems of trees reach a diameter of greater than 5 cm felling will need to be implemented to remove the individual. Felling can be undertaken using chain saws and bow saws. It is important that trees are cut with a neat straight cut to reduce the chance of resprouting and improve the effectiveness of stump herbicide treatment. Trees must be cut down as close to the ground as possible (between 5cm and 30cm above the ground). Felling must be undertaken by appropriately trained individuals that possess and make use of the required Personal Protective Equipment (PPE) for the task at hand.

Herbicide Stump Treatment

Use: Resprouting species that have undergone felling treatment

Port Jackson requires the use of poison, whilst the Rooikrans usually dies when cut below the lowest branch. To prevent resprouting of Port Jackson, a herbicide treatment needs to be applied post felling. Once the tree has been cut down to

create a smooth surface that exposes the outer rings of the stem where the trunk grows (the cambium) a 3% Triclopyr herbicide solution must be applied to the freshly cut surface. All side branches should also be removed and treated with herbicide. The herbicide treatment should be applied as soon as possible after felling (preferably within 3 minutes) to ensure effective treatment. Where trees with a diameter of greater than 10cm are felled, only the outer rings need to be treated with herbicide. Due to the potentially hazardous nature of herbicides, the precautions outlined in the Foliar Treatment section above should also be applied during herbicide stump treatment.

Herbicides can kill indigenous plant species, and some are toxic to people and animals. It is therefore important to prevent environmental contamination with herbicide. The following measures are therefore recommended:

- Do not apply herbicide while it is raining and take care to prevent it from spilling, spraying, or spreading onto the ground or onto non-target species.
- Rain may wash herbicide into watercourses and spread it downstream, or across banks that need to be revegetated.
- Never wash herbicide equipment or dispose of waste spray mixture in or near watercourses where contamination can occur.

The introduction of the acacia gall rust fungus (*Uromycladium tepperianum*) can be introduced onsite if the Port Jackson trees persist to be a problem. Consultation with a Botanist and/or Entomologist prior to introduction is recommended.

Additional considerations include:

- Conditions of EMP to be adhered to
- Appropriately designed raft foundations may significantly reduce the impact on subsurface flow and therefore reduce risk
- Rainwater harvesting schemes that may reduce runoff intensity and thereby mitigate the impact of catchment hardening
- Stormwater polishing infrastructure such as artificial wetlands that may mitigate water quality impacts.
- Search and Rescue for faunal and floral species of conservation concern (SOCC) as indicated in the Terrestrial / botanical report, this should be implemented prior to groundbreaking.

The following recommendation are made for Revegetation

Planting

To ensure adequate rehabilitation, planting must be done at a reasonable density of approximately 4 plants per square meter. Vegetation that has recently been planted is generally susceptible to being washed away until it has become well established. Transplanting of whole plants with well-established roots in a growing medium is one of the most reliable revegetation techniques. While several species suggested for revegetation can be grown from seeds and propagules, it is recommended that the majority of revegetation activities are focused on the introduction of whole plants, particularly into areas that are vulnerable to erosion.

The recommended general planting procedures are as follows:

- Use a spade to dig a square hole that is 1.5 times the depth and 2 times the width of the bag containing the plant.
- Remove the plant from its container and carefully loosen the soil by hand, being careful to not damage the roots and maintain as much of the soil as possible.
- Place the plant and associated soil in the hole.
- Replace the soil originally removed and ensure that it forms a slight depression (1-3 cm below the level of the surrounding soil) with the plant in the centre of the depression.
- Compress the soil firmly by hand.

- For plants placed in the temporary zone watering should be done approximately once every three days for the first six months after planting unless rain has fallen within the preceding 24 hours. Rainfall during the winter months (June – August for the proposed site) can substantially reduce the required watering effort. However, given that revegetation within the onsite offset wetland needs to be undertaken as rapidly as possible planting should be initiated as soon as the infill has been removed from the wetland area, and the remnant wetland has been appropriately shaped along with sufficient watering efforts.
- The best time for planting is autumn (March-May). This allows for the plants to establish roots before being subjected to heavy rains. Planting in autumn therefore reduces the risk of erosion / sedimentation, having plants wash away and will reduce watering requirements.

2.2. Provide a description of any aspects that were conditional to the findings of the assessment either by the EAP or specialist that must be included as conditions of the authorisation.

The following aspects were identified as conditional to the assessment’s findings and must be enforced as conditions of authorisation:

Aspects that were conditional

1. Implementation of the Wetland Offset, Rehabilitation, and Management Plan

- The specialists conclude that the development is acceptable only if the full Wetland Offset, Rehabilitation, and Management Plan is implemented as detailed in the report.
- The rehabilitation of the remaining ~0.9361-ha wetland to a PES of upper Category C (minimum 79% PES score) from its current Category D state is a cornerstone of the offset strategy. The specialists assert that this improvement is necessary to achieve the required functional and habitat gains, and it must be maintained in perpetuity.
- The specialists stipulate that the 0.9361-ha offset wetland must be formally protected to ensure long-term ecological gains, recommending a conservation servitude as a title deed restriction to prevent future development (Van Zyl & Morton, 2024). As this is critical to securing the offset’s permanence and meeting DWS’s ‘no net loss’ policy.
- The specialists highlight that appropriate stormwater management is essential to prevent hydrological and water quality impacts on the offset wetland from increased runoff due to catchment hardening.
- The removal of AIS (e.g., *Cenchrus clandestinum*, *Cortaderia selloana*, *Acacia saligna*) from the offset wetland and sustained control are prerequisites for achieving the target PES and preventing ecological degradation.
- The specialists condition the offset’s success on revegetating the offset wetland with indigenous species (e.g., *Bolboschoenus maritimus*, *Cyperus textilis*) at 4 plants/m², achieving 80% vegetation cover within 8-12 months to restore habitat and function.

Conditions of Authorisation

- The developer must implement the Wetland Offset, Rehabilitation, and Management Plan) in its entirety as a condition of approval. Any deviation from the plan’s specifications (e.g., rehabilitation methods, offset targets) requires prior approval from DWS and the competent environmental authority, supported by a specialist motivation demonstrating no net loss of wetland value.
- The developer must rehabilitate the offset wetland to achieve a PES of upper Category C within 12 months of completing revegetation, verified by a SACNASP-registered freshwater specialist.
- A suitably qualified restoration ecologist with a proven track record in wetland restoration (including but not limited to the revegetation component) should be appointed to lead implementation.

- All stormwater management measures outlined in the Stormwater Management Plan report must be incorporated into the development's design by a qualified engineer, with input from an aquatic specialist, and implemented during construction. The Homeowners Association (HoA) must maintain these systems in perpetuity, with quarterly inspections and immediate repairs of any damage.
- All AIS must be removed from the 0.9361 -ha offset area prior to revegetation, using methods specified in Section 8.4 of the Wetland Offset, Rehabilitation and Management Plan (e.g., manual pulling, herbicide application), under supervision of a freshwater specialist. Post-rehabilitation, the HoA must conduct quarterly AIS clearing for 5-10 years.
- Strict implementation of the no development zones (seasonal wetland area) which fall on Erven 1-8 must be enforced. These no development areas will form part of the conservation servitude and the allowable development area on these erven must be clearly indicated to the purchaser as well as clearly outlined in the homeowners association. These areas that should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way. Landowners and the HoA must be made aware of these constraints both prior to and after purchase. Alien invasive plant species should be removed from these areas on an annual basis, as part of the management actions required for the adjacent Private Open Space. Refer to Regulated Areas Management Plan.
- The no development zones (entire seasonal and permanent wetland area must be fenced off during construction and marked as no go areas for all unauthorised staff.
- A Homeowners Association (HoA) must be established prior to the transfer of any residential erven within the development.
- The HoA shall be legally constituted and shall include, within its constitution and governance rules, binding provisions for the protection, rehabilitation, management, and monitoring of the wetland, ecological corridor, and open space areas identified in the approved Site Development Plan (Alternative 4).
- The areas identified as No-Go Areas, including the permanent, seasonal, and temporary wetland areas and associated ecological corridor, shall be:
 - clearly demarcated on the final Site Development Plan;
 - protected from any development, infrastructure installation, infilling, excavation, vegetation clearing (excluding alien clearing), gardening expansion, or disturbance; and
 - managed as natural open space in perpetuity.
- A No-Go/ Regulated Area Management Plan, forming part of the approved Environmental Management Programme (EMPr), must be incorporated into the HoA constitution and shall be binding on all current and future property owners.
- The environmental management obligations described above shall be binding on successors in title and shall be reflected in:
 - the HoA constitution,
 - sale agreements, and
 - any other legally enforceable governance instruments of the development
- Proof of the establishment of the HoA, including the approved constitution reflecting the environmental management obligations, shall be submitted to the Competent Authority prior to commencement of construction.
- It is recommended that Cape Nature or an Aquatic Ecologist be consulted during the design of the residential dwellings and Town Housing unit, and an Environmental Control Officer (ECO) should be appointed during the construction of the Town Housing development in the south of the erf.

2.3.	Provide a reasoned opinion as to whether the proposed activity or development should or should not be authorised, and if the opinion is that it should be authorised, any conditions that should be included in the authorisation.
------	--

Alternative four (4) should be authorized, provided that the required conditions are enforced and audited for compliance on a regular basis. The mitigation hierarchy has been appropriately applied, with Alternative 4 emerging as the preferred

option due to its ability to avoid sensitive features, notably the seasonal and permanent wetland areas on site, minimize environmental impacts, and align with surrounding land uses, municipal policies, and provincial guidelines. The rehabilitation and conservation of more than half of the property allows for the ecological corridor and wetland area to be conserved and protected in perpetuity. This long-term protection aligns with the area wide vision to reinstate the wetland corridor between the Vermont Salt Pan and the Walker Bay Nature Reserve.

Conditions of Authorisation

- The EMP and Regulated Areas MP, must be strictly implemented (construction, operation, and post-construction). Regular monitoring, reporting and audits will be required to ensure that the conditions are being implemented correctly. It is recommended that ECO visits during the initial phases of construction are conducted bi-weekly and reduced once the development areas are adequately defined. Audits should be done quarterly during the first year of construction to ensure compliance.
- All No-Go areas (seasonal and temporary wetland) must be fenced off before vegetation clearance and construction commences and marked as strict No-Go areas.
- The use of raft foundations in houses designs is required to reduce the impact on subsurface flow
- Walling between houses must be limited, particular where they fall within the wetland area. Low impact boundaries such as clear view fencing must be used.
- Individual dwellings must be raised 1m above ground level.
- Whale Coast Conservation must be consulted well in advance of vegetation clearance and the commencement of construction to facilitate flora and fauna search-and-rescue operations. Costs of this process will be for the developer's account. Search and Rescue for possible faunal and floral species of conservation concern (SOCC) as indicated in the Terrestrial Biodiversity Impact Assessment (2023) and Terrestrial Animal Site Sensitivity Verification Report and Species Specialist Assessment Report, should be implemented prior to construction. Nighttime Search and Rescue for faunal species is mandatory prior to ground works. Sheraine van Wyk from Whale Coast Conservation Chameleon project must be contacted to facilitate the Search and Rescue (sheraine.wcc@gmail.com / 083 484 0202).
- The inclusion of rainwater tanks in house designs is mandatory to capture excess runoff.
- The Stormwater Management Plan must be fully implemented to mitigate the risk associated with stormwater runoff through construction of Permeable Paving System and vegetated Swale System. These systems shall be regularly inspected and maintained as required to ensure effective stormwater attenuation, infiltration, and quality control.
- The Wetland Offset, Rehabilitation, and Management Plan must be fully implemented, with clear timelines and accountability measures. This includes ongoing monitoring of the wetland's health and the success of offset measures, with adaptive management measures in place if targets are not met.
- A suitably qualified restoration ecologist with a proven track record in wetland restoration (including but not limited to the revegetation component) should be appointed to lead implementation.
- Securing of the retained wetland area and associated open space through a council-approved co-management agreement between the Overstrand Municipality and the Homeowners' Association (HOA), providing the necessary long-term institutional and legal standing for the offset area's protection, management and maintenance beyond the development's construction phase.
- Homeowners must be encouraged to landscape their gardens with the use of indigenous species indicated in **Table 8-1** of the Wetland Offset, Rehabilitation and Management Plan to decrease the area of hardened surface and increase infiltration.
- The establishment of a Homeowners Association will be required, with a mandate to enforce environmental conditions (e.g., maintenance of rainwater tanks, stormwater infrastructure, and alien clearing) post-construction as well as the management of the No Development Zones on private erven. See **Appendix G1** and **G2** for the EMP and No-go MP.

- The use of herbicides, pesticides and any other poisons within private gardens must be strictly prohibited. The homeowner's association must be responsible for ensuring that residents are compliant with this.
- All alien invasive vegetation should be removed from within the natural portions of the project area, prior to any authorised development. Removal of the alien vegetation must be undertaken by a trained and licensed alien vegetation removal team and must be undertaken using methodology outlined in the Best Practise Guidelines (see Martens et al 2021).
- A Homeowners Association (HoA) must be established prior to the transfer of any residential erven within the development.
- The HoA shall be legally constituted and shall include, within its constitution and governance rules, binding provisions for the protection, rehabilitation, management, and monitoring of the wetland, ecological corridor, and open space areas identified in the approved Site Development Plan (Alternative 4).
- The areas identified as No-Go Areas, including the permanent, seasonal, and temporary wetland areas and associated ecological corridor, shall be:
 - clearly demarcated on the final Site Development Plan;
 - protected from any development, infrastructure installation, infilling, excavation, vegetation clearing (excluding alien clearing), gardening expansion, or disturbance; and
 - managed as natural open space in perpetuity.
- A No-Go/ Regulated Area Management Plan, forming part of the approved Environmental Management Programme (EMPr), must be incorporated into the HoA constitution and shall be binding on all current and future property owners.
- The environmental management obligations described above shall be binding on successors in title and shall be reflected in:
 - the HoA constitution,
 - sale agreements, and
 - any other legally enforceable governance instruments of the development
- Proof of the establishment of the HoA, including the approved constitution reflecting the environmental management obligations, shall be submitted to the Competent Authority prior to commencement of construction.
- Areas outside the designated road and residential erf boundaries should not be altered, developed, gardened, covered, excavated, drained, infilled or disturbed in any way. Landowners and the HoA must be made aware of these constraints both prior to and after purchase.
- The retained wetland area and associated open space shall be secured through a council-approved co-management agreement between the Overstrand Municipality and the Homeowners' Association (HOA), providing the necessary long-term institutional and legal standing for the offset area's protection, management and maintenance beyond the development's construction phase.

2.4.	Provide a description of any assumptions, uncertainties and gaps in knowledge that relate to the assessment and mitigation measures proposed.
------	---

Wetland delineations

The site layout, offset calculation, and impact assessment presented in this report are based on the wetland delineation undertaken by Delta Ecology (2023, updated 2025/2026), independently peer-reviewed by EnviroSwift (2025), which confirmed no material discrepancy in overall extent and configuration, notwithstanding minor differences in boundary positioning between the two. It is assumed that this delineation, prepared in accordance with the DWAF/DWA/DWS field-based methodology and based on wetland indicators (terrain position, soil form, soil wetness and vegetation) observed at the time of assessment, accurately reflects the wetland boundary applicable to this application.

A separate, privately commissioned delineation by Freshwater Consulting (2026), indicating substantially greater wetland coverage, has been raised through the public participation process but has not been formally submitted as part of the specialist record informing this Basic Assessment. This represents an unresolved discrepancy between specialist opinions rather than a confirmed gap in the applicant's own specialist work; it is addressed further in the Opinion and Recommendation section of this report and in the accompanying motivation from Delta Ecology (6 September 2026).

Future hydrological and wetland-extent change

It is acknowledged that there is a genuine gap in knowledge regarding how the on-site wetland's extent, ecological state, and hydrological function may change over time in response to catchment-level factors, including the ongoing removal of alien invasive vegetation on the adjacent Whale Coast Nature Reserve and the effects of climate change on rainfall patterns. The specialist assessments informing this application do not include a predictive hydrological model of these future changes, as this falls outside the scope of the legislated wetland delineation methodology, which requires delineation on the basis of on-site conditions and indicators present at the time of assessment. This limitation has been transparently recorded in the Limitations sections of the relevant specialist reports, rather than omitted. Ongoing monitoring, rather than a speculative extension of the current delineated boundary, is proposed as the appropriate response to this uncertainty, and is provided for through the WORMP and the five-yearly independent WET-Health audits.

Wetland offset calculation

The wetland offset calculation (Macfarlane et al., 2016 methodology) is based on the current delineation and the current Present Ecological State (PES) of the wetland (Category D, largely modified).

Long-term governance and institutional mechanisms

The long-term securing of the retained wetland and offset area relies on an institutional mechanism, a council-approved co-management agreement between the Overstrand Municipality and the Homeowners Association, as recommended by Cape Nature. At the time of reporting, the co-management agreement has not yet been formally approved by Council or executed between the parties; this represents an outstanding procedural matter rather than a technical uncertainty, and is addressed through the relevant condition of authorisation requiring its finalisation. Further engagement between BOCMA, Cape Nature, and the Overstrand Municipality will be undertaken in due course to formalise this agreement, including securing the requisite Council approval and confirming the respective roles and responsibilities of the Municipality and the Homeowners Association in the long-term management of the offset site. Prior to adopting this model, third-party institutional stewardship options (Nature Connect and Whale Coast Conservation) were investigated and found not to be feasible for a site of this scale, which is noted as context for why the HoA/Municipality model has been proposed rather than an external conservation body.

2.5.	The period for which the EA is required, the date the activity will be concluded and when the post construction monitoring requirements should be finalised.
------	--

The holder must commence the listed activities on site within a period of five (5) years from the date of issue of this Environmental Authorization.

The development must be concluded within ten (10) years from the date of commencement of the first listed activity.

3. Water

Since the Western Cape is a water scarce area explain what measures will be implemented to avoid the use of potable water during the development and operational phase and what measures will be implemented to reduce your water demand, save water and measures to reuse or recycle water.

The proposal will connect to the municipal network reticulation system which is already existing. Alternative 4 allows for rehabilitation and long-term preservation of the wetland on site. Design measures for the reduction of water demand on site should be considered at the design stage. Water collection and reuse should also be included in the design as far as possible.

4. Waste

Explain what measures have been taken to reduce, reuse or recycle waste.

On-site separation, reduction and reuse should be encouraged in the construction and operational phases, with the aim of reducing waste sent to landfill. The waste management hierarchy avoidance, reduction, reuse, recycling, and disposal as a last resort has been applied in identifying the measures set out below.

Construction Phase

- Where practicable, clean builders' rubble (e.g. broken brick, concrete) should be crushed and reused on site for backfilling, bedding, or hardstanding, rather than being removed to landfill.
- Excess or unused building materials should be returned to suppliers where possible, or made available for reuse on other projects, rather than being disposed of as waste.
- All waste not reused or recycled on site must be removed by a licensed waste contractor and disposed of at a licensed landfill facility, with waste disposal records/certificates retained for audit purposes.
- No burning or dumping of construction waste is permitted on site.
- The ECO should monitor waste separation and disposal practices during routine site inspections, with corrective action taken where non-compliance is identified.

Operational Phase

- Each residential erf should be provided with adequate space for the separation of household waste into general waste and recyclables (e.g. paper, glass, plastic, metal), consistent with the Overstrand Municipality's domestic waste collection and recycling services.
- Residents should be encouraged, through the Home Owners' Association (HOA) rules or equivalent mechanism, to participate in kerbside recycling collection where offered by the municipality, and to make use of local recycling drop-off facilities where available.
- Garden/green waste generated through landscaping and maintenance of private open space (including any vegetation management associated with the wetland/open space areas) should be chipped or composted on site where practicable, rather than disposed of as general waste.
- Communal waste storage areas (if applicable to shared/private open space maintenance) should be designed to prevent litter, windblown waste, and potential contamination of the adjacent wetland system.

5. Energy Efficiency

8.1. Explain what design measures have been taken to ensure that the development proposal will be energy efficient.

Alternative energy:

- Installation of gas geysers for hot water heating is encouraged.
- Solar geysers are permitted with a max of 2 panels per erf.
- The solar panels for hot water heating must be indicated on the drawings.
- The water reservoir may not be mounted on the roof surface and must be concealed within the roof space.
- The position and extent of any solar panels for alternative energy supply must be indicated on the drawings and approved by the HOA and were deemed necessary by any adjoining effected property owner.
- Distinctions must be made between solar panels for hot water supply and alternative energy supply.

SECTION K: DECLARATIONS

DECLARATION OF THE APPLICANT

Note: Duplicate this section where there is more than one Applicant.

I **CRAIG SAUNDERS OF ELEPHANT VENTURES** AFRICA CC ID number **1999/013536/23** in my personal capacity or duly authorised thereto hereby declare/affirm that all the information submitted or to be submitted as part of this application form is true and correct, and that:

- I am fully aware of my responsibilities in terms of the National Environmental Management Act, 1998 (Act No. 107 of 1998) ("NEMA"), the Environmental Impact Assessment ("EIA") Regulations, and any relevant Specific Environmental Management Act and that failure to comply with these requirements may constitute an offence in terms of relevant environmental legislation;
- I am aware of my general duty of care in terms of Section 28 of the NEMA;
- I am aware that it is an offence in terms of Section 24F of the NEMA should I commence with a listed activity prior to obtaining an Environmental Authorisation;
- I appointed the Environmental Assessment Practitioner ("EAP") (if not exempted from this requirement) which:
 - meets all the requirements in terms of Regulation 13 of the NEMA EIA Regulations; or
 - meets all the requirements other than the requirement to be independent in terms of Regulation 13 of the NEMA EIA Regulations, but a review EAP has been appointed who does meet all the requirements of Regulation 13 of the NEMA EIA Regulations;
- I will provide the EAP and any specialist, where applicable, and the Competent Authority with access to all information at my disposal that is relevant to the application;
- I will be responsible for the costs incurred in complying with the NEMA EIA Regulations and other environmental legislation including but not limited to –
 - costs incurred for the appointment of the EAP or any legitimately person contracted by the EAP;
 - costs in respect of any fee prescribed by the Minister or MEC in respect of the NEMA EIA Regulations;
 - Legitimate costs in respect of specialist(s) reviews; and
 - the provision of security to ensure compliance with applicable management and mitigation measures;
- I am responsible for complying with conditions that may be attached to any decision(s) issued by the Competent Authority, hereby indemnify, the government of the Republic, the Competent Authority and all its officers, agents and employees, from any liability arising out of the content of any report, any procedure or any action for which I or the EAP is responsible in terms of the NEMA EIA Regulations and any Specific Environmental Management Act.



Signature of the Applicant:

Date:

07/09/2026

DECLARATION OF THE ENVIRONMENTAL ASSESSMENT PRACTITIONER (“EAP”)

I **MICHELLE NAYLOR** EAPASA Registration number **2019/698** as the appointed EAP hereby declare/affirm the correctness of the:

- Information provided in this BAR and any other documents/reports submitted in support of this BAR;
- The inclusion of comments and inputs from stakeholders and I&APs;
- The inclusion of inputs and recommendations from the specialist reports where relevant; and
- Any information provided by the EAP to interested and affected parties and any responses by the EAP to comments or inputs made by interested and affected parties, and that:
- In terms of the general requirement to be independent:
 - other than fair remuneration for work performed in terms of this application, have no business, financial, personal or other interest in the activity or application and that there are no circumstances that may compromise my objectivity; or
 - am not independent, but another EAP that meets the general requirements set out in Regulation 13 of NEMA EIA Regulations has been appointed to review my work (Note: a declaration by the review EAP must be submitted);
- In terms of the remainder of the general requirements for an EAP, am fully aware of and meet all of the requirements and that failure to comply with any the requirements may result in disqualification;
- I have disclosed, to the Applicant, the specialist (if any), the Competent Authority and registered interested and affected parties, all material information that have or may have the potential to influence the decision of the Competent Authority or the objectivity of any report, plan or document prepared or to be prepared as part of this application;
- I have ensured that information containing all relevant facts in respect of the application was distributed or was made available to registered interested and affected parties and that participation will be facilitated in such a manner that all interested and affected parties were provided with a reasonable opportunity to participate and to provide comments;
- I have ensured that the comments of all interested and affected parties were considered, recorded, responded to and submitted to the Competent Authority in respect of this application;
- I have ensured the inclusion of inputs and recommendations from the specialist reports in respect of the application, where relevant;
- I have kept a register of all interested and affected parties that participated in the public participation process; and
- I am aware that a false declaration is an offence in terms of Regulation 48 of the NEMA EIA Regulations;

MNaylor

08 September 2026

Signature of the EAP:

Date:

LORNAY ENVIRONMENTAL CONSULTING

Name of company (if applicable):

~~DECLARATION OF THE REVIEW EAP~~

I....., EAPASA Registration number as
the appointed Review EAP hereby declare/affirm that:

- ~~I have reviewed all the work produced by the EAP;~~
- ~~I have reviewed the correctness of the information provided as part of this Report;~~
- ~~I meet all of the general requirements of EAPs as set out in Regulation 13 of the NEMA EIA Regulations;~~
- ~~I have disclosed to the applicant, the EAP, the specialist (if any), the review specialist (if any), the Department and I&APs, all material information that has or may have the potential to influence the decision of the Department or the objectivity of any Report, plan or document prepared as part of the application; and~~
- ~~I am aware that a false declaration is an offence in terms of Regulation 48 of the NEMA EIA Regulations.~~

Signature of the EAP: _____

Date: _____


Name of company (if applicable):

DECLARATION OF THE SPECIALIST

Note: Duplicate this section where there is more than one specialist.

I, NA Helme, as the appointed Specialist hereby declare/affirm the correctness of the information provided or to be provided as part of the application, and that:

- In terms of the general requirement to be independent:
 - other than fair remuneration for work performed in terms of this application, have no business, financial, personal or other interest in the development proposal or application and that there are no circumstances that may compromise my objectivity; or
 - am not independent, but another specialist (the "Review Specialist") that meets the general requirements set out in Regulation 13 of the NEMA EIA Regulations has been appointed to review my work (Note: a declaration by the review specialist must be submitted);
- In terms of the remainder of the general requirements for a specialist, have throughout this EIA process met all of the requirements;
- I have disclosed to the applicant, the EAP, the Review EAP (if applicable), the Department and I&APs all material information that has or may have the potential to influence the decision of the Department or the objectivity of any Report, plan or document prepared or to be prepared as part of the application; and
- I am aware that a false declaration is an offence in terms of Regulation 48 of the EIA Regulations.

— 
Signature of the EAP:

20 June 2025
Date:

Nick Helme Botanical Surveys


Name of company (if applicable):

DECLARATION OF THE SPECIALIST

Note: Duplicate this section where there is more than one specialist.

I, Jan A Venter, as the appointed Specialist hereby declare/affirm the correctness of the information provided or to be provided as part of the application, and that:

- In terms of the general requirement to be independent:
 - other than fair remuneration for work performed in terms of this application, have no business, financial, personal or other interest in the development proposal or application and that there are no circumstances that may compromise my objectivity; or
 - am not independent, but another specialist (the "Review Specialist") that meets the general requirements set out in Regulation 13 of the NEMA EIA Regulations has been appointed to review my work (Note: a declaration by the review specialist must be submitted);
- In terms of the remainder of the general requirements for a specialist, have throughout this EIA process met all of the requirements;
- I have disclosed to the applicant, the EAP, the Review EAP (if applicable), the Department and I&APs all material information that has or may have the potential to influence the decision of the Department or the objectivity of any Report, plan or document prepared or to be prepared as part of the application; and
- I am aware that a false declaration is an offence in terms of Regulation 48 of the EIA Regulations.

Signature of the EAP: 

19/06/2025

Date:

Wildlife3 Conservation Decision Support


Name of company (if applicable):

DECLARATION OF THE SPECIALIST

Note: Duplicate this section where there is more than one specialist.

I Kimberley van Zyl, as the appointed Specialist hereby declare/affirm the correctness of the information provided or to be provided as part of the application, and that:

- In terms of the general requirement to be independent:
 - other than fair remuneration for work performed in terms of this application, have no business, financial, personal or other interest in the development proposal or application and that there are no circumstances that may compromise my objectivity; or
 - am not independent, but another specialist (the "Review Specialist") that meets the general requirements set out in Regulation 13 of the NEMA EIA Regulations has been appointed to review my work (Note: a declaration by the review specialist must be submitted);
- In terms of the remainder of the general requirements for a specialist, have throughout this EIA process met all of the requirements;
- I have disclosed to the applicant, the EAP, the Review EAP (if applicable), the Department and I&APs all material information that has or may have the potential to influence the decision of the Department or the objectivity of any Report, plan or document prepared or to be prepared as part of the application; and
- I am aware that a false declaration is an offence in terms of Regulation 48 of the EIA Regulations.


Signature of the EAP:

18 September 2025
Date:

Delta Ecology
Name of company (if applicable):

DECLARATION OF THE REVIEW SPECIALIST

I Nick Steytler....., as the appointed Review Specialist hereby declare/affirm that:

- I have reviewed all the work produced by the Specialist(s):
- I have reviewed the correctness of the specialist information provided as part of this Report;
- I meet all of the general requirements of specialists as set out in Regulation 13 of the NEMA EIA Regulations;
- I have disclosed to the applicant, the EAP, the review EAP (if applicable), the Specialist(s), the Department and I&APs, all material information that has or may have the potential to influence the decision of the Department or the objectivity of any Report, plan or document prepared as part of the application; and
- I am aware that a false declaration is an offence in terms of Regulation 48 of the NEMA EIA Regulations.



29 September 2025

Signature of the EAP:—

Date:

Name of company (if applicable):